

GENERAL SUMMARY

Prepared for:

Project ID:

Scope: **WATER REPELLENTS, CONCRETE & STEEL COATINGS**

Date:



DIVISION NO.	DESCRIPTION	TOTAL DIV. COST
	General Requirments	\$ -
	Coating & Waterproofing	
	1. DAMPPROOFING AS PER (02581, 02600, 07110)	\$ 5,206
	2. WATER REPELLENT (AS PER 07190)	\$ 545,730
	3. ARCHITECTURAL PAINTING (AS PER 09910)	\$ 20,532
	4. COAT STRUCTURAL STEEL (AS PER 09960)	\$ 392,923
	6. EPOXY COAT CONCRETE (AS PER 09960)	\$ 350,278
	7. COAT @ AG PIPE, ELECTRICAL CONDUIT & MECHANICAL EQUIPMENT	\$ 11,786
	8. PRESTRESSED CONCRETE TANKS COATING (AS PER 09986)	\$ -
	9. TOUGH-UP SHOP PRIMER COATING (AS PER 09960)	\$ 15,700
	10. COAT ALUMINUM ANGLE IN CONTACT WITH CONCRETE (AS PER 09960)	\$ 20,746
	TOTAL TRADE COST	\$ 1,362,902
OVERHEAD AND PROFIT	10%	\$ 136,290
INSURANCE	3%	\$ 40,887
CONTINGENCY	5%	\$ 68,145
TAX	7%	\$ 98,810
	TOTAL TRADE COST	\$ 1,707,034
BID ALTERNATE B		
DIVISION NO.	DESCRIPTION	TOTAL DIV. COST
9000	FINISHES	
	COAT STRUCTURAL STEEL RAS PUMP STATION CANOPY - BID ALT. B	\$ 39,939
	TOTAL TRADE COST	\$ 39,939
OVERHEAD AND PROFIT	15%	\$ 5,991
INSURANCE	3%	\$ 1,198
CONTINGENCY	5%	\$ 1,997
TAX	7%	\$ 2,896
	TOTAL TRADE COST	\$ 52,021

DETAILED BREAKDOWN OF ITEMS														
Prepared for:														
Project ID:														
Scope:			WATER REPELLENTS, CONCRETE & STEEL COATINGS											
												Date:	8-Nov-22	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
GENERAL REQUIREMENTS														
1			Permits	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
2			Supervision and Coordination	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
3			Submittals and Shop drawings	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
4			Final Cleaning	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
5			Mobilization Costs	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
6			Temporary Control & Facilities	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
7			Scaffolding	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	
												SUBTOTAL	\$ -	
COATING & WATERPROOFING														
			1. DAMPROOFING AS PER (02581, 02600, 07110)											
8	100C101:102C108		Mechanical Manholes & Hand Holes(14EA)	SF	2156	10%	2372	0.030	\$ 45.00	\$ 1.35	\$ -	\$ 1.35	\$ 3,202	
9			Electrical Manholes & Hand Holes : (13EA)	SF	1350	10%	1485	0.030	\$ 45.00	\$ 1.35	\$ -	\$ 1.35	\$ 2,005	
												SUBTOTAL	\$ 5,206	
			2. WATER REPELLENT (AS PER 07190)											
			BIOREACTOR (AREA 311)											
10	311A301, 311A302		Water Repellent @ Exterior Concrete Wall	SF	7345	10%	8080	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 88,875	
			BIOREACTOR (AREA 312)											
11	312A301, 312A302		Water Repellent @ Exterior CMU Wall	SF	7087	10%	7796	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 85,753	
			SECONDARY CLARIFIERS AND ML SPLITTER (AREA 321)											
12	321S101		Water Repellent @ Mill Splitter	SF	876	10%	963	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 10,596	
13	321S150		Water Repellent @ Secondary Clarifier	SF	7776	10%	8554	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 94,090	
			THICKENING / DEWATERING BUILDING (AREA 331)											
14	331A301, 331A302		Water Repellent @ Concrete Wall	SF	15497	10%	17047	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 187,514	
			SIDESTREAM TREATMENT (AREA 352)											
15	351A301		Water Repellent @ Concrete Wall	SF	6521	10%	7173	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 78,904	
												SUBTOTAL	\$ 545,730	
			3. ARCHITECTURAL PAINTING (AS PER 09910)											
			BLOWER BUILDING (AREA 312)											
16	312A130	Wall Type C3,E1	Wall Paint	SF	1330	10%	1463	0.038	\$ 48.00	\$ 1.82	\$ 2.75	\$ 4.57	\$ 6,692	
17	312A140, 331A401	Plan D / 312A140 , Ceiling	Ceiling Paint	SF	68	10%	75	0.045	\$ 48.00	\$ 2.16	\$ 2.75	\$ 4.91	\$ 367	
			THICKENING / DEWATERING BUILDING (AREA 331)											
18	331A130, 331A136	A2,B3,D1,D2,E2,E3	Wall Paint	SF	2649	10%	2914	0.038	\$ 48.00	\$ 1.82	\$ 2.75	\$ 4.57	\$ 13,327	
19	331A401	Plan AD/ 331 A401, Ceiling Legends	Ceiling Paint	SF	27	10%	30	0.045	\$ 48.00	\$ 2.16	\$ 2.75	\$ 4.91	\$ 146	
												SUBTOTAL	\$ 20,532	
			4. COAT STRUCTURAL STEEL (AS PER 09960)											
			Electrical Conduit Bridge Plan (Area 107)											
			Beams :											
20	107S130		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W21 X 55 : (105 LF)	SF	590	10%	649	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 5,750	
21		C/107S130	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : L4 X4 X1/2 : (68 LF)	SF	96	10%	106	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 939	
			Columns :											
22			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W21 X 55 : (10 LF)	SF	56	10%	62	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 548	
23			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W14 X 33 : (45 LF)	SF	204	10%	224	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,987	
24			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS16 X 0.5 : (28 LF)	SF	147	10%	162	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,437	
			BIOREACTOR (Area 311)											
			BEAMS :											
25	311S408		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 14 : (4 LF)	SF	14	10%	16	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 139	
26		29/311S304	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 40 : (6 LF)	SF	28	10%	31	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 271	
27			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : 2L4 X4 X 3/8 : (6 LF)	SF	16	10%	17	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 154	
			COLUMNS											
28			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 14 : (2 LF) H	SF	13	10%	14	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 128	
29		29/311S304	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS3 X 3 X 1/4 : (32 LF)	SF	32	10%	35	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 312	

Scope:

WATER REPELLENTS, CONCRETE & STEEL COATINGS

Date: 8-Nov-22

Date: 6-Nov-22														
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/WASTAGE	UNIT MANHOU R	HOURL Y WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
30	312S331,170,402		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 40 : (5 LF) H	SF	201	10%	221	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,959	
				BLOWER BUILDING (Area 312)										
31				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 53 : (73 LF)	SF	348	10%	383	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 3,394
32				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W18 X 76 : (480 LF)	SF	3173	10%	3490	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 30,922
33			H,J,K/3125304	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 45 : (11 LF)	SF	51	10%	56	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 496
34			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : C12 X 20.7 (69 LF)	SF	206	10%	226	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 2,004	
35	3215532	P/3215170	SECONDARY CLARIFIER (Area 321) Clarifier Columns: Section : HSS3 X 3 X 1/4 : (36 LF) H	SF	36	10%	40	0.050	\$ 38.00	\$ 1.90	\$ 2.35	\$ 4.25	\$ 168	
			HYDROCYCLONE OVERFLOW BOX (Area 322)											
36	322S120,140,302, 303,304		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 28 : (78 LF)	SF	271	10%	298	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 2,638	
			THICKENING AND DEWATERING BUILDING (Area 331)											
37	331S133:181		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W10 X 17 : (164 LF)	SF	489	10%	538	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 4,766	
38			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W10 X 22 : (56 LF)	SF	200	10%	220	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,949	
39			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W24 X 146 : (126 LF)	SF	1051	10%	1156	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 10,241	
40			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W14 X 34 : (263 LF)	SF	1191	10%	1311	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 11,611	
41			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 26 : (1040 LF)	SF	4326	10%	4759	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 42,165	
42			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W14 X 34 : (14 LF)	SF	63	10%	70	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 618	
43			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W40 x 183 : (350 LF)	SF	3614	10%	3975	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 35,220	
44			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 19 : (8 LF)	SF	27	10%	29	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 259	
45			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 10 : (4 LF)	SF	10	10%	11	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 101	
46			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 19 : (25 LF)	SF	83	10%	91	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 809	
47			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 10 : (10 LF)	SF	26	10%	29	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 253	
48			CF/331S173	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 19 : (22 LF)	SF	73	10%	80	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 712
49				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 10 : (101 LF)	SF	263	10%	289	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 2,559
50				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 18 : (11 LF)	SF	34	10%	37	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 329
51				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 13 : (22 LF)	SF	58	10%	63	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 562
52				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 65 : (21LF)	SF	125	10%	137	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,218
53			Y/331S173	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : C8 X 11.5 : (43LF)	SF	89	10%	98	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 872
54				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : C10 X 20 (8 LF)	SF	21	10%	23	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 201
55				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : C12 X 20.7 : (19 LF)	SF	57	10%	62	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 552
56			73/331S408	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : C6 X 10.5 : (61 LF)	SF	102	10%	113	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 998
57				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS2 X 2 X 1/4 : (62 LF)	SF	41	10%	45	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 403
58				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS3X3X1/4 (54 LF)	SF	54	10%	59	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 526
59				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS8 X 4 X 1/4 : (72 LF)	SF	144	10%	158	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,403
60				EPU-M-1: Two coats epoxy with polyurethane finish coat Section : L3 X 3 X 1/4 : (28 LF)	SF	28	10%	31	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 273
61		207/331S130	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : L5 X 5 X 1/4 : (45 LF)	SF	75	10%	82	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 728	
62			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : L3 X 3 X 3/8 (106 LF)	SF	106	10%	117	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,033	
			COLUMNS											

Scope:

WATER REPELLENTS, CONCRETE & STEEL COATINGS

Date: 8-Nov-22

Date: 6-Nov-22													
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/WASTAGE	UNIT MANHOU R	HOURL Y WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
63			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS8 X 8 X 1/2 : (56 LF)	SF	150	10%	164	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,457
64			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W 8 X 28 : (24LF) H	SF	666	10%	733	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 6,493
65			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W 8 X 18 : (9LF) H	SF	442	10%	486	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 4,306
66		BD/331S303,304	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS4 X4 X3/8 : (66 LF) H	SF	88	10%	97	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 862
67			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W8 X 31 : (11LF) H	SF	87	10%	96	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 847
			METAL DECK:										
68			EPU-M-1: Two coats epoxy with polyurethane finish coat	SF	19586	10%	21545	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 190,885
			SIDESTREAM TREATMENT (Area 352)										
69			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W12 X 45 : (65 LF)	SF	301	10%	331	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 2,936
70			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : W10 X 22 : (78 LF)	SF	278	10%	305	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 2,706
71		C/352S140	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS3 X 3 X 1/6 : (62.4 LF)	SF	62	10%	69	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 608
72	352S130,352S150, 140,150		EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS6 X 6 X 3 (100 LF)	SF	200	10%	220	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,949
73			EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS3 X 3 X 3/8 : (56LF)	SF	56	10%	62	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 546
			COLUMNS										
74		AE/352S304	EPU-M-1: Two coats epoxy with polyurethane finish coat Section : HSS6 X 6 X 3/8 : (208 LF)	SF	416	10%	458	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 4,054
75		B/352S130	EPU-M-1: Two coats epoxy with polyurethane finish coat Pipe Bridge Column : W 8 X 28 (48 LF)	SF	171	10%	188	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,665
			SUBTOTAL										\$ 392,923
			6. EPOXY COAT CONCRETE (AS PER 09960)										
			Primary Effluent Distribution Structure (Area 242)										
76			EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Wall @ Interior Side : (85 LF)	SF	1700	10%	1870	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 20,570
77	242S130	D,E,F/242S130	EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Wall @ Interior Side : (15 LF)	SF	323	10%	355	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 3,902
78			EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Surface Area (6:12)	SF	61	10%	68	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 744
			Thickening Dewatering Building (Area 331)										
79			EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Walls @ PLC Room : (10 LF)	SF	150	10%	165	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 1,815
80	331A130		EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Walls @ Polymer Room : (191LF)	SF	2865	10%	3152	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 34,667
81			EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Walls @ Pump Room : (263 LF)	SF	3945	10%	4340	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 47,735
82	331A140	BD/331S303	EPX-C-6-BSC: Blended Amine Cured Epoxy Coat At Concrete Walls @ Dewatering Room : (379 LF)	SF	7959	10%	8755	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 96,304
			DIGESTED SLUDGE STORAGE TANK (AREA 342)										
83	342S130, 342S140		EPX-C-6-BSC: Blended Amine Cured Epoxy Coat @ Interior Side	SF	7640	10%	8404	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 92,444
			SIDESTREAM TREATMENT (AREA 352)										
84	352S130		EPX-C-6-BSC: Blended Amine Cured Epoxy Coat @ Interior	SF	4306	10%	4736	0.075	\$ 38.00	\$ 2.85	\$ 8.15	\$ 11.00	\$ 52,098
			SUBTOTAL										\$ 350,278
			7. COAT @ AG PIPE, ELECTRICAL CONDUIT & MECHANICAL EQUIPMENT										
85			Allowance for coat @ AG pipe, electrical conduit & mechanical equipment	LS	1	0%	1	0.000	\$ -	\$ 3,256.00	\$ 8,530.00	\$ 11,786.00	\$ 11,786
			SUBTOTAL										\$ 11,786
			8. PRESTRESSED CONCRETE TANKS COATING (AS PER 09986)										
			DIGESTED SLUDGE STORAGE TANK (AREA 342)										
86	342S130		Paint Restress Concrete Tank @ Exterior	SF	5897	10%	6487	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
			SUBTOTAL										\$ -
			9. TOUGH-UP SHOP PRIMER COATING (AS PER 09960)										
87			Touch-Up Shop Primer Coating (SF)	LS	1	0%	1	0.000	\$ -	\$ 4,500.00	\$ 11,200.00	\$ 15,700.00	\$ 15,700
			SUBTOTAL										\$ 15,700
			10. COAT ALUMINUM ANGLE IN CONTACT WITH CONCRETE (AS PER 09960)										
88			EPU-M-1: Coat Angle in Contact W/ Concrete - Two Coat Epoxy W/ Polyurethane Finish Coat	LF	2000	10%	2200	0.085	\$ 38.00	\$ 3.23	\$ 6.20	\$ 9.43	\$ 20,746
			SUBTOTAL										\$ 20,746

DETAILED BREAKDOWN OF ITEMS															
Prepared for:															
Project ID:															
Scope: WATER REPELLENTS, CONCRETE & STEEL COATINGS															
												Date:	8-Nov-22		
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/ WASTAGE	UNIT MANHOU R	HOURL Y WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST		
												TOTAL COATING & WATERPROOFING		\$ 1,362.90	
												PROJECTED COST		\$1,362.90	
OVERHEAD AND PROFIT												0.1	0.1	10%	\$136,290
INSURANCE												0.03	0.03	3%	\$40,887
CONTINGENCY												0.05	0.05	5%	\$68,145
TAX												0.0725	0.0725	7%	\$98,810
SUGGESTED BID												\$1,707.03			
COAT STRUCTURAL STEEL RAS PUMP STATION CANOPY - BID ALT. B															
HIGH PERFORMANCE COATING															
89	323 A301	NSEW Elevations	Coating @ Sheet Metal Fascia	SF	95	10%	105	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 926		
90	322 S121	Canopy Framing Plan	Coating @ Standing Seam Sheet Metal Roofing	SF	3048	10%	3353	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 29,706		
91			Coating @ Z Section Purlin	LF	725	10%	798	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 7,066		
92			Coating @ Transverse W Section	LF	135	10%	149	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 1,316		
93			Coating @ Horizontal Cross Bracing	71	95	10%	105	0.075	\$ 38.00	\$ 2.85	\$ 6.01	\$ 8.86	\$ 926		
SUBTOTAL												\$ 39.93			
TOTAL COAT STRUCTURAL STEEL RAS PUMP STATION CANOPY - BID ALT. B												\$ 39.93			
												PROJECTED COST		\$39.939	
OVERHEAD AND PROFIT												0.15	0.15	15%	\$5,991
INSURANCE												0.03	0.03	3%	\$1,198
CONTINGENCY												0.05	0.05	5%	\$1,997
TAX												0.0725	0.0725	7%	\$2,896
SUGGESTED BID												\$52.021			
Note:															
1. Please verify the equipment's and their prices with owner.															
2. For tree plantation average prices are use. Please verify according to tree type.															
3. Online sources are used for pricing.															
4. Prices can vary depending upon field conditions.															

The information contained in this transmission and any attachments are for the sole use of the intended recipient(s) and may be confidential, privileged, copyrighted or may constitute intellectual property. Any unauthorized review, use, disclosure or distribution of this transmission and any attachments is strictly prohibited. If you have received this transmission in error, please contact the sender and destroy all paper and/or electronic copies of this transmission. Information contained in this email is not authorized to be forwarded to others or duplicated without direct consent of the sender. Information contained in any attachment is not intended to be used in any manner or altered without the expressed written permission of NEDES LLC.