

GENERAL SUMMARY

Prepared for:

Project ID:

Scope: Date: **WATER REPELLENTS, CONCRETE & STEEL COATINGS**

DIVISION NO.	DESCRIPTION	TOTAL DIV. COST
	General Requirments	\$ -
	Coating & Waterproofing	
	1. DAMPPROOFING AS PER (02581, 02600, 07110)	\$ 5,206
	2. WATER REPELLENT (AS PER 07190)	\$ 545,730
	3. ARCHITECTURAL PAINTING (AS PER 09910)	\$ 20,532
	4. COAT STRUCTURAL STEEL (AS PER 09960)	\$ 392,923
	6. EPOXY COAT CONCRETE (AS PER 09960)	\$ 350,278
	7. COAT @ AG PIPE, ELECTRICAL CONDUIT & MECHANICAL EQUIPMENT	\$ 11,786
	8. PRESTRESSED CONCRETE TANKS COATING (AS PER 09986)	\$ -
	9. TOUGH-UP SHOP PRIMER COATING (AS PER 09960)	\$ 15,700
	10. COAT ALUMINUM ANGLE IN CONTACT WITH CONCRETE (AS PER 09960)	\$ 20,746
	TOTAL TRADE COST	\$ 1,362,902
OVERHEAD AND PROFIT	10%	\$ 136,290
INSURANCE	3%	\$ 40,887
CONTINGENCY	5%	\$ 68,145
TAX	7%	\$ 98,810
	TOTAL TRADE COST	\$ 1,707,034
DIVISION NO.	BID ALTERNATE B DESCRIPTION	TOTAL DIV. COST
9000	FINISHES	
	COAT STRUCTURAL STEEL RAS PUMP STATION CANOPY - BID ALT. B	\$ 39,939
	TOTAL TRADE COST	\$ 39,939
VERHEAD AND	15%	\$ 5,991
INSURANCE	3%	\$ 1,198
CONTINGENCY	5%	\$ 1,997
TAX	7%	\$ 2,896
	TOTAL TRADE COST	\$ 52,021

DETAILED BREAKDOWN OF ITEMS														Prepared for	
S/R #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY	LABOR	MAT. COST	UNIT COST	SUB COST		
1			Permits	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
2			Supervision and Coordination	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
3			Calculate and Shop Drawings	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
4			Field Control	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
5			Mobilization Costs	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
6			Temporary Control & Facilities	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
7			Start/ending	LS	1	0%	1	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -		
SUBTOTAL \$															
COATING & WATERPROOFING															
8	10C101-10C103		1. DAMP PROOFING (AS PER 02281, 02240, 07110)	SF	7156	10%	7872	0.030	\$45.00	\$1.35	\$ -	\$1.35	\$1200		
9			Mechanical Manholes & Hand Holes (MEA)	SF	1380	10%	1485	0.030	\$45.00	\$1.35	\$ -	\$1.35	\$1200		
SUBTOTAL														\$8,206	
2. WATER REPLENT (AS PER 07190)															
10	311A101		BIOREACTOR (AREA 311)	SF	7145	10%	7860	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$88,875		
11	312A101		BIOREACTOR (AREA 312)	SF	7087	10%	7796	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$85,953		
SEC. ONDARY CLARIFIERS AND M.S. SPLITTER (AREA)															
12	321S101		Water Replenish @ M.S. Splitter	SF	876	10%	963	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$10,596		
13	321S101		Water Replenish @ Secondary Clarifier	SF	7776	10%	8554	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$94,000		
THICKENING / Dewatering Building (AREA 331)															
14	331A101		Water Replenish at Concrete Wall	SF	15497	10%	17047	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$187,514		
SIDS DREAM TREATMENT (Area 352)															
15	351A101		Water Replenish at Concrete Wall	SF	6521	10%	7173	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$76,904		
SUBTOTAL														\$448,938	
3. AIR CURTAIN PAINTING (AS PER 09110)															
BLOWER BUILDING (AREA 312)															
16	312A130	Wall Type C-1	Wall Paint	SF	1130	10%	1243	0.038	\$48.00	\$1.82	\$2.75	\$4.57	\$4,602		
17	312A140	Plan D	Grinding Paint	SF	68	10%	75	0.045	\$48.00	\$2.16	\$2.75	\$4.91	\$362		
THICKENING / Dewatering Building (AREA 331)															
18	331A130	A2-B3-D1-D2-D3	Wall Paint	SF	2649	10%	2914	0.038	\$48.00	\$1.82	\$2.75	\$4.57	\$13,527		
19	331A401	Plan A-D-331	Grinding Paint	SF	27	10%	30	0.045	\$48.00	\$2.16	\$2.75	\$4.91	\$146		
SUBTOTAL														\$28,532	
4. COAT STRUCTURAL STEEL (AS PER 09160)															
Electrical Control Bridge (Area 107)															
Beams															
20	107S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	990	10%	1089	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$5,750		
21		C/107S130	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	96	10%	106	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$599		
Columns															
22			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	56	10%	62	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$548		
23	311S108		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	204	10%	224	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,907		
24			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	147	10%	162	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,437		
BIOREACTOR (AREA 311)															
Beams															
25	311S108		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	14	10%	16	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$139		
26			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	28	10%	31	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$271		
27			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	16	10%	17	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$154		
Columns															
28	311S108		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	11	10%	12	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$128		
29			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	32	10%	35	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$312		
30			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	201	10%	221	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,959		
BLOWER BUILDING (Area 312)															
31	312S331.170.402		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	348	10%	383	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$3,230		
32			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	3173	10%	3490	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$30,922		
33		H/J-K-312S304	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	51	10%	56	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$496		
34			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	206	10%	226	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$2,004		
SEC. ONDARY CLARIFIER (Area 321)															
35	321S332	P-321S370	Clarifier Column Section - HSB3 X 1 X 14 - (36.12.11)	SF	36	10%	40	0.050	\$130.00	\$1.90	\$2.35	\$4.25	\$168		
HYDRO CYCLONE OVERFLOW BOX (Area 321)															
36	322S120.140.302		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	271	10%	298	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$2,618		
THICKENING AND DEWATERING BUILDING (Area 331)															
37	331S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	489	10%	538	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$4,736		
38			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	209	10%	229	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,949		
39			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	1051	10%	1158	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$10,241		
40			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	1191	10%	1311	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$11,611		
41	331S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	4326	10%	4759	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$42,055		
42			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	63	10%	70	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$565		
43			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	3614	10%	3975	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$35,230		
44			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	27	10%	29	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$259		
45	331S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	10	10%	11	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$100		
46			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	63	10%	69	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$565		
47			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	26	10%	29	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$253		
48		C/31S1373	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	73	10%	80	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$712		
49	331S1373		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	201	10%	209	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$2,159		
50			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	14	10%	15	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$129		
51			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	58	10%	61	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$528		
52			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	125	10%	137	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,121		
53	331S1373		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	89	10%	98	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$872		
54			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	21	10%	23	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$206		
55			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	57	10%	62	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$552		
56		73-31S1408	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	102	10%	113	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$998		
57	331S1408		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	41	10%	45	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$403		
58			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	54	10%	59	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$528		
59			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	144	10%	158	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,403		
60			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	28	10%	31	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$273		
61	331S13311		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	75	10%	82	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$728		
62			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	166	10%	182	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,603		
Columns															
63			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	150	10%	164	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,437		
64	331S13311		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	666	10%	732	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$6,409		
65			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	442	10%	486	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$4,236		
66		BD-331S303.304	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	88	10%	97	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$802		
67			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	87	10%	96	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$847		
METAL DECK															
68	332S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	19986	10%	21945	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$199,085		
SIDS DREAM TREATMENT (Area 352)															
69			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	301	10%	331	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$2,926		
70	332S130		EPDM-1: Two coats epoxy with polyurethane finish coat	SF	278	10%	305	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$2,706		
71		C/332S140	EPDM-1: Two coats epoxy with polyurethane finish coat	SF	62	10%	69	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$608		
72			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	200	10%	220	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$1,949		
73			EPDM-1: Two coats epoxy with polyurethane finish coat	SF	58	10%	63	0.075	\$130.00	\$2.85	\$6.01	\$8.86	\$548		
SUBTOTAL														\$3,992,425	
5. EPDM COAT CONCRETE (AS PER 09160)															
Primary Effluent Distribution Structure (Area 242)															
76	242S130		EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	1700	10%	1870	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$20,570		
77		D/E/242S130	EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	323	10%	355	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$3,902		
78			EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1 Surface	SF	61	10%	68	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$848		
Thickening Dewatering Building (Area 331)															
79	331A130		EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	150	10%	165	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$1,815		
80			EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	2868	10%	3135	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$41,067		
81			EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	9485	10%	10430	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$137,755		
82		331A140	EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1	SF	7949	10%	8754	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$96,304		
DESIGNED SLUDGE STORAGE TANK (Area 342)															
83	342S130		EPX-C-6-ISC: Blended Amine Cured Epoxy Coat A1 Interior	SF	7640	10%	8404	0.075	\$130.00	\$2.85	\$8.15	\$11.00	\$92,444		

1. Please verify the equipment's and their prices with owner