

GENERAL SUMMARY

Prepared for:

Project ID:

Scope: Masonry

No. Of Floors: 2

Date: 11/16/23

BUILDING GSF15,400

Lower Level Floor (SF)8160

Upper Level Floor (SF)7280

DIVISIONDESCRIPTIONTOTAL DIV. COSTTOTAL DIV. COST (PER SF)

1000General Requirements\$ 54,500\$ 3.53

4000Masonry\$ 169,224\$ 10.96

TOTAL\$ 223,724\$ 14

TRADE COST

OVERHEAD AND PROFIT15%\$ 33,559\$ 2.17

I3%\$ 6,712\$ 0

N

CONTR5%\$ 11,186\$ 1

NGENC

TAX8.8%\$ 10,401\$ 1

SUBTOTAL\$ 285,582\$ 19

DIVISION COST COMPARISON

DIVISION COST COMPARISON

\$160,000

\$140,000

\$120,000

\$100,000

\$80,000

\$60,000

\$40,000

\$20,000

General Requirements

Masonry

DETAILED BREAKDOWN OF ITEMS											
Prepared for: Masonry										Date: 12/14/23	
Project ID:											
Sl#	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTE	UNIT	HOURLY	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS											
1	Permits	LS	1	0%	1	0.000	3	\$	\$	\$	\$
2	Supervision and Coordination	LS	1	0%	1	0.000	3	\$	\$	\$25,000.00	\$25,000.00
3	Submittals and Shop drawings	LS	1	0%	1	0.000	3	\$	\$2,500.00	\$2,500.00	\$2,500.00
4	Final Estimate	LS	1	0%	1	0.000	3	\$	\$2,500.00	\$2,500.00	\$2,500.00
5	Mobilization Costs	LS	1	0%	1	0.000	3	\$	\$15,000.00	\$15,000.00	\$15,000.00
6	Temporarily Control & Facilities	LS	1	0%	1	0.000	3	\$	\$6,000.00	\$6,000.00	\$6,000.00
7	Storage/Loading	LS	1	0%	1	0.000	3	\$	\$1,000.00	\$1,000.00	\$1,000.00
										SUBTOTAL	\$54,500.00

DETAILED BREAKDOWN OF ITEMS												
Prepared for:	Masonry	Date: 12/14/23										
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/	UNIT	HOURLY	LABOR COST	MAT. COST	UNIT COST
			MASONRY WALL									
			CMU STEM WALL									
1			MW1 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (40 LF)	SF	53	10%	58	0.110	\$52.00	\$5.72	\$3.15	\$58.87
2			Grouting	CY	1	10%	1	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
3			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (80 LF)	LBS	41	10%	46	0.015	\$58.00	\$0.87	\$0.95	\$1.82
4			Excavation	CY	3	10%	4	0.324	\$48.00	\$15.55	\$ -	\$15.55
5			Backfill	CY	2	10%	2	0.410	\$48.00	\$19.68	\$ -	\$19.68
6			MW2 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (188 LF)	SF	250	10%	275	0.110	\$52.00	\$5.72	\$3.15	\$58.87
7			Grouting	CY	5	10%	5	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
8			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (188 LF)	LBS	196	10%	216	0.015	\$58.00	\$0.87	\$0.95	\$1.82
9			Excavation	CY	16	10%	17	0.324	\$48.00	\$15.55	\$ -	\$15.55
10			Backfill	CY	9	10%	10	0.410	\$48.00	\$19.68	\$ -	\$19.68
11			MW3 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (13 LF)	SF	17	10%	18	0.110	\$52.00	\$5.72	\$3.15	\$58.87
12			Grouting	CY	0.31	10%	0.34	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
13			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (13 LF)	LBS	13	10%	14	0.015	\$58.00	\$0.87	\$0.95	\$1.82
14			Excavation	CY	1.1	10%	1.2	0.324	\$48.00	\$15.55	\$ -	\$15.55
15			Backfill	CY	0.7	10%	0.8	0.410	\$48.00	\$19.68	\$ -	\$19.68
16			MW6 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (6 LF)	SF	8	10%	9	0.110	\$52.00	\$5.72	\$3.15	\$58.87
17			Grouting	CY	5	10%	5	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
18			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (6 LF)	LBS	6	10%	7	0.015	\$58.00	\$0.87	\$0.95	\$1.82
19			Excavation	CY	1	10%	1	0.324	\$48.00	\$15.55	\$ -	\$15.55
20			Backfill	CY	0.38	10%	0.42	0.410	\$48.00	\$19.68	\$ -	\$19.68
21			0'-8" Wide & 0'-8" High, CMU Stem Wall : (131 LF)	SF	88	10%	97	0.110	\$52.00	\$5.72	\$3.15	\$58.87
22			Solid Grouting	CY	2	10%	2	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
23			Horizontal Reinforcement (1) #4 Bar @ Bond Beam : (131 LF)	LBS	88	10%	96	0.015	\$58.00	\$0.87	\$0.95	\$1.82
24			Excavation	CY	5	10%	6	0.324	\$48.00	\$15.55	\$ -	\$15.55
25			Backfill	CY	3	10%	4	0.410	\$48.00	\$19.68	\$ -	\$19.68
26			0'-8" Wide & 1'-4" High, CMU Stem Wall : (112 LF)	SF	112	10%	123	0.110	\$52.00	\$5.72	\$3.15	\$58.87
27			Solid Grouting	CY	3	10%	4	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
28			Horizontal Reinforcement (1) #4 Bar @ Bond Beam : (112 LF)	LBS	75	10%	82	0.015	\$58.00	\$0.87	\$0.95	\$1.82
29			Excavation	CY	7	10%	8	0.324	\$48.00	\$15.55	\$ -	\$15.55
30			Backfill	CY	4	10%	5	0.410	\$48.00	\$19.68	\$ -	\$19.68
31			0'-12" Wide & 1'-9" High, CMU Stem Wall : (210 LF)	SF	367	10%	403	0.110	\$52.00	\$5.72	\$3.15	\$58.87
32			Solid Grouting	CY	11	10%	12	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
33			Horizontal Reinforcement (2) #5 Bar @ Bond Beam : (210 LF)	LBS	438	10%	482	0.015	\$58.00	\$0.87	\$0.95	\$1.82
34			Excavation	CY	27	10%	30	0.324	\$48.00	\$15.55	\$ -	\$15.55
35			Backfill	CY	14	10%	15	0.410	\$48.00	\$19.68	\$ -	\$19.68
			CMU WALL AT LOWER LEVEL									
36			Tag W17 - (8'-0" x 16") CMU Wall At (12'-4" H) : (59 LF)	SF	724	10%	796	0.110	\$52.00	\$5.72	\$3.15	\$58.87
37			Vertical Reinforcement #5 @ 8" O.C. (106 LF)	LBS	1132	10%	1246	0.015	\$58.00	\$0.87	\$0.95	\$1.82
38			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (59 LF)	LBS	29	10%	32	0.015	\$58.00	\$0.87	\$0.95	\$1.82
39			Chain Link 600 Ghast Shield Solder On Exterior Side	SF	724	10%	796	0.010	\$52.00	\$0.52	\$0.52	\$1.04
40			Solid Grouting	CY	13	10%	15	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
41			Tag W18 - (8'-0" x 16") CMU Wall At (12'-4" H) : (17 LF)	SF	205	10%	226	0.110	\$52.00	\$5.72	\$3.15	\$58.87
42			Vertical Reinforcement #5 @ 8" O.C. (306 LF)	LBS	320	10%	352	0.015	\$58.00	\$0.87	\$0.95	\$1.82
43			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (17 LF)	LBS	17	10%	19	0.015	\$58.00	\$0.87	\$0.95	\$1.82
44			Solid Grouting	CY	4	10%	4	1.250	\$68.00	\$85.00	\$165.50	\$1,290.50
45			Tag W19 - (8'-0" x 16") CMU Wall At (12'-4" H) : (67 LF)	SF	826	10%	909	0.110	\$52.00	\$5.72	\$3.15	\$58.87
46			Vertical Reinforcement #5 @ 8" O.C. (123 LF)	LBS	1286	10%	1415	0.015	\$58.00	\$0.87	\$0.95	\$1.82
47			Horizontal Reinforcement (1) #5 Bar @ Bond Beam : (67 LF)	LBS	67	10%	74	0.015	\$58.00	\$0.87	\$0.95	\$1.82

DETAILED BREAKDOWN OF ITEMS												
Prepared for:												
Project ID:												
Scope:												
Masonry												
											Date:	12/14/23
SR.#	Drawing #	Data	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/	UNIT	HOURLY	LABOR COST	MAT. COST	UNIT COST
48	A-305, A-306		Shim-Tex 8500 Ghost Shield Sander On Interior Side	SF	826	10%	743	0.010	\$52.00	\$352	\$3.02	\$11.04
49			Solid Geotextile	CY	15	10%	17	1.250	\$48.00	\$35.00	\$165.50	\$250.50
50			Tap W19 - (8" x 8" x 16") CMI Wall At (12'-4" H) (42 LF)	SF	376	10%	344	0.110	\$52.00	\$5.72	\$3.15	\$8.87
51			Vertical Reinforcement #5 @ 16" O.C. (263 LF)	LBS	795	10%	725	0.015	\$58.00	\$3.87	\$3.05	\$1.82
52			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (87 LF)	LBS	42	10%	36	0.015	\$58.00	\$3.87	\$3.05	\$1.82
53			Shim-Tex 8500 Ghost Shield Sander On Interior Side	SF	376	10%	344	0.010	\$52.00	\$5.72	\$3.02	\$1.04
54			Solid Geotextile	CY	15	10%	17	1.250	\$48.00	\$35.00	\$165.50	\$250.50
55			Tap W20 - (8" x 10" x 16") CMI Wall At (12'-4" H) (46 LF)	SF	321	10%	283	0.120	\$52.00	\$6.24	\$4.25	\$10.49
56			Vertical Reinforcement #5 @ 8" O.C. (478 LF)	LBS	899	10%	809	0.015	\$58.00	\$3.87	\$3.05	\$1.82
57			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (76 LF)	LBS	26	10%	23	0.015	\$58.00	\$3.87	\$3.05	\$1.82
58			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	321	10%	283	0.010	\$52.00	\$3.52	\$3.02	\$1.04
59			Solid Geotextile	CY	8	10%	9	1.250	\$48.00	\$35.00	\$165.50	\$250.50
60			Tap W21 - (8" x 12" x 16") CMI Wall At (12'-4" H) (49 LF)	SF	144	10%	128	0.145	\$52.00	\$7.54	\$5.45	\$13.99
61			Vertical Reinforcement #5 @ 8" O.C. (260 LF)	LBS	202	10%	180	0.015	\$58.00	\$3.87	\$3.05	\$1.82
62			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (109 LF)	LBS	109	10%	97	0.015	\$58.00	\$3.87	\$3.05	\$1.82
63			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	144	10%	128	0.010	\$52.00	\$3.52	\$3.02	\$1.04
64			Solid Geotextile	CY	41	10%	45	1.250	\$48.00	\$35.00	\$165.50	\$250.50
65			Tap W22 - (8" x 12" x 16") CMI Wall At (12'-4" H) (44 LF)	SF	165	10%	131	0.145	\$52.00	\$7.54	\$5.45	\$13.99
66			Vertical Reinforcement #5 @ 48" O.C. (41 LF)	LBS	133	10%	116	0.015	\$58.00	\$3.87	\$3.05	\$1.82
67			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (41 LF)	LBS	41	10%	35	0.015	\$58.00	\$3.87	\$3.05	\$1.82
68			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	165	10%	131	0.010	\$52.00	\$3.52	\$3.02	\$1.04
69			Solid Geotextile	CY	8	10%	8	1.250	\$48.00	\$35.00	\$165.50	\$250.50
70			Tap W22 - (8" x 12" x 16") CMI Wall At (12'-4" H) (14 LF)	SF	173	10%	155	0.145	\$52.00	\$7.54	\$5.45	\$13.99
71			Vertical Reinforcement #5 @ 8" O.C. (258 LF)	LBS	269	10%	236	0.015	\$58.00	\$3.87	\$3.05	\$1.82
72			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (141 LF)	LBS	14	10%	15	0.015	\$58.00	\$3.87	\$3.05	\$1.82
73			Shim-Tex 8500 Ghost Shield Sander On Interior Side	SF	173	10%	155	0.010	\$52.00	\$3.52	\$3.02	\$1.04
74			Solid Geotextile	CY	5	10%	6	1.250	\$48.00	\$35.00	\$165.50	\$250.50
75			Tap W23 - (8" x 10" x 16") CMI Wall At (12'-4" H) (41 LF)	SF	141	10%	125	0.120	\$52.00	\$6.24	\$4.25	\$10.49
76			Vertical Reinforcement #5 @ 8" O.C. (210 LF)	LBS	219	10%	197	0.015	\$58.00	\$3.87	\$3.05	\$1.82
77			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (111 LF)	LBS	11	10%	13	0.015	\$58.00	\$3.87	\$3.05	\$1.82
78			Solid Geotextile	CY	3	10%	4	1.250	\$48.00	\$35.00	\$165.50	\$250.50
79			Tap W24 - (8" x 12" x 16") CMI Wall At (12'-4" H) (48 LF)	SF	177	10%	159	0.145	\$52.00	\$7.54	\$5.45	\$13.99
80			Vertical Reinforcement #5 @ 8" O.C. (70 LF)	LBS	74	10%	65	0.015	\$58.00	\$3.87	\$3.05	\$1.82
81			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (38 LF)	LBS	18	10%	16	0.015	\$58.00	\$3.87	\$3.05	\$1.82
82			Solid Geotextile	CY	9	10%	10	1.250	\$48.00	\$35.00	\$165.50	\$250.50
CMI WALL AT UPPER LEVEL												
83	A-307, A-308		Tap W17 - (8" x 8" x 16") CMI Wall At (12'-4" H) (76 LF)	SF	996	10%	897	0.110	\$52.00	\$5.72	\$3.15	\$8.87
84			Vertical Reinforcement #5 @ 8" O.C. (1361 LF)	LBS	1411	10%	1252	0.015	\$58.00	\$3.87	\$3.05	\$1.82
85			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (76 LF)	LBS	76	10%	68	0.015	\$58.00	\$3.87	\$3.05	\$1.82
86			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	996	10%	897	0.010	\$52.00	\$3.52	\$3.02	\$1.04
87			Solid Geotextile	CY	17	10%	19	1.250	\$48.00	\$35.00	\$165.50	\$250.50
88			Tap W19 - (8" x 8" x 16") CMI Wall At (12'-4" H) (52 LF)	SF	637	10%	561	0.110	\$52.00	\$5.72	\$3.15	\$8.87
89			Vertical Reinforcement #5 @ 8" O.C. (951 LF)	LBS	992	10%	893	0.015	\$58.00	\$3.87	\$3.05	\$1.82
90			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (131 LF)	LBS	53	10%	46	0.015	\$58.00	\$3.87	\$3.05	\$1.82
91			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	637	10%	561	0.010	\$52.00	\$3.52	\$3.02	\$1.04
92			Solid Geotextile	CY	12	10%	13	1.250	\$48.00	\$35.00	\$165.50	\$250.50
93			Tap W22 - (8" x 12" x 16") CMI Wall At (12'-4" H) (14 LF)	SF	179	10%	157	0.145	\$52.00	\$7.54	\$5.45	\$13.99
94			Vertical Reinforcement #5 @ 8" O.C. (254 LF)	LBS	265	10%	231	0.015	\$58.00	\$3.87	\$3.05	\$1.82
95			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (114 LF)	LBS	14	10%	16	0.015	\$58.00	\$3.87	\$3.05	\$1.82
96			Shim-Tex 8500 Ghost Shield Sander On Exterior Side	SF	179	10%	157	0.010	\$52.00	\$3.52	\$3.02	\$1.04
97			Solid Geotextile	CY	8	10%	8	1.250	\$48.00	\$35.00	\$165.50	\$250.50
98			Tap W28 - (8" x 8" x 16") CMI Wall At (12'-4" H) (8 LF)	SF	100	10%	89	0.110	\$52.00	\$5.72	\$3.15	\$8.87
99			Vertical Reinforcement #5 @ 8" O.C. (143 LF)	LBS	156	10%	139	0.015	\$58.00	\$3.87	\$3.05	\$1.82
100			Horizontal Reinforcement (1) #5 Bars @ Bond Beams (6 LF)	LBS	8	10%	9	0.015	\$58.00	\$3.87	\$3.05	\$1.82
101			Solid Geotextile	CY	2	10%	2	1.250	\$48.00	\$35.00	\$165.50	\$250.50
CONTROL JOINT												
102	S2.1, A305 To	Plan Notes	Control Joint @ 24'-0" O.C. At Masonry Walls	LF	311	10%	282	0.012	\$52.00	\$3.62	\$1.20	\$1.82
EXTRA REINFORCEMENT												
103	S2.1	Key Notes/S2.1	Tap 1465 (1) #5 VEA Vertical Bars @ 12'-0" H Walls (107 LF)	LBS	26	10%	23	0.015	\$58.00	\$3.87	\$3.05	\$1.82
104			Tap 1465 (2) #5 VEA Vertical Bars @ 12'-0" H Walls (24 LF)	LBS	25	10%	22	0.015	\$58.00	\$3.87	\$3.05	\$1.82
105			Tap 1497 (4) #5 VEA Vertical Bars @ 12'-0" H Walls (247 LF)	LBS	257	10%	233	0.015	\$58.00	\$3.87	\$3.05	\$1.82
106			Tap 1497 (4) #5 VEA Vertical Bars @ 12'-0" H Walls (144 LF)	LBS	150	10%	135	0.015	\$58.00	\$3.87	\$3.05	\$1.82
107			Tap 1121 (4) #6 VEA Vertical Bars @ 12'-0" H Walls (409 LF)	LBS	514	10%	462	0.015	\$58.00	\$3.87	\$3.05	\$1.82
108			Tap 1121 (4) #6 VEA Vertical Bars @ 12'-0" H Walls (118 LF)	LBS	154	10%	138	0.015	\$58.00	\$3.87	\$3.05	\$1.82
MASONRY LINTELS												
109	A-305-308	Masonry Lintels Schedule / S1.3	8" W x 10" Deep CMI Groat Filled Lintel	LF	16	10%	14	0.119	\$52.00	\$6.19	\$5.42	\$11.61
110			Main Reinforcement	LBS	33	10%	29	0.015	\$58.00	\$3.87	\$3.05	\$1.82
111			8" W x 20" Deep CMI Groat Filled Lintel	LF	22	10%	19	0.210	\$52.00	\$10.92	\$11.20	\$22.12
112			Main Reinforcement	LBS	67	10%	60	0.015	\$58.00	\$3.87	\$3.05	\$1.82
Notes												
											SUBTOTAL	
											\$169,224	
											PRODUCED COST	
OVERHEAD AND PROFIT											15%	
INSURANCE											3%	
CONTINGENCY											5%	
TAX											0.8%	
SUGGESTED BID											\$215,431	