

GENERAL SUMMARY

Prepared for:
 Project ID:
 Scope: Framing
 No. Of Floors: 3
 Date: 22-Apr-24

		UNIT 1 & 2 (GSF)		UNIT 3 & 4 (GSF)		UNIT 5,6 & 7 (GSF)		UNIT 8,9,10,11 & 12 (GSF)		UNIT 13 & 14 (GSF)	
		SF	5,948	SF	2,928	SF	4,440	SF	9,984	SF	3,120
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 26,000	\$ 4	\$ 13,000	\$ 4	\$ 18,000	\$ 4	\$ 39,000	\$ 3.91	\$ 17,000	\$ 5.45
5000	Metals	\$ 2,993	\$ 1	\$ 9,443	\$ 3	\$ 15,637	\$ 4	\$ 49,811	\$ 4.99	\$ -	\$ -
6000	Wood, Plastics & Composites	\$ 63,709	\$ 11	\$ 37,607	\$ 13	\$ 56,352	\$ 13	\$ 121,572	\$ 12.18	\$ 68,816	\$ 22.06
7000	Thermal & Moisture Protection	\$ 17,404	\$ 3	\$ 9,532	\$ 3	\$ 14,818	\$ 3	\$ 20,867	\$ 2.09	\$ 16,507	\$ 5.29
9000	Finishes	\$ 111,550	\$ 19	\$ 64,569	\$ 22	\$ 75,060	\$ 17	\$ 150,938	\$ 15.12	\$ 73,682	\$ 23.62
TOTAL TRADE COST		\$ 221,656	\$ 37	\$ 134,151	\$ 46	\$ 179,868	\$ 41	\$ 382,188	\$ 38	\$ 176,005	\$ 56
OVERHEAD AND PROFIT											
INSURANCE	20%	\$ 44,331.17	\$ 7	\$ 26,830.15	\$ 9	\$ 35,974	\$ 8	\$ 76,438	\$ 8	\$ 35,201	\$ 11
CONTINGENCY	3%	\$ 6,650	\$ 1	\$ 4,024.52	\$ 1	\$ 5,396	\$ 1	\$ 11,466	\$ 1	\$ 5,280	\$ 2
TAX	5%	\$ 11,083	\$ 2	\$ 6,707.54	\$ 2	\$ 8,993	\$ 2	\$ 19,109	\$ 2	\$ 8,800	\$ 3
	13%	\$ 28,815	\$ 5	\$ 17,439.60	\$ 6	\$ 23,383	\$ 5	\$ 49,684	\$ 5	\$ 22,881	\$ 7
SUGGESTED BID		\$ 312,535	\$ 53	\$ 189,153	\$ 65	\$ 253,613	\$ 57	\$ 538,886	\$ 54	\$ 248,167	\$ 80

TOTAL	
TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
\$ 113,000	\$ 22.22
\$ 77,884	\$ 12.24
\$ 348,055	\$ 70.48
\$ 79,129	\$ 16.90
\$ 475,799	\$ 96.45
\$ 1,093,867	\$ 218

\$ 218,773	\$ 44
\$ 32,816	\$ 7
\$ 54,693	\$ 11
\$ 142,203	\$ 28
\$ 1,542,353	\$ 308

DETAILED BREAKDOWN OF ITEMS													
Prepared for: Project ID: Scope: Framing													
												Date:	22-Apr-24
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 7,000.00	\$ 7,000.00
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,500.00	\$ 3,500.00
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,000.00	\$ 4,000.00
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 8,500.00	\$ 8,500.00
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,000.00	\$ 3,000.00
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
												SUB TOTAL	\$ 25,000
METALS													
			1ST FLOOR										
			STRUCTURAL STEEL										
			BEAM										
8	1 OF 1		W 200 x 27 Beam	LBS	698	10%	767	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 2,993
												SUB TOTAL	\$ 2,993
WOOD & PLASTIC													
			BASEMENT										
			ROUGH CARPENTRY										
			HEADER										
9			L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.700	\$ 42.00	\$ 29.40	\$ 62.40	\$ 91.80	\$ 184
			SHEATHING										
10			5/8" T & G Plywood Sheathing (4'x 8')	EA	41	0%	41	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 3,296
11			Nailing	EA	3409	0%	3409	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 382
			JOISTS										
			2 x 10 Row Of Bridging @ 16" (440 LF)	SF	1202								
12			2 x 10 Row Of Bridging @ 14' L.	EA	14	0%	14	0.298	\$ 42.00	\$ 12.52	\$ 40.35	\$ 52.87	\$ 740
13			2 x 10 Row Of Bridging @ 10' L.	EA	18	0%	18	0.220	\$ 42.00	\$ 9.24	\$ 28.96	\$ 38.20	\$ 688
14			2 x 10 Row Of Bridging @ 16' L.	EA	42	0%	42	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 2,542
			STAIRS										
15			7" Riser 3' Wide	EA	28	0%	28	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 2,068
16			11" Tread 3' Wide	EA	26	0%	26	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 2,168
17			2 x 12 Stair Stringer @ 16' L.	EA	4	0%	4	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 281
18			Wood Guard Rail	LF	28	10%	31	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 1,925
			1ST FLOOR										
			ROUGH CARPENTRY										
			POST										
19			P-3: 6" x 6" Pressure Treated Wood Post (9'-0" H.)	EA	4	0%	4	0.630	\$ 42.00	\$ 26.46	\$ 87.49	\$ 113.95	\$ 456
20			P-1: (3) 2 x 6 Wood Post (9'-0" H.)	EA	6	0%	6	0.438	\$ 42.00	\$ 18.40	\$ 52.65	\$ 71.05	\$ 426
21			P-2: (3) 2 x 4 Wood Post (9'-0" H.)	EA	2	0%	2	0.382	\$ 42.00	\$ 16.04	\$ 40.77	\$ 56.81	\$ 114
			HEADER										
22			L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 178
23			L-2: (2) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 198
24			L-3: (3) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.868	\$ 42.00	\$ 36.46	\$ 111.88	\$ 148.34	\$ 297
25			L-5: LVL Header By Truss Manufacture @ 16' L.	EA	4	0%	4	0.650	\$ 42.00	\$ 27.30	\$ 99.00	\$ 226.30	\$ 793
			SHEATHING										
26			5/8" T & G Plywood Sheathing (4'x 8')	EA	75	0%	75	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 5,995
27			Nailing	EA	6199	0%	6199	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 694
			JOISTS										
			2 x 10 Row Of Bridging @ 16" (762 LF)	SF	2051								
28			2 x 10 Row Of Bridging @ 16' L.	EA	60	0%	60	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 3,631
29			2 x 10 Row Of Bridging @ 12' L.	EA	66	0%	66	0.255	\$ 42.00	\$ 10.71	\$ 34.60	\$ 45.31	\$ 2,990
			2 x 8 Joist @ 16" O.C (50 LF)	SF	67								
30			2 x 8 Joist @ 6' L.	EA	12	0%	12	0.110	\$ 42.00	\$ 4.62	\$ 14.05	\$ 18.67	\$ 224
31			2 x 8 Joist @ 8' L.	EA	8	0%	8	0.148	\$ 42.00	\$ 6.22	\$ 18.70	\$ 24.92	\$ 199
			LEDGER BOARD										
32			2 x 10 Leger Board @ 16' L.	EA	7	0%	7	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 433
			STAIRS										
33			7" Riser 3' Wide	EA	28	0%	28	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 2,068
34			11" Tread 3' Wide	EA	26	0%	26	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 2,168
35			2 x 12 Stair Stringer @ 16' L.	EA	4	0%	4	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 321
36			Wood Guard Rail	LF	28	10%	31	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 1,925
			2ND FLOOR										
			ROUGH CARPENTRY										
			HEADER										
37			L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 169
38			L-2: (2) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 239
			ROOF FRAMING										
			ROUGH CARPENTRY										
			SHEATHING										
39			5/8" T & G Plywood Sheathing (4'x 8')	EA	91	0%	91	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 7,240
40			Nailing	EA	7487	0%	7487	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 839
41			Roof Sheathing Clip	EA	299	0%	299	0.048	\$ 42.00	\$ 2.02	\$ 0.20	\$ 2.22	\$ 664
			TRUSSES										
			Pre Engineering Wood Trusses Pitch 6 @ 24" O.C (1155 LF)	SF	2640								
42			Pre Engineering Wood Trusses @ 18' L.	EA	1	0%	1	1.480	\$ 42.00	\$ 62.16	\$ 178.75	\$ 240.91	\$ 241
43			Pre Engineering Wood Trusses @ 4' L.	EA	4	0%	4	0.340	\$ 42.00	\$ 14.28	\$ 39.78	\$ 54.06	\$ 216
44			Pre Engineering Wood Trusses @ 2' L.	EA	1	0%	1	0.168	\$ 42.00	\$ 7.06	\$ 19.92	\$ 26.98	\$ 27
45			Pre Engineering Wood Trusses @ 34' L.	EA	18	0%	18	2.750	\$ 42.00	\$ 115.50	\$ 377.85	\$ 493.35	\$ 8,880
46			Pre Engineering Wood Trusses @ 10' L.	EA	1	0%	1	0.825	\$ 42.00	\$ 34.65	\$ 99.39	\$ 134.04	\$ 134
47			Pre Engineering Wood Trusses @ 32' L.	EA	18	0%	18	2.588	\$ 42.00	\$ 108.70	\$ 317.80	\$ 426.50	\$ 7,677
												SUB TOTAL	\$ 63,900
THERMAL & MOISTURE PROTECTION													
			1ST FLOOR										
			THERMAL INSULATION										
			CEILING INSULATION										
48			6 Mili Poly Vapor Barrier	SF	1316	0%	1316	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 1,513

DETAILED BREAKDOWN OF ITEMS															
Prepared for: Project ID: Scope:												Date: 22-Apr-24			
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MAN/ HOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST		
49	1 OF 1		R-31 Batt Insulation	SF	1316	0%	1316	0.015	\$ 40.00	\$ 0.60	\$ 3.77	\$ 4.37	\$ 5,751		
				2ND FLOOR											
				THERMAL INSULATION											
				CEILING INSULATION											
50			6 Mili Poly Vapor Barrier	SF	1300	0%	1300	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 1,495		
51			R-60 Batt Insulation	SF	1300	0%	1300	0.015	\$ 40.00	\$ 0.60	\$ 6.05	\$ 6.65	\$ 8,645		
SUBTOTAL \$ 17,881															
FINISHES															
BASEMENT															
DRY WALL ASSEMBLIES															
52	1 OF 1		2 x 4 Load Bearing Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	24	8									
53			1/2" Type X Gypsum Wall Board (4' x 8')	SF	386	10%	425	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 662		
54				Tapping	LF	193	10%	212	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 119	
55				Mudding	LBs	20	10%	22	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 162	
56				Screw	EA	637	0%	637	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 57	
57				R22 Sound Batt Insulation	SF	193	10%	212	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 520	
58				2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	20	0%	20	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 339	
59				2 x 4 P.T Bottom Plate (16' L.)	EA	2	0%	2	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 55	
60				2 x 4 Top Plate (16' L.)	EA	3	0%	3	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 111	
61				Sealant	LF	96	10%	106	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 101	
62				2 x 4 Wood Stud Furring Wall @ 16" O.C (8'-0" H.)	LF	246	8								
63				1/2" Type X Gypsum Wall Board (4' x 8')	SF	1966	10%	2162	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 3,373	
64					Tapping	LF	983	10%	1081	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 605
65					Mudding	LBs	104	10%	115	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 827
66					Screw	EA	3244	0%	3244	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 292
67			R22 Sound Batt Insulation	SF	1966	10%	2162	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 5,298		
68			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	203	0%	203	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 3,455		
69			2 x 4 P.T Bottom Plate (16' L.)	EA	17	0%	17	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 564		
70			2 x 4 Top Plate (16' L.)	EA	34	0%	34	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 1,127		
71			Sealant	LF	983	10%	1081	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 1,027		
1ST FLOOR															
DRY WALL ASSEMBLIES															
72	1 OF 1		2 x 6 Exterior Wall @ 16" O.C (9'-0" H.)	LF	212	9									
73			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1912	10%	2103	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 3,659		
74				Tapping	LF	956	10%	1052	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 589	
75				Mudding	LBs	101	10%	111	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 805	
76				Screw	EA	3155	0%	3155	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 284	
77				5/8" Plywood Sheathing (4x 8')	EA	66	0%	66	0.380	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02	\$ 5,193	
78					Nailing	EA	5422	0%	5422	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 596
79				R22 Sound Batt Insulation	SF	1912	10%	2103	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 5,153	
80				2 x 6 Wood Stud @ 16" O.C (10' H.)	EA	176	0%	176	0.165	\$ 40.00	\$ 6.60	\$ 19.55	\$ 26.15	\$ 4,595	
81				2 x 6 Bottom Plate (16' L.)	EA	15	0%	15	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 609	
82				2 x 6 Top Plate (16' L.)	EA	29	0%	29	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 1,218	
83				Sealant	LF	425	10%	467	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 444	
84				2 x 6 Interior Wood Stud Wall @ 16" O.C (9'-0" H.)	LF	75	9								
85				5/8" Type X Gypsum Wall Board (4' x 8')	SF	1358	10%	1494	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 2,600	
86					Tapping	LF	679	10%	747	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 418
87				Mudding	LBs	72	10%	79	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 572	
88				Screw	EA	2241	0%	2241	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 202	
89			R22 Sound Batt Insulation	SF	679	10%	747	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,830		
90			2 x 6 Wood Stud @ 16" O.C (10' H.)	EA	62	0%	62	0.165	\$ 40.00	\$ 6.60	\$ 19.55	\$ 26.15	\$ 1,632		
91			2 x 6 Bottom Plate (16' L.)	EA	5	0%	5	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 216		
92			2 x 6 Top Plate (16' L.)	EA	10	0%	10	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 433		
93			Sealant	LF	302	10%	332	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 315		
94	1 OF 1		2 x 4 Interior Wood Stud Wall @ 16" O.C (9'-0" H.)	LF	73	9									
95			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1315	10%	1447	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 2,518		
96				Tapping	LF	658	10%	723	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 405	
97				Mudding	LBs	70	10%	77	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 554	
98				Screw	EA	2170	0%	2170	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 195	
99				R22 Sound Batt Insulation	SF	658	10%	723	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,773	
100				2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	60	0%	60	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 1,281	
101				2 x 4 Bottom Plate (16' L.)	EA	5	0%	5	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 168	
102				2 x 4 Top Plate (16' L.)	EA	10	0%	10	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 335	
103				Sealant	LF	292	10%	322	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 305	
104		1 OF 1		2 x 4 Demising Wall @ 16" O.C (9'-0" H.)	LF	26	9								
105				5/8" Type X Gypsum Wall Board (4' x 8')	SF	474	10%	522	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 908	
106					Tapping	LF	237	10%	261	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 146
107					Mudding	LBs	25	10%	28	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 200
108					Screw	EA	783	0%	783	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 70
109				R22 Sound Batt Insulation	SF	237	10%	261	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 639	
110				2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	44	0%	44	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 924	
111				2 x 4 Bottom Plate (16' L.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 121	
112				2 x 4 Top Plate (16' L.)	EA	7	0%	7	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 242	
113				Sealant	LF	105	10%	116	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 110	
2ND FLOOR															
DRY WALL ASSEMBLIES															
114	1 OF 1			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	26	8								
115				5/8" Type X Gypsum Wall Board (4' x 8')	SF	416	10%	458	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 797	
116					Tapping	LF	208	10%	229	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 128
117				Mudding	LBs	22	10%	24	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 175	
118				Screw	EA	687	0%	687	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 62	
119				R22 Sound Batt Insulation	SF	208	10%	229	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 561	
120				2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	43	0%	43	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 912	
121				2 x 4 Bottom Plate (16' L.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 119	
122				2 x 4 Top Plate (16' L.)	EA	7	0%	7	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 239	
123				Sealant	LF	104	10%	114	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 109	
124		1 OF 1		2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	297	8								
125				5/8" Type X Gypsum Wall Board (4' x 8')	SF	4752	10%	5228	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 9,096	
126					Tapping	LF	2376	10%	2614	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 1,464
127					Mudding	LBs	252	10%	277	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 2,000
128					Screw	EA	7841	0%	7841	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 706
129				R22 Sound Batt Insulation	SF	2376	10%	2614	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 6,404	
130				2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	246	0%	246	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 4,176	
131				2 x 4 Bottom Plate (16' L.)	EA	20	0%	20	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 681	
132				2 x 4 Top Plate (16' L.)	EA	41	0%	41	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 1,363	
133				Sealant	LF	1188	10%	1307	0.010	\$ 40.00	\$ 0.40	\$			

DETAILED BREAKDOWN OF ITEMS														
Prepared for: Project ID: Scope: Framing														
												Date:	22-Apr-24	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
GENERAL REQUIREMENTS														
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -	
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,500.00	\$ 3,500.00	
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 1,750.00	\$ 1,750.00	
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 2,000.00	\$ 2,000.00	
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,250.00	\$ 4,250.00	
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 1,500.00	\$ 1,500.00	
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -	
												SUBTOTAL	\$ 13,000	
METALS														
BASEMENT														
STRUCTURAL STEEL														
BEAM														
8	2 OF 1		W 150 x 22 Beam	LBS	959	10%	1055	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 4,115	
1ST FLOOR														
STRUCTURAL STEEL														
BEAM														
9			W 200 x 27 Beam	LBS	1242	10%	1366	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 5,328	
												SUBTOTAL	\$ 9,443	
WOOD & PLASTIC														
BASEMENT														
ROUGH CARPENTRY														
HEADER														
10	2 OF 1		L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 169	
11			L-2: (2) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 198	
SHEATHING														
12			5/8" T & G Plywood Sheathing (4'x 8')	EA	25	0%	25	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 1,980	
13			Nailing	EA	2048	0%	2048	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 229	
JOISTS														
2 x 10 Row Of Bridging @ 16" (518 LF)														
14			2 x 10 Row Of Bridging @ 8'	EA	22	0%	22	0.172	\$ 42.00	\$ 7.22	\$ 23.45	\$ 30.67	\$ 675	
15			2 x 10 Row Of Bridging @ 14'	EA	16	0%	16	0.298	\$ 42.00	\$ 12.52	\$ 40.35	\$ 52.87	\$ 846	
16			2 x 10 Row Of Bridging @ 20'	EA	10	0%	10	0.428	\$ 42.00	\$ 17.98	\$ 57.65	\$ 75.63	\$ 756	
STAIRS														
17			7" Riser 3' Wide	EA	14	0%	14	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 1,034	
18			11" Tread 3' Wide	EA	12	0%	12	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 1,001	
19			7" Riser 3'-4" Wide	EA	12	0%	12	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 910	
20			11" Tread 3'-4" Wide	EA	4	0%	4	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 350	
21			2.60 SF Triangular Stair Step	EA	6	0%	6	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 535	
22			2 x 12 Stair Stringer @ 16' L.	EA	6	0%	6	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 402	
23			3'-6" x 3'-0" Stair Landing	EA	2	0%	2	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 375	
24			Wood Guard Rail	LF	28	10%	31	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 1,925	
1ST FLOOR														
ROUGH CARPENTRY														
POST														
25				P-3: 6" x 6" Pressure Treated Wood Post (8'-6" H.)	EA	4	0%	4	0.605	\$ 42.00	\$ 25.41	\$ 82.62	\$ 108.03	\$ 432
26				P-1: (3) 2 x 6 Wood Post (8'-0" H.)	EA	2	0%	2	0.388	\$ 42.00	\$ 16.30	\$ 46.88	\$ 63.18	\$ 126
27				P-2: (3) 2 x 4 Wood Post (8'-0" H.)	EA	2	0%	2	0.339	\$ 42.00	\$ 14.24	\$ 37.35	\$ 51.59	\$ 103
HEADER														
28				L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 169
29				L-2: (2) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 198
SHEATHING														
30				5/8" T & G Plywood Sheathing (4'x 8')	EA	28	0%	28	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 2,271
31				Nailing	EA	2348	0%	2348	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 263
JOISTS														
2 x 10 Row Of Bridging @ 16" (596 LF)														
32				2 x 10 Row Of Bridging@ 10' L.	EA	22	0%	22	0.220	\$ 42.00	\$ 9.24	\$ 28.96	\$ 38.20	\$ 840
33				2 x 10 Row Of Bridging @ 8' L.	EA	14	0%	14	0.172	\$ 42.00	\$ 7.22	\$ 23.45	\$ 30.67	\$ 429
34				2 x 10 Row Of Bridging @ 14' L.	EA	26	0%	26	0.298	\$ 42.00	\$ 12.52	\$ 40.35	\$ 52.87	\$ 1,375
2 x 8 Joist @ 16" O.C (74 LF)														
35				2 x 8 Joist @ 6' L.	SF	100								
					EA	16	0%	16	0.110	\$ 42.00	\$ 4.62	\$ 14.05	\$ 18.67	\$ 299
LEDGER BOARD														
36				2 x 10 Leger Board @ 16' L.	EA	7	0%	7	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 399
STAIRS														
37				7" Riser 3' Wide	EA	14	0%	14	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 1,034
38				11" Tread 3' Wide	EA	12	0%	12	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 1,001
39				7" Riser 3'-4" Wide	EA	12	0%	12	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 910
40				11" Tread 3'-4" Wide	EA	4	0%	4	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 350
41				2.60 SF Triangular Stair Step	EA	6	0%	6	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 535
42				2 x 12 Stair Stringer @ 16' L.	EA	6	0%	6	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 402
43			3'-6" x 3'-0" Stair Landing	EA	2	0%	2	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 375	
44			Wood Guard Rail	LF	28	10%	31	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 1,925	
2ND FLOOR														
ROUGH CARPENTRY														
HEADER														
45			L-1: (2) 2 x 6 Header @ 16' L.	EA	2	0%	2	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 169	
46			L-2: (2) 2 x 8 Header @ 16' L.	EA	2	0%	2	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 198	
ROOF FRAMING														
ROUGH CARPENTRY														
SHEATHING														
47			5/8" T & G Plywood Sheathing (4'x 8')	EA	42	0%	42	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 3,376	
48			Nailing	EA	3491	0%	3491	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 391	
49			Roof Sheathing Clip	EA	140	0%	140	0.048	\$ 42.00	\$ 2.02	\$ 0.20	\$ 2.22	\$ 309	
FACIA BOARD														
50			2 x 6 Fascia Board	EA	10	0%	10	0.256	\$ 42.00	\$ 10.75	\$ 31.28	\$ 42.03	\$ 422	
TRUSSES														
Pre Engineering Wood Trusses Pitch 6 @ 24" O.C (517 LF)														
51			Pre Engineering Wood Trusses @ 16' L.	EA	2	0%	2	1.290	\$ 42.00	\$ 54.18	\$ 159.75	\$ 213.93	\$ 428	
52			Pre Engineering Wood Trusses @ 14' L.	EA	1	0%	1	1.125	\$ 42.00	\$ 47.25	\$ 138.25	\$ 185.50	\$ 186	

DETAILED BREAKDOWN OF ITEMS													
Prepared for: Project ID: Scope: Framing													
												Date: 22-Apr-24	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MAN/ HOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
53			Pre Engineering Wood Trusses @ 10' L.	EA	2	0%	2	0.825	\$ 42.00	\$ 34.65	\$ 99.39	\$ 134.04	\$ 268
54			Pre Engineering Wood Trusses @ 8' L.	EA	2	0%	2	0.650	\$ 42.00	\$ 27.30	\$ 78.95	\$ 106.25	\$ 213
55			Pre Engineering Wood Trusses @ 6' L.	EA	2	0%	2	0.485	\$ 42.00	\$ 20.37	\$ 59.25	\$ 79.62	\$ 159
56			Pre Engineering Wood Trusses @ 12' L.	EA	1	0%	1	0.966	\$ 42.00	\$ 40.57	\$ 118.39	\$ 158.96	\$ 159
57			Pre Engineering Wood Trusses @ 18' L.	EA	1	0%	1	1.480	\$ 42.00	\$ 62.16	\$ 178.75	\$ 240.91	\$ 241
58			Pre Engineering Wood Trusses @ 24' L.	EA	4	0%	4	1.928	\$ 42.00	\$ 80.98	\$ 236.69	\$ 317.67	\$ 1,271
59			Pre Engineering Wood Trusses @ 22' L.	EA	1	0%	1	1.769	\$ 42.00	\$ 74.30	\$ 216.98	\$ 291.28	\$ 291
60			Pre Engineering Wood Trusses @ 16' L.	EA	1	0%	1	1.290	\$ 42.00	\$ 54.18	\$ 159.75	\$ 213.93	\$ 214
61			Pre Engineering Wood Trusses @ 10' L.	EA	4	0%	4	0.825	\$ 42.00	\$ 34.65	\$ 99.39	\$ 134.04	\$ 536
62			Pre Engineering Wood Trusses @ 2' L.	EA	1	0%	1	0.168	\$ 42.00	\$ 7.06	\$ 19.92	\$ 26.98	\$ 27
63			Pre Engineering Wood Trusses @ 26' L.	EA	7	0%	7	2.090	\$ 42.00	\$ 87.78	\$ 256.45	\$ 344.23	\$ 2,410
64			Pre Engineering Wood Trusses @ 18' L.	EA	4	0%	4	1.480	\$ 42.00	\$ 62.16	\$ 178.75	\$ 240.91	\$ 964
65			Pre Engineering Wood Trusses @ 20' L.	EA	1	0%	1	1.625	\$ 42.00	\$ 68.25	\$ 197.45	\$ 265.70	\$ 266
66			Pre Engineering Wood Trusses @ 14' L.	EA	1	0%	1	1.125	\$ 42.00	\$ 47.25	\$ 138.25	\$ 185.50	\$ 186
67			Pre Engineering Wood Trusses @ 8' L.	EA	1	0%	1	0.650	\$ 42.00	\$ 27.30	\$ 78.95	\$ 106.25	\$ 106
												SUBTOTAL \$	37,607
THERMAL & MOISTURE PROTECTION													
			1ST FLOOR										
			THERMAL INSULATION										
			CEILING INSULATION										
68			6 Mil Poly Vapor Barrier	SF	732	0%	732	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 842
69			R-31 Batt Insulation	SF	732	0%	732	0.015	\$ 40.00	\$ 0.60	\$ 3.77	\$ 4.37	\$ 3,199
			2ND FLOOR										
			THERMAL INSULATION										
			CEILING INSULATION										
			6 Mil Poly Vapor Barrier	SF	704	0%	704	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 810
71			R-60 Batt Insulation	SF	704	0%	704	0.015	\$ 40.00	\$ 0.60	\$ 6.05	\$ 6.65	\$ 4,682
												SUBTOTAL \$	9,532
FINISHES													
			BASEMENT										
			DRY WALL ASSEMBLIES										
			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	76	8							
72			1/2" Type X Gypsum Wall Board (4' x 8')	SF	1209	10%	1330	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 2,075
73				LF	604	10%	665	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 372
74				LBs	64	10%	70	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 509
75				EA	1995	0%	1995	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 180
76				SF	604	10%	665	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,629
77			R22 Sound Batt Insulation	EA	62	0%	62	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,062
78			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	5	0%	5	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 173
79			2 x 4 P.T Bottom Plate (16' L.)	EA	10	0%	10	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 347
80			2 x 4 Top Plate (16' L.)	EA	10	0%	10	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 347
81			Sealant	LF	302	10%	332	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 316
			2 x 4 Wood Stud Furring Wall @ 16" O.C (8'-0" H.)	LF	158	8							
82			1/2" Type X Gypsum Wall Board (4' x 8')	SF	1264	10%	1390	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 2,169
83				LF	632	10%	695	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 389
84				LBs	67	10%	74	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 532
85				EA	2086	0%	2086	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 188
86				SF	1264	10%	1390	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 3,406
87			R22 Sound Batt Insulation	EA	131	0%	131	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 2,222
88			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	11	0%	11	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 362
89			2 x 4 P.T Bottom Plate (16' L.)	EA	22	0%	22	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 725
90			2 x 4 Top Plate (16' L.)	EA	22	0%	22	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 725
91			Sealant	LF	632	10%	695	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 660
			1ST FLOOR										
			DRY WALL ASSEMBLIES										
			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	135	8							
92			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1079	10%	1186	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 2,064
93				LF	539	10%	593	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 332
94				LBs	57	10%	63	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 454
95				EA	1780	0%	1780	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 160
96				SF	1079	10%	1186	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 2,907
97			R22 Sound Batt Insulation	EA	112	0%	112	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 2,334
98			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	9	0%	9	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 387
99			2 x 6 Bottom Plate (16' L.)	EA	19	0%	19	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 773
100			2 x 6 Top Plate (16' L.)	EA	19	0%	19	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 773
101			Sealant	LF	270	10%	297	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 282
			2 x 4 Interior Wood Stud Wall @ 16" O.C (9'-0" H.)	LF	56	8							
102			5/8" Type X Gypsum Wall Board (4' x 8')	SF	896	10%	986	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,715
103				LF	448	10%	493	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 276
104				LBs	47	10%	52	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 377
105				EA	1478	0%	1478	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 133
106				SF	448	10%	493	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,207
107			R22 Sound Batt Insulation	EA	46	0%	46	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 787
108			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 128
109			2 x 4 Bottom Plate (16' L.)	EA	8	0%	8	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 257
110			2 x 4 Top Plate (16' L.)	EA	8	0%	8	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 257
111			Sealant	LF	224	10%	246	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 234
			2 x 4 Demising Wall @ 16" O.C (9'-0" H.)	LF	21	9							
112			5/8" Type X Gypsum Wall Board (4' x 8')	SF	373	10%	410	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 714
113				LF	186	10%	205	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 115
114				LBs	20	10%	22	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 157
115				EA	615	0%	615	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 55
116				SF	186	10%	205	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 502
117			R22 Sound Batt Insulation	EA	34	0%	34	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 726
118			2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	3	0%	3	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 95
119			2 x 4 Bottom Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 190
120			2 x 4 Top Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 190
121			Sealant	LF	83	10%	91	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 87
			2ND FLOOR										
			DRY WALL ASSEMBLIES										
			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	21	8							
122			5/8" Type X Gypsum Wall Board (4' x 8')	SF	336	10%	370	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 643
123				LF	168	10%	185	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 103
124				LBs	18	10%	20	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 141
125				EA	554	0%	554	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 50
126				SF	168	10%	185	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 453
127			R22 Sound Batt Insulation	EA	35	0%	35	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 736
128			2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	3	0%	3	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 96
129			2 x 4 Bottom Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 193
130			2 x 4 Top Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 193
131			Sealant	LF	84	10%	92	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 88
			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	120	8							

DETAILED BREAKDOWN OF ITEMS

Prepared for:	
Project ID:	
Scope:	Framing

Date: 22-Apr-24

[illegible]

DETAILED BREAKDOWN OF ITEMS													
Prepared for: Project ID: Scope: Framing													
												Date:	22-Apr-24
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,000.00	\$ 4,000.00
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 2,000.00	\$ 2,000.00
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,500.00	\$ 3,500.00
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 5,500.00	\$ 5,500.00
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,000.00	\$ 3,000.00
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
												SUBTOTAL \$	18,000
METALS													
			BASEMENT										
			STRUCTURAL STEEL										
8	3 OF 1		BEAM										
			W 150 x 27 Beam	LBS	1782	10%	1960	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 7,645
			1ST FLOOR										
			STRUCTURAL STEEL										
9			BEAM										
			W 200 x 27 Beam	LBS	1863	10%	2049	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 7,992
												SUBTOTAL \$	15,637
WOOD & PLASTIC													
			BASEMENT										
			ROUGH CARPENTRY										
			HEADER										
10			L-1: (2) 2 x 6 Header @ 16' L.	EA	3	0%	3	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 253
11			L-2: (2) 2 x 8 Header @ 16' L.	EA	3	0%	3	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 297
			SHEATHING										
12			5/8" T & G Plywood Sheathing (4'x 8')	EA	37	0%	37	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 2,970
13			Nailing	EA	3071	0%	3071	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 344
			JOISTS										
			2 x 10 Row Of Bridging @ 16" (774 LF)	SF	1083								
14			2 x 10 Row Of Bridging @ 8' L.	EA	48	0%	48	0.172	\$ 42.00	\$ 7.22	\$ 23.45	\$ 30.67	\$ 1,472
15			2 x 10 Row Of Bridging @ 14' L.	EA	39	0%	39	0.298	\$ 42.00	\$ 12.52	\$ 40.35	\$ 52.87	\$ 2,062
			STAIRS										
16			7" Riser 3' Wide	EA	21	0%	21	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 1,551
17			11" Tread 3' Wide	EA	18	0%	18	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 1,501
18			7" Riser 3'-4" Wide	EA	18	0%	18	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 1,364
19			11" Tread 3'-4" Wide	EA	6	0%	6	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 525
20			2.60 SF Triangular Stair Step	EA	9	0%	9	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 803
21			2 x 12 Stair Stringer @ 16' L.	EA	8	0%	8	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 603
22			3'-6" x 3'-0" Stair Landing	EA	3	0%	3	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 562
23			Wood Guard Rail	LF	42	10%	46	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 2,888
			1ST FLOOR										
			ROUGH CARPENTRY										
			POST										
24			P-3: 6" x 6" Pressure Treated Wood Post (8'-6" H.)	EA	6	0%	6	0.605	\$ 42.00	\$ 25.41	\$ 82.62	\$ 108.03	\$ 648
25			P-1: (3) 2 x 6 Wood Post (8'-0" H.)	EA	3	0%	3	0.388	\$ 42.00	\$ 16.30	\$ 46.88	\$ 63.18	\$ 190
26			P-2: (3) 2 x 4 Wood Post (8'-0" H.)	EA	3	0%	3	0.339	\$ 42.00	\$ 14.24	\$ 37.35	\$ 51.59	\$ 155
			HEADER										
27			L-1: (2) 2 x 6 Header @ 16' L.	EA	3	0%	3	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 253
28			L-2: (2) 2 x 8 Header @ 16' L.	EA	3	0%	3	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 297
			SHEATHING										
29			5/8" T & G Plywood Sheathing (4'x 8')	EA	42	0%	42	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 3,357
30			Nailing	EA	3471	0%	3471	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 389
			JOISTS										
			2 x 10 Row Of Bridging @ 16" (888 LF)	SF	1224								
31			2 x 10 Row Of Bridging@ 10' L.	EA	30	0%	30	0.220	\$ 42.00	\$ 9.24	\$ 28.96	\$ 38.20	\$ 1,146
32			2 x 10 Row Of Bridging @ 8' L.	EA	24	0%	24	0.172	\$ 42.00	\$ 7.22	\$ 23.45	\$ 30.67	\$ 736
33			2 x 10 Row Of Bridging @ 14' L.	EA	39	0%	39	0.298	\$ 42.00	\$ 12.52	\$ 40.35	\$ 52.87	\$ 2,062
			2 x 8 Joist @ 16" O.C (96 LF)	SF	162								
34			2 x 8 Joist @ 8' L.	EA	21	0%	21	0.148	\$ 42.00	\$ 6.22	\$ 18.70	\$ 24.92	\$ 523
			LEDGER BOARD										
35			2 x 10 Leger Board @ 16' L.	EA	10	0%	10	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 599
			STAIRS										
36			7" Riser 3' Wide	EA	21	0%	21	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 1,551
37			11" Tread 3' Wide	EA	18	0%	18	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 1,501
38			7" Riser 3'-4" Wide	EA	18	0%	18	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 1,364
39			11" Tread 3'-4" Wide	EA	6	0%	6	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 525
40			2.60 SF Triangular Stair Step	EA	9	0%	9	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 803
41			2 x 12 Stair Stringer @ 16' L.	EA	8	0%	8	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 603
42			3'-6" x 3'-0" Stair Landing	EA	3	0%	3	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 562
43			Wood Guard Rail	LF	42	10%	46	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 2,888
			2ND FLOOR										
			ROUGH CARPENTRY										
			HEADER										
44			L-1: (2) 2 x 6 Header @ 16' L.	EA	3	0%	3	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 253
45			L-2: (2) 2 x 8 Header @ 16' L.	EA	3	0%	3	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 297
			ROOF FRAMING										
			ROUGH CARPENTRY										
			SHEATHING										
46			5/8" T & G Plywood Sheathing (4'x 8')	EA	63	0%	63	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 5,016
47			Nailing	EA	5187	0%	5187	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 581
48			Roof Sheathing Clip	EA	207	0%	207	0.048	\$ 42.00	\$ 2.02	\$ 0.20	\$ 2.22	\$ 460
			FACIA BOARD										
49			2 x 6 Fascia Board	EA	10	0%	10	0.256	\$ 42.00	\$ 10.75	\$ 31.28	\$ 42.03	\$ 422
			TRUSSES										
			Pre Engineering Wood Trusses Pitch 6 @ 24" O.C (782 LF)	SF	1603								
50			Pre Engineering Wood Trusses @ 24' L.	EA	4	0%	4	1.928	\$ 42.00	\$ 80.98	\$ 236.69	\$ 317.67	\$ 1,271
51			Pre Engineering Wood Trusses @ 22' L.	EA	10	0%	10	1.769	\$ 42.00	\$ 74.30	\$ 216.98	\$ 291.28	\$ 2,913
52			Pre Engineering Wood Trusses @ 16' L.	EA	7	0%	7	1.290	\$ 42.00	\$ 54.18	\$ 159.75	\$ 213.93	\$ 1,498

DETAILED BREAKDOWN OF ITEMS													
Prepared for: Project ID: Scope: Framing													
												Date: 22-Apr-24	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
53			Pre Engineering Wood Trusses @ 10' L.	EA	4	0%	4	0.825	\$ 42.00	\$ 34.65	\$ 99.39	\$ 134.04	\$ 536
54			Pre Engineering Wood Trusses @ 2' L.	EA	1	0%	1	0.168	\$ 42.00	\$ 7.06	\$ 19.92	\$ 26.98	\$ 27
55			Pre Engineering Wood Trusses @ 12' L.	EA	4	0%	4	0.966	\$ 42.00	\$ 40.57	\$ 118.39	\$ 158.96	\$ 636
56			Pre Engineering Wood Trusses @ 8' L.	EA	3	0%	3	0.650	\$ 42.00	\$ 27.30	\$ 78.95	\$ 106.25	\$ 319
57			Pre Engineering Wood Trusses @ 6' L.	EA	3	0%	3	0.485	\$ 42.00	\$ 20.37	\$ 59.25	\$ 79.62	\$ 239
58			Pre Engineering Wood Trusses @ 14' L.	EA	20	0%	20	1.125	\$ 42.00	\$ 47.25	\$ 138.25	\$ 185.50	\$ 3,710
59			Pre Engineering Wood Trusses @ 18' L.	EA	3	0%	3	1.480	\$ 42.00	\$ 62.16	\$ 178.75	\$ 240.91	\$ 723
60			Pre Engineering Wood Trusses @ 4' L.	EA	2	0%	2	0.340	\$ 42.00	\$ 14.28	\$ 39.78	\$ 54.06	\$ 108
												SUBTOTAL	\$ 56,352
THERMAL & MOISTURE PROTECTION													
			1ST FLOOR										
			THERMAL INSULATION										
			CEILING INSULATION										
61			6 Mili Poly Vapor Barrier	SF	1116	0%	1116	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 1,283
62			R-31 Batt Insulation	SF	1116	0%	1116	0.015	\$ 40.00	\$ 0.60	\$ 3.77	\$ 4.37	\$ 4,877
			2ND FLOOR										
			THERMAL INSULATION										
			CEILING INSULATION										
63			6 Mili Poly Vapor Barrier	SF	1110	0%	1110	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 1,277
64			R-60 Batt Insulation	SF	1110	0%	1110	0.015	\$ 40.00	\$ 0.60	\$ 6.05	\$ 6.65	\$ 7,382
												SUBTOTAL	\$ 14,818
FINISHES													
			BASEMENT										
			DRY WALL ASSEMBLIES										
65			2 X 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	114	8							
66			1/2" Type X Gypsum Wall Board (4' x 8')	SF	1824	10%	2006	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 3,130
67				LF	912	10%	1003	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 562
68				Tapping	LBs	106	10%	106	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
69				Mudding	EA	3010	0%	3010	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
70				Screw	EA	3010	0%	3010	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
71			R22 Sound Batt Insulation	SF	912	10%	1003	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 2,458
72			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	94	0%	94	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,603
73			2 x 4 P.T Bottom Plate (16' L.)	EA	8	0%	8	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 262
74			2 x 4 Top Plate (16' L.)	EA	16	0%	16	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 523
			Sealant	LF	456	10%	502	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 477
75			2 x 4 Wood Stud Furring Wall @ 16" O.C (8'-0" H.)	LF	237	8							
76			1/2" Type X Gypsum Wall Board (4' x 8')	SF	1896	10%	2086	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 3,254
77				LF	948	10%	1043	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 584
78				Tapping	LBs	100	10%	111	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
79				Mudding	EA	3128	0%	3128	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
80				Screw	EA	3128	0%	3128	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
81			R22 Sound Batt Insulation	SF	1896	10%	2086	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 5,110
82			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	196	0%	196	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 3,332
83			2 x 4 P.T Bottom Plate (16' L.)	EA	16	0%	16	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 544
84			2 x 4 Top Plate (16' L.)	EA	33	0%	33	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 1,087
			Sealant	LF	948	10%	1043	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 991
			1ST FLOOR										
			DRY WALL ASSEMBLIES										
85			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	204	8							
86			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1632	10%	1795	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 3,124
87				LF	816	10%	898	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 503
88				Tapping	LBs	86	10%	95	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
89				Mudding	EA	2693	0%	2693	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
90				Screw	EA	56	0%	56	0.380	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02
91			5/8" Plywood Sheathing (4'x 8')	Nailing	EA	4628	0%	4628	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11
92			R22 Sound Batt Insulation	SF	1632	10%	1795	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 4,398
93			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	169	0%	169	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 3,531
94			2 x 6 Bottom Plate (16' L.)	EA	14	0%	14	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 585
95			2 x 6 Top Plate (16' L.)	EA	28	0%	28	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 1,170
96			Sealant	LF	408	10%	449	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 426
97			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	84	8							
98			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1344	10%	1478	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 2,572
99				LF	672	10%	739	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 414
100				Tapping	LBs	71	0%	78	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
101				Mudding	EA	2218	0%	2218	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
102				Screw	SF	672	10%	739	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45
103			R22 Sound Batt Insulation	SF	672	10%	739	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,811
104			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	69	0%	69	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,181
105			2 x 4 Bottom Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 193
106			2 x 4 Top Plate (16' L.)	EA	12	0%	12	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 385
			Sealant	LF	336	10%	370	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 351
107			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	42	8							
108			5/8" Type X Gypsum Wall Board (4' x 8')	SF	672	10%	739	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,286
109				LF	336	10%	370	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 207
110				Tapping	LBs	36	10%	39	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
111				Mudding	EA	1109	0%	1109	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
112				Screw	EA	1109	0%	1109	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
113			R22 Sound Batt Insulation	SF	336	10%	370	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 906
114			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	69	0%	69	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,181
115			2 x 4 Bottom Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 193
116			2 x 4 Top Plate (16' L.)	EA	12	0%	12	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 385
			Sealant	LF	168	10%	185	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 176
			2ND FLOOR										
			DRY WALL ASSEMBLIES										
117			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	42	8							
118			5/8" Type X Gypsum Wall Board (4' x 8')	SF	672	10%	739	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,286
119				LF	336	10%	370	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 207
120				Tapping	LBs	36	10%	39	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
121				Mudding	EA	1109	0%	1109	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
122				Screw	EA	1109	0%	1109	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
123			R22 Sound Batt Insulation	SF	336	10%	370	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 906
124			2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	69	0%	69	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 1,473
125			2 x 4 Bottom Plate (16' L.)	EA	6	0%	6	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 193
126			2 x 4 Top Plate (16' L.)	EA	12	0%	12	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 385
			Sealant	LF	168	10%	185	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 176
127			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	59	8							
128			5/8" Type X Gypsum Wall Board (4' x 8')	SF	944	10%	1038	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,807
129				LF	472	10%	519	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 291
130				Tapping	LBs	50	10%	55	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22
131				Mudding	EA	1558	0%	1558	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
132				Screw	EA	1558	0%	1558	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09
133			R22 Sound Batt Insulation	SF	472	10%	519	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,272
134			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	49	0%	49	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 830
			2 x 4 Bottom Plate (16' L.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 135

DETAILED BREAKDOWN OF ITEMS														
Prepared for:														
Project ID:														
Scope: Framing														
												Date:	22-Apr-24	
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
135			2 x 4 Top Plate (16' L.)	EA	8	0%	8	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 271	
136			Sealant	LF	236	10%	260	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 247	
137			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	69		8							
138			5/8" Type X Gypsum Wall Board (4' x 8')	SF	552	10%	607	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,057	
139				LF	276	10%	304	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 170	
140				Tapping	LBs	29	10%	32	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 232
141				Screw	EA	911	0%	911	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 82
142			5/8" Plywood Sheathing (4'x 8')	EA	19	0%	19	0.380	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02	\$ 1,499	
143				Nailing	EA	1565	0%	1565	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 172
144			R22 Sound Batt Insulation	SF	552	10%	607	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,488	
145			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	57	0%	57	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 1,194	
146			2 x 6 Bottom Plate (16' L.)	EA	5	0%	5	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 198	
147			2 x 6 Top Plate (16' L.)	EA	9	0%	9	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 396	
148			Sealant	LF	138	10%	152	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 144	
												SUBTOTAL \$	75,060	
												PROJECTED COST	\$179,868	
OVERHEAD AND PROFIT												15%	\$26,980	
INSURANCE												3%	\$5,396	
CONTINGENCY												5%	\$8,993	
TAX												13%	\$15,451	
												SUGGESTED BID	\$236,688	

DETAILED BREAKDOWN OF ITEMS														
Prepared for: Project ID: Scope: Framing														
												Date: 22-Apr-24		
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
GENERAL REQUIREMENTS														
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -	
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 12,000.00	\$ 12,000.00	
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,500.00	\$ 3,500.00	
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,500.00	\$ 4,500.00	
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 15,000.00	\$ 15,000.00	
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,000.00	\$ 4,000.00	
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -	
												SUBTOTAL	\$ 39,000	
METALS														
BASEMENT														
STRUCTURAL STEEL														
	4 OF 1		BEAM											
8			W 200 x 21 Beam	LBS	5355	10%	5891	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 22,973	
			POST											
9			3" Heavy Duty Steel Post (8'-0" H.)	EA	15	0%	15	1.150	\$ 40.00	\$ 46.00	\$ 211.68	\$ 257.68	\$ 3,865	
1ST FLOOR														
STRUCTURAL STEEL														
		BEAM												
10			W 200 x 21 Beam	LBS	5355	10%	5891	0.020	\$ 40.00	\$ 0.80	\$ 3.10	\$ 3.90	\$ 22,973	
												SUBTOTAL	\$ 49,811	
WOOD & PLASTIC														
BASEMENT														
ROUGH CARPENTRY														
	4 OF 1		HEADER											
11			L-1: (2) 2 x 6 Header @ 16' L.	EA	5	0%	5	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 421	
			SHEATHING											
12			5/8" T & G Plywood Sheathing (4'x 8')	EA	118	0%	118	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 9,393	
13				Nailing	EA	9713	0%	9713	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 1,088
JOISTS														
2 x 10 Row Of Bridging @ 16" (509 LF)														
14				2 x 10 Row Of Bridging @ 8' L.	EA	80	0%	80	0.172	\$ 42.00	\$ 7.22	\$ 23.45	\$ 30.67	\$ 2,454
15				2 x 10 Row Of Bridging @ 12' L.	EA	80	0%	80	0.255	\$ 42.00	\$ 10.71	\$ 34.60	\$ 45.31	\$ 3,625
16				2 x 10 Row Of Bridging @ 18' L.	EA	15	0%	15	0.385	\$ 42.00	\$ 16.17	\$ 51.92	\$ 68.09	\$ 1,021
17				2 x 10 Row Of Bridging @ 4' L.	EA	15	0%	15	0.105	\$ 42.00	\$ 4.41	\$ 11.65	\$ 16.06	\$ 241
18				2 x 10 Row Of Bridging @ 6' L.	EA	15	0%	15	0.135	\$ 42.00	\$ 5.67	\$ 17.35	\$ 23.02	\$ 345
19				2 x 10 Row Of Bridging @ 10' L.	EA	110	0%	110	0.220	\$ 42.00	\$ 9.24	\$ 28.96	\$ 38.20	\$ 4,202
STAIRS														
20				7" Riser 3' Wide	EA	35	0%	35	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 2,584
21				11" Tread 3' Wide	EA	30	0%	30	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 2,502
22				7" Riser 3'-4" Wide	EA	30	0%	30	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 2,274
23				11" Tread 3'-4" Wide	EA	10	0%	10	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 875
24				2.60 SF Triangular Stair Step	EA	15	0%	15	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 1,338
25				2 x 12 Stair Stringer @ 16' L.	EA	14	0%	14	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 1,004
26				3'-6" x 3'-0" Stair Landing	EA	5	0%	5	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 937
27				Wood Guard Rail	LF	70	10%	77	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 4,813
1ST FLOOR														
ROUGH CARPENTRY														
				POST										
28				P-3: 6" x 6" Pressure Treated Wood Post (8'-6" H.)	EA	6	0%	6	0.605	\$ 42.00	\$ 25.41	\$ 82.62	\$ 108.03	\$ 648
29				P-1: (3) 2 x 6 Wood Post	EA	10	0%	10	0.388	\$ 42.00	\$ 16.30	\$ 46.88	\$ 63.18	\$ 632
30			P-2: (3) 2 x 4 Wood Post	EA	20	0%	20	0.339	\$ 42.00	\$ 14.24	\$ 37.35	\$ 51.59	\$ 1,032	
HEADER														
31			L-1: (2) 2 x 6 Header @ 16' L.	EA	5	0%	5	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 421	
32			L-2: (2) 2 x 8 Header @ 16' L.	EA	5	0%	5	0.580	\$ 42.00	\$ 24.36	\$ 74.60	\$ 98.96	\$ 495	
33			L-3: (3) 2 x 8 Header @ 16' L.	EA	5	0%	5	0.868	\$ 42.00	\$ 36.46	\$ 111.88	\$ 148.34	\$ 742	
SHEATHING														
34			5/8" T & G Plywood Sheathing (4'x 8')	EA	86	0%	86	0.380	\$ 42.00	\$ 15.96	\$ 63.82	\$ 79.78	\$ 6,884	
35				Nailing	EA	7118	0%	7118	0.001	\$ 42.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 797
JOISTS														
2 x 10 Row Of Bridging @ 16" (379 LF)														
36			2 x 10 Row Of Bridging @ 10' L.	EA	115	0%	115	0.220	\$ 42.00	\$ 9.24	\$ 28.96	\$ 38.20	\$ 4,393	
37			2 x 10 Row Of Bridging @ 12' L.	EA	95	0%	95	0.255	\$ 42.00	\$ 10.71	\$ 34.60	\$ 45.31	\$ 4,304	
38			2 x 10 Row Of Bridging @ 4' L.	EA	15	0%	15	0.105	\$ 42.00	\$ 4.41	\$ 11.65	\$ 16.06	\$ 241	
LEDGER BOARD														
39			2 x 10 Leger Board @ 16' L.	EA	20	0%	20	0.339	\$ 42.00	\$ 14.24	\$ 46.28	\$ 60.52	\$ 1,227	
STAIRS														
40			7" Riser 3' Wide	EA	35	0%	35	0.380	\$ 42.00	\$ 15.96	\$ 57.88	\$ 73.84	\$ 2,584	
41			11" Tread 3' Wide	EA	30	0%	30	0.420	\$ 42.00	\$ 17.64	\$ 65.76	\$ 83.40	\$ 2,502	
42			7" Riser 3'-4" Wide	EA	30	0%	30	0.392	\$ 42.00	\$ 16.46	\$ 59.33	\$ 75.79	\$ 2,274	
43			11" Tread 3'-4" Wide	EA	10	0%	10	0.450	\$ 42.00	\$ 18.90	\$ 68.58	\$ 87.48	\$ 875	
44			2.60 SF Triangular Stair Step	EA	15	0%	15	0.458	\$ 42.00	\$ 19.24	\$ 69.99	\$ 89.23	\$ 1,338	
45			2 x 12 Stair Stringer @ 16' L.	EA	14	0%	14	0.400	\$ 42.00	\$ 16.80	\$ 56.25	\$ 73.05	\$ 1,004	
46			3'-6" x 3'-0" Stair Landing	EA	5	0%	5	0.355	\$ 42.00	\$ 14.91	\$ 172.58	\$ 187.49	\$ 937	
47			Wood Guard Rail	LF	70	10%	77	0.250	\$ 42.00	\$ 10.50	\$ 52.00	\$ 62.50	\$ 4,813	
2ND FLOOR														
ROUGH CARPENTRY														
			HEADER											
48			L-1: (2) 2 x 6 Header @ 16' L.	EA	5	0%	5	0.520	\$ 42.00	\$ 21.84	\$ 62.45	\$ 84.29	\$ 421	
49			L-3: (3) 2 x 8 Header @ 16' L.	EA	5	0%	5	0.868	\$ 42.00	\$ 36.46	\$ 111.88	\$ 148.34	\$ 742	
50			L-4:VL By Truss Manufacture Header	EA	5	0%	5	0.650	\$ 42.00	\$ 27.30	\$ 199.00	\$ 226.30	\$ 1,132	
TRUSSES														
Pre Engineering Wood Trusses Pitch 14 @ 24" O.C (782 LF)														
51			Pre Engineering Wood Trusses @ 18' L.	EA	2	0%	2	1.480	\$ 42.00	\$ 62.16	\$ 178.75	\$ 240.91	\$ 482	
52			Pre Engineering Wood Trusses @ 16' L.	EA	2	0%	2	1.390	\$ 42.00	\$ 54.18	\$ 159.75	\$ 213.93	\$ 428	
53			Pre Engineering Wood Trusses @ 10' L.	EA	1	0%	1	0.825	\$ 42.00	\$ 34.65	\$ 99.39	\$ 134.04	\$ 134	
54			Pre Engineering Wood Trusses @ 8' L.	EA	1	0%	1	0.650	\$ 42.00	\$ 27.30	\$ 78.95	\$ 106.25	\$ 106	
Girder Truss @ 24" O.C (141 LF)														
55			Girder Truss @ 10' L.	EA	80	0%	80	0.825	\$ 42.00	\$ 34.65	\$ 115.95	\$ 150.60	\$ 12,048	

DETAILED BREAKDOWN OF ITEMS

Prepared for:	
Project ID:	
Scope:	Framing

Date: 22-Apr-24

[illegible]

THERMAL & MOISTURE PROTECTION

			1ST FLOOR														
	4 OF 1		THERMAL INSULATION														
			CEILING INSULATION														
69			6 Mil Poly Vapor Barrier	SF	1960	10%	2156	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 2.479				
70			R-31 Batt Insulation	SF	1960	10%	2156	0.015	\$ 40.00	\$ 0.60	\$ 3.77	\$ 4.37	\$ 9.422				
			2ND FLOOR														
			THERMAL INSULATION														
			CEILING INSULATION														
71			6 Mil Poly Vapor Barrier	SF	1045	10%	1150	0.009	\$ 40.00	\$ 0.36	\$ 0.79	\$ 1.15	\$ 1.322				
72			R-60 Batt Insulation	SF	1045	10%	1150	0.015	\$ 40.00	\$ 0.60	\$ 6.05	\$ 7.644					
															SUBTOTAL	\$ 20,867	

FINISHES

[illegible]

DETAILED BREAKDOWN OF ITEMS

Prepared for:	
Project ID:	
Scope:	Framing

Date: 22-Apr-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
			DRY WALL ASSEMBLIES										
125			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	54	8							
126			5/8" Type X Gypsum Wall Board (4' x 8')	SF	864	10%	950	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,654
127				LF	432	10%	475	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 266
128				LBs	46	10%	50	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 364
129				EA	1426	0%	1426	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 121
130			R22 Sound Batt Insulation	SF	432	10%	475	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,164
131			2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	89	0%	89	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 1,894
132			2 x 4 Bottom Plate (16' L.)	EA	7	0%	7	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 248
133			2 x 4 Top Plate (16' L.)	EA	15	0%	15	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 496
134			Sealant	LF	216	10%	238	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 226
135			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	180	8							
136			5/8" Type X Gypsum Wall Board (4' x 8')	SF	2880	10%	3168	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 5,512
137				LF	1440	10%	1584	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 887
138				LBs	153	10%	168	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 1,212
139				EA	4752	0%	4752	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 428
140			R22 Sound Batt Insulation	SF	1440	10%	1584	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 3,383
141			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	149	0%	149	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 2,531
142			2 x 4 Bottom Plate (16' L.)	EA	12	0%	12	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 413
143			2 x 4 Top Plate (16' L.)	EA	25	0%	25	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 826
144			Sealant	LF	720	10%	792	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 752
145			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	85	8							
146			5/8" Type X Gypsum Wall Board (4' x 8')	SF	680	10%	748	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,302
147				LF	340	10%	374	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 209
148				LBs	36	10%	40	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 286
149				EA	1122	0%	1122	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 101
150			5/8" Plywood Sheathing (4'x 8')	EA	23	0%	23	0.580	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02	\$ 1,847
151				EA	1928	0%	1928	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 212
152			R22 Sound Batt Insulation	SF	680	10%	748	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,383
153			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	70	0%	70	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 1,471
154			2 x 6 Bottom Plate (16' L.)	EA	6	0%	6	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 244
155			2 x 6 Top Plate (16' L.)	EA	12	0%	12	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 487
156			Sealant	LF	170	10%	187	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 178
SUBTOTAL												\$ 150,938	
OVERHEAD AND PROFIT													
INSURANCE													
CONTINGENCY													
TAX													
SUGGESTED BID												\$502,825	

DETAILED BREAKDOWN OF ITEMS

Prepared for:	
Project ID:	
Scope:	Framing

Date: 22-Apr-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 4,000.00	\$ 4,000.00
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 2,000.00	\$ 2,000.00
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 3,000.00	\$ 3,000.00
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 5,500.00	\$ 5,500.00
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 2,500.00	\$ 2,500.00
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
SUBTOTAL												\$	\$ 17,000.

WOOD & PLASTIC

BASEMENT

ROUGH CARPENTRY

[illegible]

THERMAL & MOISTURE PROTECTION

FLOOR

THERMAL INSULATION

[illegible]

DETAILED BREAKDOWN OF ITEMS																
Prepared for: Project ID: Scope: Framing												Date: 22-Apr-24				
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/WASTAGE	UNIT MAN/ HOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST			
FINISHES																
BASEMENT																
DRY WALL ASSEMBLIES																
			2 X 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	26	8										
46			1/2" Type X Gypsum Wall Board (4' x 8')	SF	416	10%	458	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 714			
47				Tapping	LF	208	10%	229	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 128		
48				Mudding	LBs	22	10%	24	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 175		
49				Screw	EA	686	0%	686	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 62		
50			R22 Sound Batt Insulation	SF	208	10%	229	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 561			
51			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	22	0%	22	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 366			
52			2 x 4 P.T Bottom Plate (16' L.)	EA	2	0%	2	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 60			
53			2 x 4 Top Plate (16' L.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 119			
54			Sealant	LF	104	10%	114	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 109			
			2 x 4 Wood Stud Furring Wall @ 16" O.C (8'-0" H.)	LF	156	8										
56			1/2" Type X Gypsum Wall Board (4' x 8')	SF	1248	10%	1373	0.016	\$ 40.00	\$ 0.64	\$ 0.92	\$ 1.56	\$ 2,142			
57				Tapping	LF	624	10%	686	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 384		
58				Mudding	LBs	66	10%	73	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 185		
59				Screw	EA	2059	0%	2059	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 525		
60			R22 Sound Batt Insulation	SF	1248	10%	1373	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 3,363			
61			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	129	0%	129	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 2,193			
62			2 x 4 P.T Bottom Plate (16' L.)	EA	11	0%	11	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 358			
63			2 x 4 Top Plate (16' L.)	EA	21	0%	21	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 716			
64			Sealant	LF	624	10%	686	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 652			
65																
1ST FLOOR																
DRY WALL ASSEMBLIES																
			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	162	8										
66			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1296	10%	1426	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 2,481			
67				Tapping	LF	648	10%	713	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 399		
68				Mudding	LBs	69	10%	76	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 546		
69				Screw	EA	2138	0%	2138	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 192		
70			5/8" Plywood Sheathing (4'x 8')	EA	45	0%	45	0.380	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02	\$ 3,520			
71				Nailing	EA	3675	0%	3675	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 404		
72			R22 Sound Batt Insulation	SF	1296	10%	1426	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 3,493			
73			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	134	0%	134	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 2,804			
74			2 x 6 Bottom Plate (16' L.)	EA	11	0%	11	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 464			
75			2 x 6 Top Plate (16' L.)	EA	22	0%	22	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 929			
76			Sealant	LF	324	10%	356	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 339			
77																
			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	126	8										
78			5/8" Type X Gypsum Wall Board (4' x 8')	SF	2016	10%	2218	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 3,859			
79				Tapping	LF	1008	10%	1109	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 621		
80				Mudding	LBs	107	10%	118	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 849		
81				Screw	EA	3326	0%	3326	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 299		
82			R22 Sound Batt Insulation	SF	1008	10%	1109	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 2,717			
83			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	104	0%	104	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,772			
84			2 x 4 Bottom Plate (16' L.)	EA	9	0%	9	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 289			
85			2 x 4 Top Plate (16' L.)	EA	17	0%	17	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 578			
86			Sealant	LF	504	10%	554	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 527			
87																
			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	65	8										
88			5/8" Type X Gypsum Wall Board (4' x 8')	SF	1040	10%	1144	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,991			
89				Tapping	LF	520	10%	572	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 320		
90				Mudding	LBs	55	10%	61	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 438		
91				Screw	EA	1716	0%	1716	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 154		
92			R22 Sound Batt Insulation	SF	520	10%	572	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 1,401			
93			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	108	0%	108	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,828			
94			2 x 4 Bottom Plate (16' L.)	EA	9	0%	9	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 298			
95			2 x 4 Top Plate (16' L.)	EA	18	0%	18	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 596			
96			Sealant	LF	260	10%	286	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 272			
97																
2ND FLOOR																
DRY WALL ASSEMBLIES																
			2 x 4 Demising Wall @ 16" O.C (8'-0" H.)	LF	31	8										
98			5/8" Type X Gypsum Wall Board (4' x 8')	SF	496	10%	546	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 949			
99				Tapping	LF	248	10%	273	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 153		
100				Mudding	LBs	26	10%	29	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 209		
101				Screw	EA	818	0%	818	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 74		
102			R22 Sound Batt Insulation	SF	248	10%	273	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 668			
103			2 x 4 Wood Stud @ 16" O.C (10' H.)	EA	51	0%	51	0.150	\$ 40.00	\$ 6.00	\$ 15.20	\$ 21.20	\$ 1,087			
104			2 x 4 Bottom Plate (16' L.)	EA	4	0%	4	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 142			
105			2 x 4 Top Plate (16' L.)	EA	9	0%	9	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 284			
106			Sealant	LF	124	10%	136	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 130			
107																
			2 x 4 Interior Wood Stud Wall @ 16" O.C (8'-0" H.)	LF	138	8										
108			5/8" Type X Gypsum Wall Board (4' x 8')	SF	2208	10%	2429	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 4,226			
109				Tapping	LF	1104	10%	1214	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 680		
110				Mudding	LBs	117	10%	129	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 929		
111				Screw	EA	3643	0%	3643	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 328		
112			R22 Sound Batt Insulation	SF	1104	10%	1214	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 2,975			
113			2 x 4 Wood Stud @ 16" O.C (8' H.)	EA	114	0%	114	0.118	\$ 40.00	\$ 4.72	\$ 12.28	\$ 17.00	\$ 1,940			
114			2 x 4 Bottom Plate (16' L.)	EA	9	0%	9	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 317			
115			2 x 4 Top Plate (16' L.)	EA	19	0%	19	0.228	\$ 40.00	\$ 9.12	\$ 24.25	\$ 33.37	\$ 633			
116			Sealant	LF	552	10%	607	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 577			
117																
			2 x 6 Exterior Wall @ 16" O.C (8'-0" H.)	LF	106	8										
118			5/8" Type X Gypsum Wall Board (4' x 8')	SF	848	10%	933	0.016	\$ 40.00	\$ 0.64	\$ 1.10	\$ 1.74	\$ 1,623			
119				Tapping	LF	424	10%	466	0.010	\$ 40.00	\$ 0.40	\$ 0.16	\$ 0.56	\$ 261		
120				Mudding	LBs	45	10%	49	0.128	\$ 40.00	\$ 5.12	\$ 2.10	\$ 7.22	\$ 357		
121				Screw	EA	1399	0%	1399	0.001	\$ 40.00	\$ 0.02	\$ 0.07	\$ 0.09	\$ 126		
122			5/8" Plywood Sheathing (4'x 8')	EA	29	0%	29	0.380	\$ 40.00	\$ 15.20	\$ 63.82	\$ 79.02	\$ 2,303			
123				Nailing	EA	2405	0%	2405	0.001	\$ 40.00	\$ 0.04	\$ 0.07	\$ 0.11	\$ 265		
124			R22 Sound Batt Insulation	SF	848	10%	933	0.015	\$ 40.00	\$ 0.60	\$ 1.85	\$ 2.45	\$ 2,285			
125			2 x 6 Wood Stud @ 16" O.C (8' H.)	EA	88	0%	88	0.132	\$ 40.00	\$ 5.28	\$ 15.65	\$ 20.93	\$ 1,835			
126			2 x 6 Bottom Plate (16' L.)	EA	7	0%	7	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 304			
127			2 x 6 Top Plate (16' L.)	EA	15	0%	15	0.260	\$ 40.00	\$ 10.40	\$ 31.30	\$ 41.70	\$ 608			
128			Sealant	LF	212	10%	233	0.010	\$ 40.00	\$ 0.40	\$ 0.55	\$ 0.95	\$ 222			
129																
SUBTOTAL												\$ 73,682				
OVERHEAD AND PROFIT												15%			\$176,005	
INSURANCE												3%			\$5,280	
CONTINGENCY												5%			\$8,800	
TAX												13%			\$15,147	
SUGGESTED BID															\$231,633	