

GENERAL SUMMARY

Prepared for:

Project ID:

Scope: Lumber

No. Of Floors: 2

Date:

BUILDING GSF		10,026	
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 13,700	1.37
6000	Wood, Plastics & Composites	\$ 38,138	3.80
TOTAL TRADE COST		\$ 51,838	5.17
OVERHEAD AND PROFIT	20%	\$ 10,368	\$ 1.03
INSURANCE	3%	\$ 1,555	\$ 0.16
CONTINGENCY	5%	\$ 2,592	\$ 0.26
TAX	0%	\$ -	\$ -
SUGGESTED BID		\$ 66,352	\$ 6.62

\$-



DETAILED BREAKDOWN OF ITEMS						
Prepared for: Lumber						
Project ID: Scope:						

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
GENERAL REQUIREMENTS						
1			Permits	LS	1	0%
2			Supervision and Coordination	LS	1	0%
3			Submittals and Shop drawings	LS	1	0%
4			Final Cleaning	LS	1	0%
5			Mobilization Costs	LS	1	0%
6			Temporary Control & Facilities	LS	1	0%
7			Scaffolding	LS	1	0%

WOOD & PLASTIC						
			ROUGH CARPENTRY			
			GROUND FLOOR			
			BEAM			
8		Plan Notes	FB9: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length: 6'-0" - Plies: 3 - Pieces: 3	EA	1	0%
9			FB10: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length: 16'-0" - Plies: 3 - Pieces: 3	EA	1	0%
10			FB11: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length: 18'-0" - Plies: 3 - Pieces: 6	EA	2	0%
11			FB12: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length:28'-0" - Plies: 3 - Pieces: 3	EA	1	0%
12			FB13: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length: 32'-0" - Plies: 3 - Pieces: 3	EA	1	0%
13			FB14: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 14" - Length: 44'-0" - Plies: 3 - Pieces: 3	EA	1	0%
			IJOISTS			
14			J1: PWI 20S - Size: 2-1/2" x 14" - Length: 6'-0"	EA	2	0%
15			J2: PWI 20S - Size: 2-1/2" x 14" - Length: 16'-0"	EA	12	0%

DETAILED BREAKDOWN OF ITEMS						
Prepared for:						
Project ID:						
Scope: Lumber						

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
16	Ground Floor		J3: PWI 20S - Size: 2-1/2" x 14" - Length: 20'-0"	EA	4	0%
17			J4: PWI 20S - Size: 2-1/2" x 14" - Length: 28'-0"	EA	4	0%

18			J5: PWI 20S - Size: 2-1/2" x 14" - Length: 32'-0"	EA	30	0%
19			J6: PWI 20S - Size: 2-1/2" x 14" - Length: 34'-0"	EA	7	0%
20			J7: PWI 20S - Size: 2-1/2" x 14" - Length: 42'-0"	EA	9	0%
21		Plan Notes	J8: PWI 20S - Size: 2-1/2" x 14" - Length: 44'-0"	EA	9	0%
22			J9: PWI 20S - Size: 2-1/2" x 14" - Length: 48'-0"	EA	14	0%
23			J10: PWI 20S - Size: 2-1/2" x 14" - Length: 18'-0"	EA	25	0%
24			J11: PWI 20S - Size: 2-1/2" x 14" - Length: 12'-0"	EA	5	0%
25			J15: PWI 20S - Size: 2-1/2" x 14" - Length: 6'-0" - Plies: 2 - Pieces: 8	EA	4	0%
			RIM BOARD			
26		Plan Notes	R1: Tolko Rim Board Plus - Size: 1-9/8" x 14" - Length: 12'-0"	EA	34	0%
			BLOCKING			
27		Plan Notes	B2: PWI 20 S - Size: 2-1/2" x 14" - Length: 2'-0"	EA	66	0%
			FLOOR SHEATHING			
28		Plan Notes	(4x8) 3/4" Thick, Plywood Sheathing (5075 SF)	EA	159	0%
			EXTERIOR WALL			
		Plan Notes	2 x 6 Exterior Wall			
29			2 x 6 Wood Studs (10'-0" High)	EA	326	0%
30			2 x 6 Top Plate (16 LF)	EA	54	0%
31			2 x 6 Bottom Plate (16 LF)	EA	27	0%
32			(4x8) 3/8" Thick, Plywood Sheathing (4340 SF)	EA	136	0%
			INTERIOR WALL			
			2 x 4 Interior Wall			
33			2 x 4 Wood Studs (10'-0" High)	EA	23	0%
34			2 x 4 Top Plate (16 LF)	EA	4	0%

DETAILED BREAKDOWN OF ITEMS

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
35		Plan Notes	2 x 4 Bottom Plate (16 LF)	EA	2	0%
			2 x 6 Interior Wall (Non- Load Bearing)			
36			2 x 6 Wood Studs (10'-0" High)	EA	138	0%
37			2 x 6 Top Plate (16 LF)	EA	23	0%
38			2 x 6 Bottom Plate (16 LF)	EA	11	0%
			2 x 6 Interior Wall			
39			2 x 6 Wood Studs (10'-0" High)	EA	32	0%
40			2 x 6 Top Plate (16 LF)	EA	5	0%
41			2 x 6 Bottom Plate (16 LF)	EA	3	0%
			SECOND FLOOR			
			BEAM			
42			FB8: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 11-21/2" - Length: 16'-0" - Plies: 2 - Pieces: 6	EA	3	0%
43			FB15: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 6'-0" - Plies: 2 - Pieces: 2	EA	1	0%

44
45
46
47
48
49

--

FB16: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 10'-0" - Plies: 2 - Pieces: 2	EA	1	0%
FB17: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 12'-0" - Plies: 2 - Pieces: 6	EA	3	0%
FB18: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 16'-0" - Plies: 2 - Pieces: 2	EA	1	0%
FB19: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 12'-0" - Plies: 3 - Pieces: 3	EA	1	0%
FB20: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 14'-0" - Plies: 3 - Pieces: 6	EA	2	0%
FB21: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 40'-0" - Plies: 3 - Pieces: 3	EA	1	0%

Date: _____

QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
1	0.000	\$ -	\$ -	\$ -		\$ -
1	0.000	\$ -	\$ -	\$ -	\$ 5,500.00	\$ 5,500.00
1	0.000	\$ -	\$ -	\$ -	\$ 500.00	\$ 500.00
1	0.000	\$ -	\$ -	\$ -	\$ 1,500.00	\$ 1,500.00
1	0.000	\$ -	\$ -	\$ -	\$ 2,500.00	\$ 2,500.00
1	0.000	\$ -	\$ -	\$ -	\$ 2,500.00	\$ 2,500.00
1	0.000	\$ -	\$ -	\$ -	\$ 1,200.00	\$ 1,200
SUBTOTAL						\$ 13,700

1	0.102	\$ 55.00	\$ 5.61	\$ -	\$ 5.61	\$ 6
1	0.272	\$ 55.00	\$ 14.96	\$ -	\$ 14.96	\$ 15
2	0.306	\$ 55.00	\$ 16.83	\$ -	\$ 16.83	\$ 34
1	0.476	\$ 55.00	\$ 26.18	\$ -	\$ 26.18	\$ 26
1	0.544	\$ 55.00	\$ 29.92	\$ -	\$ 29.92	\$ 30
1	0.748	\$ 55.00	\$ 41.14	\$ -	\$ 41.14	\$ 41
2	0.120	\$ 55.00	\$ 6.60	\$ -	\$ 6.60	\$ 13
12	0.320	\$ 55.00	\$ 17.60	\$ -	\$ 17.60	\$ 211

Date:

12/05/23

QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
4	0.400	\$ 55.00	\$ 22.00	\$ -	\$ 22.00	\$ 88
4	0.560	\$ 55.00	\$ 30.80	\$ -	\$ 30.80	\$ 123

30	0.640	\$ 55.00	\$ 35.20	\$ -	\$ 35.20	\$ 1,056
7	0.680	\$ 55.00	\$ 37.40	\$ -	\$ 37.40	\$ 262
9	0.840	\$ 55.00	\$ 46.20	\$ -	\$ 46.20	\$ 416
9	0.880	\$ 55.00	\$ 48.40	\$ -	\$ 48.40	\$ 436
14	0.960	\$ 55.00	\$ 52.80	\$ -	\$ 52.80	\$ 739
25	0.360	\$ 55.00	\$ 19.80	\$ -	\$ 19.80	\$ 495
5	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 66
4	0.125	\$ 55.00	\$ 6.88	\$ -	\$ 6.88	\$ 28
34	0.216	\$ 55.00	\$ 11.88	\$ -	\$ 11.88	\$ 404
66	0.040	\$ 55.00	\$ 2.20	\$ -	\$ 2.20	\$ 145
159	0.260	\$ 55.00	\$ 14.30	\$ -	\$ 14.30	\$ 2,268
326	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 2,692
54	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 716
27	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 358
136	0.260	\$ 55.00	\$ 14.30	\$ -	\$ 14.30	\$ 1,939
23	0.140	\$ 55.00	\$ 7.70	\$ -	\$ 7.70	\$ 179
4	0.224	\$ 55.00	\$ 12.32	\$ -	\$ 12.32	\$ 48

Prepared for:

Project ID:

Scope:

Lumber

Date:

QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
2	0.224	\$ 55.00	\$ 12.32	\$ -	\$ 12.32	\$ 24
138	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 1,135
23	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 302
11	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 151
32	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 267
5	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 71
3	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 35
3	0.256	\$ 55.00	\$ 14.08	\$ -	\$ 14.08	\$ 42
1	0.108	\$ 55.00	\$ 5.94	\$ -	\$ 5.94	\$ 6

1	0.180	\$ 55.00	\$ 9.90	\$ -	\$ 9.90	\$ 10
3	0.216	\$ 55.00	\$ 11.88	\$ -	\$ 11.88	\$ 36
1	0.288	\$ 55.00	\$ 15.84	\$ -	\$ 15.84	\$ 16
1	0.216	\$ 55.00	\$ 11.88	\$ -	\$ 11.88	\$ 12
2	0.252	\$ 55.00	\$ 13.86	\$ -	\$ 13.86	\$ 28
1	0.720	\$ 55.00	\$ 39.60	\$ -	\$ 39.60	\$ 40

DETAILED BREAKDOWN OF ITEMS

Prepared for:
Project ID:
Scope: Lumber

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
50		Plan Notes	DB10: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 8'-0" - Plies: 2 - Pieces: 2	EA	1	0%
51			DB11: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 10'-0" - Plies: 2 - Pieces: 4	EA	2	0%
52			DB12: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 12'-0" - Plies: 2 - Pieces: 2	EA	1	0%
53			DB14: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 12" - Length: 14'-0" - Plies: 2 - Pieces: 2	EA	1	0%
54			DB15: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 12" - Length: 14'-0" - Plies: 3 - Pieces: 3	EA	1	0%
55			DB16: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 22'-0" - Plies: 3 - Pieces: 3	EA	1	0%
56			DB17: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 12'-0" - Plies: 2 - Pieces: 2	EA	1	0%
57			DB18: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 28'-0" - Plies: 4 - Pieces: 4	EA	1	0%
58			DB19: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 6'-0" - Plies: 2 - Pieces: 2	EA	1	0%
			POST			
59	Second Floor	Plan Notes	C1: Boozer 1.9E Column - Size: 7" x 3-1/2" - Length: 12'-0"	EA	2	0%
60			C2: Boozer 1.9E Column - Size: 5-1/2" x 5-1/2" - Length: 12'-0"	EA	24	0%
			JOISTS			

Prepared for:
Project ID:
Scope: Lumber

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
61			J16: PW1 32S - Size: 2-1/2" x 16" - Length: 2'-0"	EA	9	0%
62			J17: PW1 32S - Size: 2-1/2" x 16" - Length: 4'-0"	EA	15	0%

63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78

Plan Notes	J18: PW1 32S - Size: 2-1/2" x 16" - Length: 12'-0"	EA	5	0%
	J19: PW1 32S - Size: 2-1/2" x 16" - Length: 18'-0"	EA	48	0%
	J20: PW1 32S - Size: 2-1/2" x 16" - Length: 26'-0"	EA	12	0%
	J21: PW1 32S - Size: 2-1/2" x 16" - Length: 28'-0"	EA	2	0%
	J22: PW1 32S - Size: 2-1/2" x 16" - Length: 28'-0"	EA	9	0%
	J23: PW1 32S - Size: 2-1/2" x 16" - Length: 18'-0" - Plies: 2 - Pieces: 4	EA	2	0%
	2 x 12 WOOD JOIST @ 16" O.C.			
Plan Notes	2 x 12 Wood Joist - Length: 18'-0"	EA	12	0%
	2 x 12 Wood Joist - Length: 20'-0"	EA	4	0%
	2 x 12 Wood Joist - Length: 16'-0"	EA	66	0%
	2 x 12 Wood Joist - Length: 14'-0"	EA	1	0%
	RIM BOARD			
Plan Notes	R2: Tolko Rim Board Plus - Size: 1-9/8" x 16" - Length: 12'-0"	EA	17	0%
	Tolko Rim Board Plus - Size: 2" x 12" - Length: 12'-0"	EA	16	0%
	BLOCKING			
Plan Notes	B1: PW1 32 S - Size: 2-1/2" x 16" - Length: 2'-0"	EA	14	0%
	FLOOR SHEATHING			
Plan Notes	(4'x8') 3/4" Thick, Plywood Sheathing (4697 SF)	EA	147	0%
	EXTERIOR WALL			
Plan Notes	2 x 6 Exterior Wall			
	2 x 6 Wood Studs (10'-0" High)	EA	299	0%
	2 x 6 Top Plate (16 LF)	EA	50	0%

Date:

QUANTITY W/ WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
1	0.128	\$ 55.00	\$ 7.04	\$ -	\$ 7.04	\$ 7
2	0.160	\$ 55.00	\$ 8.80	\$ -	\$ 8.80	\$ 18
1	0.192	\$ 55.00	\$ 10.56	\$ -	\$ 10.56	\$ 11
1	0.238	\$ 55.00	\$ 13.09	\$ -	\$ 13.09	\$ 13
1	0.238	\$ 55.00	\$ 13.09	\$ -	\$ 13.09	\$ 13
1	0.396	\$ 55.00	\$ 21.78	\$ -	\$ 21.78	\$ 22
1	0.216	\$ 55.00	\$ 11.88	\$ -	\$ 11.88	\$ 12
1	0.504	\$ 55.00	\$ 27.72	\$ -	\$ 27.72	\$ 28
1	0.096	\$ 55.00	\$ 5.28	\$ -	\$ 5.28	\$ 5
2	0.180	\$ 55.00	\$ 9.90	\$ -	\$ 9.90	\$ 20
24	0.180	\$ 55.00	\$ 9.90	\$ -	\$ 9.90	\$ 238

Date: 12/05/23

QUANTITY W/ WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
9	0.044	\$ 55.00	\$ 2.42	\$ -	\$ 2.42	\$ 22
15	0.088	\$ 55.00	\$ 4.84	\$ -	\$ 4.84	\$ 73

5	0.264	\$ 55.00	\$ 14.52	\$ -	\$ 14.52	\$ 73
48	0.396	\$ 55.00	\$ 21.78	\$ -	\$ 21.78	\$ 1,045
12	0.572	\$ 55.00	\$ 31.46	\$ -	\$ 31.46	\$ 378
2	0.616	\$ 55.00	\$ 33.88	\$ -	\$ 33.88	\$ 68
9	0.616	\$ 55.00	\$ 33.88	\$ -	\$ 33.88	\$ 305
2	0.396	\$ 55.00	\$ 21.78	\$ -	\$ 21.78	\$ 44
12	0.396	\$ 55.00	\$ 21.78	\$ -	\$ 21.78	\$ 261
4	0.440	\$ 55.00	\$ 24.20	\$ -	\$ 24.20	\$ 97
66	0.352	\$ 55.00	\$ 19.36	\$ -	\$ 19.36	\$ 1,278
1	0.308	\$ 55.00	\$ 16.94	\$ -	\$ 16.94	\$ 17
		\$ 55.00				
17	0.252	\$ 55.00	\$ 13.86	\$ -	\$ 13.86	\$ 236
16	0.264	\$ 55.00	\$ 14.52	\$ -	\$ 14.52	\$ 230
14	0.044	\$ 55.00	\$ 2.42	\$ -	\$ 2.42	\$ 34
147	0.260	\$ 55.00	\$ 14.30	\$ -	\$ 14.30	\$ 2,099
299	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 2,469
50	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 657

DETAILED BREAKDOWN OF ITEMS

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
79		Plan Notes	2 x 6 Bottom Plate (16 LF)	EA	25	0%
80			(4'x8') 3/8" Thick, Plywood Sheathing (3980 SF)	EA	124	0%
			INTERIOR WALL			
			2 x 4 Interior Wall			
81			2 x 4 Wood Studs (10'-0" High)	EA	55	0%
82			2 x 4 Top Plate (16 LF)	EA	9	0%
83			2 x 4 Bottom Plate (16 LF)	EA	5	0%
			2 x 6 Interior Wall (Non- Load Bearing)			
84			2 x 6 Wood Studs (10'-0" High)	EA	7	0%
85			2 x 6 Top Plate (16 LF)	EA	1	0%
86			2 x 6 Bottom Plate (16 LF)	EA	1	0%
			2 x 6 Interior Wall			
87			2 x 6 Wood Studs (10'-0" High)	EA	91	0%
88			2 x 6 Top Plate (16 LF)	EA	15	0%
89			2 x 6 Bottom Plate (16 LF)	EA	8	0%
			THIRD FLOOR			
			BEAM			
90	Third Floor	Plan Notes	Walkway Beam: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 16" - Length: 12'-0"	EA	6	0%
91			DB11: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 10'-0" - Plies: 2 - Pieces: 8	EA	4	0%
92			DB12: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 12'-0" - Plies: 2 - Pieces: 2	EA	1	0%
93			DB13: 2.0E 2900Fb PWT LVL - Size:1-3/4" x 9-1/2" - Length: 18'-0" - Plies: 3 - Pieces: 3	EA	1	0%
			POST			
94		Plan Notes	Walkway: Boozer 1.9E Column - Size: 5-1/2" x 5-1/2" - Length: 12'-0"	EA	4	0%
95			C2: Boozer 1.9E Column - Size: 5-1/2" x 5-1/2" - Length: 12'-0"	EA	14	0%
			ROOF			
			ROOF SHEATHING			
96		Plan Notes	(4'x8') 1/2" Thick, Plywood Sheathing (6172 SF)	EA	193	0%
			TRUSSES			
			NOTE: All Trusses to have slope of 4:12 as mentioned in the Trusses Profile Document			
97			A1: Hip Girder Truss (22 LF)	EA	1	0%
98			A2: Hip Truss (22 LF)	EA	1	0%
99			A3: Hip Truss (22 LF)	EA	1	0%
100			A4: Common Girder Truss (18 LF)	EA	1	0%
101			AJ1: Jack-Closed Truss (6 LF)	EA	2	0%
102			AJ2: Jack-Closed Truss (4 LF)	EA	2	0%
103			AJ3: Half Hip Girder Truss (6 LF)	EA	2	0%
104			AJ4: Jack-Closed Truss (6 LF)	EA	6	0%
105			B1: Hip Girder Truss (48 LF)	EA	1	0%
106			B2: Hip Truss (48 LF)	EA	1	0%
107			B3: Hip Girder Truss (48 LF)	EA	1	0%
108			B4: Hip Truss (48 LF)	EA	1	0%
109			B5: Hip Girder Truss (48 LF)	EA	1	0%
110			B6: Hip Girder Truss (48 LF)	EA	1	0%
111			B7: Half Hip Truss (18 LF)	EA	1	0%
112			B8: Monopitch Truss (18 LF)	EA	4	0%
113			BJ1: Half Hip Girder Truss (8 LF)	EA	2	0%
114			BJ2: Jack Closed Truss (8 LF)	EA	3	0%
115			BJ3: Jack Closed Truss (6 LF)	EA	7	0%
116			C1: Hip Girder Truss (32 LF)	EA	1	0%
117			C2: Hip Girder Truss (32 LF)	EA	1	0%

118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198

**Roof Truss
Layout**

Truss Profile

C3: Hip Truss (24 LF)	EA	1	0%
C4: Hip Truss (24 LF)	EA	1	0%
C5: Hip Truss (24 LF)	EA	1	0%
C6: Common Truss (24 LF)	EA	1	0%
C7: Common Truss (22 LF)	EA	2	0%
C8: Common Girder Truss (30 LF)	EA	1	0%
C9: Common Truss (30 LF)	EA	4	0%
C11: Flat Girder Truss (14 LF)	EA	1	0%
CJ1: Half Hip Girder Truss (8 LF)	EA	2	0%
CJ2: Half Hip Truss (8 LF)	EA	2	0%
CJ3: Jack Closed Truss (8 LF)	EA	9	0%
D1: Half Hip Girder Truss (10LF)	EA	2	0%
D2: Half Hip Truss (10LF)	EA	2	0%
D3: Half Hip Truss (10LF)	EA	2	0%
G1: Half Hip Girder Truss (38 LF)	EA	1	0%
G2: Hip Truss (38 LF)	EA	1	0%
G3: Hip Truss (38 LF)	EA	1	0%
G4: Hip Truss (36 LF)	EA	1	0%
G5: Hip Truss (36 LF)	EA	1	0%
G6: Hip Truss (36 LF)	EA	1	0%
G7: Hip Girder Truss (34 LF)	EA	1	0%
H1: Hip Girder Truss (36 LF)	EA	1	0%
H2: Roof Special Truss (36 LF)	EA	1	0%
H3: Hip Truss (36 LF)	EA	1	0%
H4: Hip Truss (34 LF)	EA	2	0%
H5: Hip Truss (34 LF)	EA	2	0%
H6: Hip Truss (34 LF)	EA	2	0%
H7: Hip Truss (34 LF)	EA	1	0%
H8: Hip Truss (34 LF)	EA	1	0%
H9: Hip Girder Truss (34 LF)	EA	1	0%
HJ1: Half Hip Girder Truss (6 LF)	EA	1	0%
HJ2: Half Hip Truss (6 LF)	EA	1	0%
HJ3: Jack Closed Truss (6 LF)	EA	6	0%
HJ4: Jack Closed Truss (8 LF)	EA	3	0%
HJ5: Jack Closed Truss (8 LF)	EA	7	0%
HJ6: Half Hip Truss (8 LF)	EA	2	0%
HJ7: Half Hip Girder Truss (8 LF)	EA	2	0%
HJ8: Half Hip Girder Truss (10 LF)	EA	2	0%
HJ9: Half Hip Truss (10 LF)	EA	2	0%
HJ10: Half Hip Truss (10 LF)	EA	1	0%
HJ11: Jack Closed Truss (10 LF)	EA	4	0%
HJ12: Jack Closed Truss (6 LF)	EA	2	0%
J1: Jack Closed Truss (6 LF)	EA	10	0%
J2: Jack Closed Truss (4 LF)	EA	12	0%
J3: Jack Closed Structural Gable Truss (6 LF)	EA	2	0%
J4: Jack Closed Truss (2 LF)	EA	2	0%
J5: Jack Closed Truss (2 LF)	EA	3	0%
J6: Jack Closed Truss (4 LF)	EA	8	0%
J7: Half Hip Girder Truss (6 LF)	EA	6	0%
J8: Jack Closed Truss (6 LF)	EA	36	0%
J9: Jack Closed Truss (6 LF)	EA	2	0%
J10: Jack Closed Truss (6 LF)	EA	2	0%
J11: Jack Closed Truss (6 LF)	EA	1	0%
J12: Jack Closed Truss (4 LF)	EA	1	0%
K1: Hip Girder Truss (32 LF)	EA	1	0%
K2: Hip Truss (32 LF)	EA	1	0%
K3: Hip Truss (32 LF)	EA	1	0%
K4: Hip Truss (32 LF)	EA	1	0%
K5: Hip Truss (32 LF)	EA	1	0%
K6: Hip Truss (32 LF)	EA	1	0%
K7: Common Girder Truss (28 LF)	EA	1	0%
L1: Hip Girder Truss (32 LF)	EA	1	0%
L2: Hip Truss (32 LF)	EA	1	0%
L3: Hip Truss (32 LF)	EA	1	0%
L4: Hip Truss (32 LF)	EA	1	0%
L5: Hip Truss (32 LF)	EA	1	0%
L6: Common Truss (32 LF)	EA	4	0%
L7: Common Girder Truss (30 LF)	EA	2	0%
L8: Common Truss (30 LF)	EA	4	0%
P1: Monopitch Truss (12 LF)	EA	7	0%
P2: Monopitch Girder Truss (10 LF)	EA	1	0%
P3: Jack Closed Truss (6 LF)	EA	3	0%
P4: Jack Closed Truss (4 LF)	EA	2	0%
P5: Half Hip Girder Truss (6 LF)	EA	2	0%
P6: Jack Closed Truss (6 LF)	EA	4	0%
P7: Hip Girder Truss (18 LF)	EA	1	0%
P8: Hip Truss (16 LF)	EA	1	0%
P9: Common Truss (16 LF)	EA	2	0%
P10: Common Truss (14 LF)	EA	1	0%
P11: Roof Special Girder Truss (18 LF)	EA	1	0%
P12: Roof Special Truss (18 LF)	EA	1	0%

199
200
201
202
203
204
205

--

V1: Valley Truss (12 LF)	EA	2	0%
V2: Valley Truss (8 LF)	EA	2	0%
V3: Valley Truss (16 LF)	EA	1	0%
V4: Valley Truss (8 LF)	EA	1	0%
V5: Valley Truss (10 LF)	EA	1	0%
V6: Valley Truss (6 LF)	EA	1	0%
V7: Valley Truss (10 LF)	EA	1	0%

Prepared for:
Project ID:
Scope: Lumber
Date:

QUANTITY W/ WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
25	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 328
124	0.260	\$ 55.00	\$ 14.30	\$ -	\$ 14.30	\$ 1,779
55	0.140	\$ 55.00	\$ 7.70	\$ -	\$ 7.70	\$ 423
9	0.224	\$ 55.00	\$ 12.32	\$ -	\$ 12.32	\$ 112
5	0.224	\$ 55.00	\$ 12.32	\$ -	\$ 12.32	\$ 56
7	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 56
1	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 15
1	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 13
91	0.150	\$ 55.00	\$ 8.25	\$ -	\$ 8.25	\$ 751
15	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 200
8	0.240	\$ 55.00	\$ 13.20	\$ -	\$ 13.20	\$ 100
6	0.216	\$ 55.00	\$ 11.88	\$ -	\$ 11.88	\$ 71
4	0.160	\$ 55.00	\$ 8.80	\$ -	\$ 8.80	\$ 35
1	0.192	\$ 55.00	\$ 10.56	\$ -	\$ 10.56	\$ 11
1	0.288	\$ 55.00	\$ 15.84	\$ -	\$ 15.84	\$ 16
4	0.180	\$ 55.00	\$ 9.90	\$ -	\$ 9.90	\$ 40
14	0.180	\$ 55.00	\$ 9.90	\$ -	\$ 9.90	\$ 139
193	0.260	\$ 55.00	\$ 14.30	\$ -	\$ 14.30	\$ 2,758
1	0.550	\$ 55.00	\$ 30.25	\$ -	\$ 30.25	\$ 30
1	0.550	\$ 55.00	\$ 30.25	\$ -	\$ 30.25	\$ 30
1	0.550	\$ 55.00	\$ 30.25	\$ -	\$ 30.25	\$ 30
1	0.520	\$ 55.00	\$ 28.60	\$ -	\$ 28.60	\$ 29
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
2	0.200	\$ 55.00	\$ 11.00	\$ -	\$ 11.00	\$ 22
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
6	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 73
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	1.180	\$ 55.00	\$ 64.90	\$ -	\$ 64.90	\$ 65
1	0.520	\$ 55.00	\$ 28.60	\$ -	\$ 28.60	\$ 29
4	0.520	\$ 55.00	\$ 28.60	\$ -	\$ 28.60	\$ 114
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
3	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 41
7	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 85
1	0.785	\$ 55.00	\$ 43.18	\$ -	\$ 43.18	\$ 43
1	0.785	\$ 55.00	\$ 43.18	\$ -	\$ 43.18	\$ 43

1	0.590	\$ 55.00	\$ 32.45	\$ -	\$ 32.45	\$ 32
1	0.590	\$ 55.00	\$ 32.45	\$ -	\$ 32.45	\$ 32
1	0.590	\$ 55.00	\$ 32.45	\$ -	\$ 32.45	\$ 32
1	0.590	\$ 55.00	\$ 32.45	\$ -	\$ 32.45	\$ 32
2	0.550	\$ 55.00	\$ 30.25	\$ -	\$ 30.25	\$ 61
1	0.720	\$ 55.00	\$ 39.60	\$ -	\$ 39.60	\$ 40
4	0.720	\$ 55.00	\$ 39.60	\$ -	\$ 39.60	\$ 158
1	0.425	\$ 55.00	\$ 23.38	\$ -	\$ 23.38	\$ 23
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
9	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 124
2	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 31
2	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 31
2	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 31
1	0.950	\$ 55.00	\$ 52.25	\$ -	\$ 52.25	\$ 52
1	0.950	\$ 55.00	\$ 52.25	\$ -	\$ 52.25	\$ 52
1	0.950	\$ 55.00	\$ 52.25	\$ -	\$ 52.25	\$ 52
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
1	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 47
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
1	0.900	\$ 55.00	\$ 49.50	\$ -	\$ 49.50	\$ 50
2	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 94
2	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 94
2	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 94
1	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 47
1	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 47
1	0.850	\$ 55.00	\$ 46.75	\$ -	\$ 46.75	\$ 47
1	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 12
1	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 12
6	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 73
3	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 41
7	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 96
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
2	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 31
2	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 31
1	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 15
4	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 62
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
10	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 121
12	0.200	\$ 55.00	\$ 11.00	\$ -	\$ 11.00	\$ 132
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
2	0.045	\$ 55.00	\$ 2.48	\$ -	\$ 2.48	\$ 5
3	0.045	\$ 55.00	\$ 2.48	\$ -	\$ 2.48	\$ 7
8	0.200	\$ 55.00	\$ 11.00	\$ -	\$ 11.00	\$ 88
6	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 73
36	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 436
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
1	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 12
1	0.200	\$ 55.00	\$ 11.00	\$ -	\$ 11.00	\$ 11
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.700	\$ 55.00	\$ 38.50	\$ -	\$ 38.50	\$ 39
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
1	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 44
4	0.800	\$ 55.00	\$ 44.00	\$ -	\$ 44.00	\$ 176
2	0.750	\$ 55.00	\$ 41.25	\$ -	\$ 41.25	\$ 83
4	0.750	\$ 55.00	\$ 41.25	\$ -	\$ 41.25	\$ 165
7	0.300	\$ 55.00	\$ 16.50	\$ -	\$ 16.50	\$ 116
1	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 15
3	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 36
2	0.200	\$ 55.00	\$ 11.00	\$ -	\$ 11.00	\$ 22
2	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 24
4	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 48
1	0.450	\$ 55.00	\$ 24.75	\$ -	\$ 24.75	\$ 25
1	0.400	\$ 55.00	\$ 22.00	\$ -	\$ 22.00	\$ 22
2	0.400	\$ 55.00	\$ 22.00	\$ -	\$ 22.00	\$ 44
1	0.350	\$ 55.00	\$ 19.25	\$ -	\$ 19.25	\$ 19
1	0.450	\$ 55.00	\$ 24.75	\$ -	\$ 24.75	\$ 25
1	0.450	\$ 55.00	\$ 24.75	\$ -	\$ 24.75	\$ 25

2	0.300	\$ 55.00	\$ 16.50	\$ -	\$ 16.50	\$ 33
2	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 28
1	0.400	\$ 55.00	\$ 22.00	\$ -	\$ 22.00	\$ 22
1	0.250	\$ 55.00	\$ 13.75	\$ -	\$ 13.75	\$ 14
1	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 15
1	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 12
1	0.280	\$ 55.00	\$ 15.40	\$ -	\$ 15.40	\$ 15

DETAILED BREAKDOWN OF ITEMS

Project ID:

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
206			V8: Valley Truss (6 LF)	EA	1	0%
			STAIRS			
207			(3'-8" Wide) Wood Stairs - Risers: 36 EA - (7'-4"x3'-8") Stair Landing: 2 EA	EA	1	0%
OVERHEAD AND PROFIT						
INSURANCE						
CONTINGENCY						
TAX						
SUGGESTED BID						

Date:

QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
1	0.220	\$ 55.00	\$ 12.10	\$ -	\$ 12.10	\$ 12
1	16.250	\$ 55.00	\$ 893.75	\$ -	\$ 893.75	\$ 894
					SUBTOTAL	\$ 38,138
PROJECTED COST						\$51,838
					20%	\$10,368
					3%	\$1,555
					5%	\$2,592
					0%	\$0
						\$66,352