

GENERAL SUMMARY

Prepared for:
Project ID:
Scope: Masonry
No. Of Floors: 2
Date:

BUILDING GSF		15,440	
Lower Level Floor (SF)		8160	
Upper Level Floor (SF)		7280	
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ 54,500	\$ 3.53
4000	Masonry	\$ 169,224	\$ 10.96
TOTAL TRADE COST		\$ 223,724	\$ 14
OVERHEAD AND PROFIT		15%	\$ 2.17
INSURANCE		3%	\$ 0
CONTINGENCY		5%	\$ 1
TAX		8.8%	\$ 1
SUGGESTED BID		\$ 285,582	\$ 19



\$160,000
\$140,000
\$120,000
\$100,000
\$80,000
\$60,000
\$40,000
\$20,000

\$180,000
\$-

DIVISION COST COMPARISON

General Requirements Masonry

General Requirements Masonry

DETAILED BREAKDOWN OF ITEMS

Prepared for: Masonry
Project ID: Scope:

SR #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST
GENERAL REQUIREMENTS									
1	Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
2	Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
3	Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
4	Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
5	Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
6	Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -
7	Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -

Date:

UNIT COST	SUB COST
	\$ -
\$ 25,000.00	\$ 25,000.00
\$ 2,500.00	\$ 2,500.00
\$ 2,500.00	\$ 2,500.00
\$ 15,500.00	\$ 15,500.00
\$ 6,000.00	\$ 6,000.00
\$ 3,000.00	\$ 3,000
SUBTOTAL	\$ 54,500

DETAILED BREAKDOWN OF ITEMS

Prepared for: Masonry
Project ID: Scope:

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
MASONRY						
			MASONRY WALL			
			CMU STEM WALL			
1	S2.1	A4/S4.1, B4/S4.1	MW1 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (40 LF)	SF	53	10%
2			Grouting	CY	1	10%
3			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (40 LF)	LBS	41	10%
4			Excavation	CY	3	10%
5			Backfill	CY	2	10%
6		A3/S4.1, A4/S4.1, B4/S4.1	MW2 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (188 LF)	SF	250	10%
7			Grouting	CY	5	10%
8			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (188 LF)	LBS	196	10%
9			Excavation	CY	16	10%
10			Backfill	CY	9	10%
11		A3/S4.1	MW5 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (13 LF)	SF	17	10%
12			Grouting	CY	0.31	10%
13			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (13 LF)	LBS	13	10%
14			Excavation	CY	1.1	10%
15			Backfill	CY	0.7	10%
16		A3/S4.1	MW6 - 0'-8" Wide & 1'-4" High, CMU Stem Wall : (6 LF)	SF	8	10%
17			Grouting	CY	5	10%
18			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (6 LF)	LBS	6	10%
19			Excavation	CY	1	10%
20			Backfill	CY	0.38	10%
21		A2/S4.1, C3/S4.2	0'-8" Wide & 0'-8" High, CMU Stem Wall : (131 LF)	SF	88	10%
22			Solid Grouting	CY	2	10%
23			Horizontal Reinforcement (1) #4 Bars @ Bond Beam : (131 LF)	LBS	88	10%
24			Excavation	CY	5	10%
25			Backfill	CY	3	10%
26		A3/S4.2	0'-8" Wide & 1'-0" High, CMU Stem Wall : (112 LF)	SF	112	10%
27			Solid Grouting	CY	3	10%
28			Horizontal Reinforcement (1) #4 Bars @ Bond Beam : (112 LF)	LBS	75	10%
29			Excavation	CY	7	10%
30			Backfill	CY	4	10%
31		A3/S4.2	0'-12" Wide & 1'-9" High, CMU Stem Wall : (210 LF)	SF	367	10%
32			Solid Grouting	CY	11	10%
33			Horizontal Reinforcement (2) #5 Bars @ Bond Beam : (210 LF)	LBS	438	10%
34			Excavation	CY	27	10%
35			Backfill	CY	14	10%
			CMU WALL AT LOWER LEVEL			
36		C3/S1.5	Tag W17 - (8"x8"x16") CMU Wall At (12'-4" H) : (59 LF)	SF	724	10%
37			Vertical Reinforcement #5 @ 8" O.C: (1086 LF)	LBS	1132	10%
38			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (59 LF)	LBS	59	10%
39			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	724	10%
40			Solid Grouting	CY	13	10%
41		C3/S1.5	Tag W18 - (8"x8"x16") CMU Wall At (12'-4" H) : (17 LF)	SF	205	10%
42			Vertical Reinforcement #5 @ 8" O.C: (306 LF)	LBS	320	10%
43			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (17 LF)	LBS	17	10%
44			Solid Grouting	CY	4	10%
45			Tag W19 - (8"x8"x16") CMU Wall At (12'-4" H) : (67 LF)	SF	826	10%
46		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (1233 LF)	LBS	1286	10%
47			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (67 LF)	LBS	67	10%

Date:

QUANTITY W/ WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
58	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 516
1	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 270
46	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 83
4	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 57
2	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 45
275	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 2,441
5	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,277
216	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 393
17	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 266
10	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 204
18	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 163
0.34	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 85
14	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 26
1.2	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 19
0.8	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 15
9	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 79
5	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,277
7	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 13
1	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 10
0.42	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 8
97	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 856
2	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 448
96	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 175
6	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 94
4	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 72
123	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 1,093
4	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 949
82	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 150
8	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 120
5	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 91
403	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 3,577
12	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 3,113
482	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 877
30	0.324	\$ 48.00	\$ 15.55	\$ -	\$ 15.55	\$ 468
15	0.410	\$ 48.00	\$ 19.68	\$ -	\$ 19.68	\$ 297
796	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 7,062
1246	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 2,267
65	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 118
796	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 828
15	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 3,712
226	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 2,003
352	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 640
19	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 34
4	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,048
909	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 8,060
1415	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 2,575
74	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 134

DETAILED BREAKDOWN OF ITEMS

Prepared for:
Project ID:
Scope: Masonry

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE
48	A-305, A-306		Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	826	10%
49			Solid Grouting	CY	15	10%
50			Tag W19 - (8"x8"x16") CMU Wall At (9'-0" H) : (42 LF)	SF	376	10%
51		B3/S1.5	Vertical Reinforcement #5 @ 16" O.C: (283 LF)	LBS	295	10%
52			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (67 LF)	LBS	42	10%
53			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	376	10%
54			Solid Grouting	CY	15	10%
55			Tag W20 - (8"x10"x16") CMU Wall At (12'-4" H) : (26 LF)	SF	321	10%
56		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (478 LF)	LBS	499	10%
57			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (26 LF)	LBS	26	10%
58			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	321	10%
59			Solid Grouting	CY	8	10%
60			Tag W21 - (8"x12"x16") CMU Wall At (12'-4" H) : (109 LF)	SF	1344	10%
61		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (2006 LF)	LBS	2092	10%
62			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (109 LF)	LBS	109	10%
63			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	1344	10%
64			Solid Grouting	CY	41	10%
65			Tag W21 - (8"x12"x16") CMU Wall At (4'-0" H) : (41 LF)	SF	165	10%
66		A4/S1.5	Vertical Reinforcement #5 @ 48" O.C: (41 LF)	LBS	133	10%
67			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (41 LF)	LBS	41	10%
68			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	165	10%
69			Solid Grouting	CY	5	10%
70			Tag W22 - (8"x12"x16") CMU Wall At (12'-4" H) : (14 LF)	SF	173	10%
71		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (258 LF)	LBS	269	10%
72			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (14 LF)	LBS	14	10%
73			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	173	10%
74			Solid Grouting	CY	5	10%
75			Tag W23 - (8"x10"x16") CMU Wall At (12'-4" H) : (11 LF)	SF	141	10%
76		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (210 LF)	LBS	219	10%
77			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (11 LF)	LBS	11	10%
78			Solid Grouting	CY	3	10%
79			Tag W24 - (8"x12"x16") CMU Wall At (12'-4" H) : (38 LF)	SF	472	10%
80		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (704 LF)	LBS	734	10%
81			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (38 LF)	LBS	38	10%
82			Solid Grouting	CY	9	10%
			CMU WALL AT UPPER LEVEL			
83	A-307, A-308		Tag W17 - (8"x8"x16") CMU Wall At (12'-0" H) : (76 LF)	SF	906	10%
84		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (1361 LF)	LBS	1411	10%
85			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (76 LF)	LBS	76	10%
86			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	906	10%
87			Solid Grouting	CY	17	10%
88			Tag W19 - (8"x8"x16") CMU Wall At (12'-0" H) : (53 LF)	SF	637	10%
89		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (951 LF)	LBS	992	10%
90			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (53 LF)	LBS	53	10%
91			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	637	10%
92			Solid Grouting	CY	12	10%
93			Tag W22 - (8"x12"x16") CMU Wall At (12'-0" H) : (14 LF)	SF	170	10%
94			Vertical Reinforcement #5 @ 8" O.C: (254 LF)	LBS	265	10%
95		C3/S1.5	Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (14 LF)	LBS	14	10%
96			Siloxa-Tex 8500 Ghost Shield Sealer On Exterior Side	SF	170	10%
97			Solid Grouting	CY	5	10%
98			Tag W28 - (8"x8"x16") CMU Wall At (12'-0" H) : (8 LF)	SF	100	10%
99		C3/S1.5	Vertical Reinforcement #5 @ 8" O.C: (143 LF)	LBS	156	10%
100			Horizontal Reinforcement (1) #5 Bars @ Bond Beam : (8 LF)	LBS	8	10%
101			Solid Grouting	CY	2	10%
			CONTROL JOINT			
102	S2.1, A305 To A308	Plan Notes	Control Joint @ 24'-0" O.C. At Masonry Walls	LF	311	10%
			EXTRA REINFORCEMENT			
103	S2.1	Key Notes/S2.1	Tag 106: (2) #5, 8 EA, Vertical Bars @ 12'-4" H Walls.(197 LF)	LBS	206	10%
104			Tag 106: (2) #5, 1EA, Vertical Bars @ 12'-0" H Walls.(24 LF)	LBS	25	10%
105			Tag 107: (4) #5, 5 EA, Vertical Bars @ 12'-4" H Walls.(247 LF)	LBS	257	10%
106			Tag 107: (4) #5, 3 EA, Vertical Bars @ 12'-0" H Walls.(144 LF)	LBS	150	10%
107			Tag 112: (8) #6, 5 EA, Vertical Bars @ 12'-4" H Walls.(493 LF)	LBS	514	10%
108			Tag 113: (6) #6, 2 EA, Vertical Bars @ 12'-4" H Walls.(148 LF)	LBS	154	10%
			MASONRY LINTELS			
109	A-305-308	Masonry Lintels	8" W x 16" Deep CMU Grout Filled Lintel	LF	16	10%
110		Schedule / S1.3	Main Reinforcement (2) #5 Continuous Bottom Bars (32 LF)	LBS	33	10%

111			8" W x 32" Deep CMU Grout Filled Lintel	LF	22	10%
112			Main Reinforcement (2) #5 Continuous Bottom Bars (44 LF)	LBS	67	10%
			Note: (1)-Masonry Details: Superlite Color Integrated Block. Color Opal. (2)-Hollow Concrete Masonry Units Should Be Of 2000 PSI Compressive Strength.			
OVERHEAD AND PROFIT						
INSURANCE						
CONTINGENCY						
TAX						
SUGGESTED BID						

Date:

QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
909	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 945
17	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 4,215
414	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 3,673
325	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 591
46	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 84
414	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 431
17	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 4,215
353	0.120	\$ 52.00	\$ 6.24	\$ 4.25	\$ 10.49	\$ 3,699
549	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 999
29	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 52
353	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 367
9	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 2,192
1478	0.145	\$ 52.00	\$ 7.54	\$ 5.45	\$ 12.99	\$ 19,204
2301	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 4,189
120	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 218
1478	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 1,538
45	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 11,384
181	0.145	\$ 52.00	\$ 7.54	\$ 5.45	\$ 12.99	\$ 2,356
146	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 265
45	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 83
181	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 189
6	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,397
190	0.145	\$ 52.00	\$ 7.54	\$ 5.45	\$ 12.99	\$ 2,467
296	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 538
15	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 28
190	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 197
6	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,462
155	0.120	\$ 52.00	\$ 6.24	\$ 4.25	\$ 10.49	\$ 1,626
241	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 439
13	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 23
4	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 964
519	0.145	\$ 52.00	\$ 7.54	\$ 5.45	\$ 12.99	\$ 6,739
808	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 1,470
42	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 77
10	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 2,407
997	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 8,845
1552	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 2,825
83	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 151
997	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 1,037
18	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 4,626
701	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 6,216
1091	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 1,985
58	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 106
701	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 729
13	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 3,251
187	0.145	\$ 52.00	\$ 7.54	\$ 5.45	\$ 12.99	\$ 2,430
291	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 530
16	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 28
187	0.010	\$ 52.00	\$ 0.52	\$ 0.52	\$ 1.04	\$ 195
6	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 1,440
110	0.110	\$ 52.00	\$ 5.72	\$ 3.15	\$ 8.87	\$ 979
172	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 313
9	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 17
2	1.250	\$ 68.00	\$ 85.00	\$ 165.50	\$ 250.50	\$ 512
342	0.012	\$ 52.00	\$ 0.62	\$ 1.20	\$ 1.82	\$ 623
226	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 412
28	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 50
283	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 515
165	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 301
566	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 1,030
170	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 309
18	0.119	\$ 52.00	\$ 6.19	\$ 5.42	\$ 11.61	\$ 204
37	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 67

24	0.210	\$ 52.00	\$ 10.92	\$ 11.20	\$ 22.12	\$ 535
73	0.015	\$ 58.00	\$ 0.87	\$ 0.95	\$ 1.82	\$ 134
SUBTOTAL						\$ 169,224
PROJECTED COST						\$169,224
					15%	\$25,384
					3%	\$5,077
					5%	\$8,461
					8.8%	\$7,276
						\$215,421