

GENERAL SUMMARY

Prepared for:
Project ID:
Scope: Paint
No. Of Floors: 1
Date: 20-Sep-24

BUILDING GSF 3,458

DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)
1000	General Requirements	\$ -	\$ -
9000	Finishes	\$ 6,830	\$ 1.98
TOTAL TRADE COST		\$ 6,830	\$ 2
PROFIT	25%	\$ 1,707	\$ 0.49
OVERHEAD ON MATERIA	10%	\$ 300	\$ 0
CONTINGENCY	5%	\$ 341	\$ 0
TAX	6%	\$ 165	\$ 0
SUGGESTED BID		\$ 9,344	\$ 3



DETAILED BREAKDOWN OF ITEMS		
Prepared for: Project ID: Scope: Paint	TOTAL TRADE COST	\$6,830
	OH & PROFIT	\$2,008
	INSURANCE	
	CONTINGENCY	\$341
	TAX	\$165
	SUGGESTED BID	\$9,344
		Date: 20-Sep-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/WASTAGE	UNIT MANHOURL	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST	
GENERAL REQUIREMENTS														
1			Permits	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
2			Supervision and Coordination	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
3			Submittals and Shop drawings	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
4			Final Cleaning	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
5			Delivery of Material	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
6			Temporary Control & Facilities	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
7			Scaffolding	LS	1	0%	1	0.00	0.00	\$ -	\$ -	\$ -	\$ -	
SUBTOTAL												\$	-	
FINISHES														
			PAINTING											
			WALL PAINT											
8		Plane Notes/ A201	PT-01: Paint @ Wall -MFR.: Benjamin Moore -Color: Harbor Gray Ac-25; -Finish: Aura Eggshell-Ultra Base	SF	2810	10%	3091	0.015	\$ 50.00	\$ 0.75	\$ 0.62	\$ 1.37	\$ 4,237	
9			PT-02: Paint @ Wall -MFR.: Benjamin Moore -Color: Decorators White CC-20; -Finish: Aura Eggshell	SF	1150	10%	1265	0.015	\$ 50.00	\$ 0.75	\$ 0.62	\$ 1.37	\$ 1,734	
				SOFFIT PAINT										
10	A000			PT-01: Paint @ Wall -MFR.: Benjamin Moore -Color: Harbor Gray Ac-25; -Finish: Aura Eggshell-Ultra Base	SF	23	10%	25	0.020	\$ 50.00	\$ 1.00	\$ 0.62	\$ 1.62	\$ 41
			DOOR PAINT											
11		Plane Notes #12/ A000	Paint @ Existing Door (2'-6" x 5'-0") -Sand, Seal & Recoat	EA	7	10%	8	0.630	\$ 50.00	\$ 31.50	\$ 15.50	\$ 47.00	\$ 362	
12			Paint @ Door (2'-6" x 6'-8") -Assume	EA	1	10%	1	0.750	\$ 50.00	\$ 37.50	\$ 21.70	\$ 59.20	\$ 65	
			TRIM PAINT											
13		Plane Notes #12/ A000	Paint @ Door Trim -Matte & Clear Finish	LF	254	10%	279	0.018	\$ 50.00	\$ 0.90	\$ 0.50	\$ 1.40	\$ 391	
SUBTOTAL												\$	6,830	
PROJECTED COST												\$6,830		
PROFIT											25%	\$1,707		
OVERHEAD ON MATERIAL											10%	\$300		
CONTINGENCY											5%	\$341		
TAX											6%	\$165		

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID:

Scope:	Paint
--------	-------

TOTAL TRADE COST	\$6,830
OH & PROFIT	\$2,008
INSURANCE	
CONTINGENCY	\$341
TAX	\$165
SUGGESTED BID	\$9,344

Date: 20-Sep-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTIT Y	WASTAG E	QUANTITY W/WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
SUGGESTED BID													\$9,344