

GENERAL SUMMARY			
Prepared for: Project ID: Scope:	X.Y.Z.	No. Of Floors: 4	
Date: Total GSF	Everything 7-Feb-22		
Cellar Floor 1st Level 2nd Level	4075		
3rd Level	1085		
	1010		
	1000		
	980		
DIVISION NO.	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST
1000	General Requirements	\$ 114,043	\$ 27.99
2000	Demolition/Site Work	\$ 21,174	\$ 5.20
3000	Concrete	\$ 25,860	\$ 6.35
4000	Masonry	\$ 11,340	\$ 2.78
5000	Metals	\$ 29,016	\$ 7.12
6000	Wood Plastics And Compoites	\$ 93,938	\$ 23.05
7000	Thermal and Moisture Protection	\$ 24,150	\$ 5.93
8000	Openings	\$ 56,920	\$ 13.97
9000	Finishes	\$ 230,135	\$ 56.47
10000	Specialities	\$ 31,739	\$ 7.79
11000	Equipment	\$ 15,300	\$ 3.75
22000	Plumbing	\$ 39,289	\$ 9.64
23000	Hvac/Mechanical	\$ 22,628	\$ 5.55
26000	Electrical	\$ 55,115	\$ 13.53
TOTAL TRADE COST		\$ 770,647	\$ 189
OVERHEAD AND PROFIT	20%	\$ 154,129	\$ 38
INSURANCE CONTINGENCY	3%	\$ 23,119	\$ 6
TAX	7%	\$ 53,945	\$ 13
	7%	\$ 53,945	\$ 13
TOTAL TRADE COST		\$ 1,055,786	\$ 259

DETAILED BREAKDOWN OF ITEMS

SR #	REF. DWG.	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST
GENERAL REQUIREMENTS								
1		Permits	LS	1	0%	1	\$ -	\$ -
2		Supervision and Coordination	LS	1	0%	1	\$ -	\$ -
3		Submittals and Shop drawings	LS	1	0%	1	\$ -	\$ -
4		Final Cleaning	LS	1	0%	1	\$ -	\$ -
5		Mobilization Costs	LS	1	0%	1	\$ -	\$ -
6		Temporary Control & Facilities	LS	1	0%	1	\$ -	\$ -
7		Scaffolding	SF	2890	0%	2890	\$ 2.10	\$ 0.60

EXISTING CONDITIONS/SITE WORK

		Demolition						
		Cellar Level						
8		Remove Wall Structure	LF	36	0%	36	\$ 3.20	\$ -
9		Remove Partition Wall	SF	375	0%	375	\$ 1.50	\$ -
10		Remove Stairs	SF	21	0%	21	\$ 2.00	\$ -
		1st Level						
11		Remove Wall Structure	LF	50	0%	50	\$ 3.20	\$ -
12		Remove Partition Wall	SF	281	0%	281	\$ 1.50	\$ -
13		Remove Stairs	SF	63	0%	63	\$ 2.00	\$ -
		2nd Level						
14		Remove Wall Structure	LF	53	0%	53	\$ 3.20	\$ -
15		Remove Partition Wall	SF	504	0%	504	\$ 1.50	\$ -
16		Remove Stairs	SF	40	0%	40	\$ 2.00	\$ -
		Site Work						
17		SOD Ground Covering	SF	803	0%	803	\$ 1.30	\$ 2.30
18		(9'x19') Parking Pad (2 EA)	SF	342	0%	342	\$ 1.80	\$ 3.20
19		(6' High) Construction Fencing W/ Dust Screening And (42" High) Silt Fence	LF	225	0%	225	\$ 6.48	\$ 11.52
20		Brick Bat Ground	SF	2499	0%	2499	\$ 0.86	\$ 1.54
21		(4" Thick) Crushed Gravels	SF	969	0%	969	\$ 0.72	\$ 1.28
		Earth Work						
22		Compacted Earth Fill	SF	38	0%	38	\$ 12.00	\$ -
23		Uncompacted Potting Soil Back Fill	SF	19	0%	19	\$ 16.00	\$ -
		Excavation						
24		Excavation @ Footing	CY	31	0%	31	\$ 45.00	\$ -

CONCRETE

		Foundation						
		Concrete Footing						
25		(2'-8"x1'-0") Cont. Concrete Footing Reinforced W/ (#4) Rebar @ 12" O.C.	CY	17.2	0%	17	\$ 230.40	\$ 409.60
26		(18"x18"x1'-0") Isolated Concrete Footing Pier Reinforced W/ (#4) Rebar @ 12" O.C.	CY	0.3	0%	0	\$ 230.40	\$ 409.60
27		(1'-0"x2'-4") Cont. Concrete Underpinning Pier Reinforced W/ (2)#4 Rebar @ 12" O.C.	CY	7.1	0%	7	\$ 230.40	\$ 409.60
28		(2'-0"x1'-0") Cont. Concrete Footing Reinforced W/ (#4) Rebar @ 12" O.C.	CY	3.1	0%	3	\$ 230.40	\$ 409.60
		Concrete Slab						
29		(1'-0" Thick) Concrete Raft Footing Reinforced W/ (#4) Rebar @ 12" O.C.	CY	3.185	0%	3	\$ 230.40	\$ 409.60
30		(4" Thick) Concrete Slab On Grade W/ #6 WWF	SF	969	0%	969	\$ 2.16	\$ 3.84
		Concrete Cap						
31		Precast Concrete Wall Cap	LF	11	0%	11	\$ 7.92	\$ 14.08

MASONRY

		CMU Wall						
32		(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (1'-2" H)	SF	13	0%	13	\$ 5.04	\$ 8.96
33		(6" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (2'-0" H)	SF	22	0%	22	\$ 3.60	\$ 6.40
34		(6" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (3'-10" H)	SF	77	0%	77	\$ 3.60	\$ 6.40
35		(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (3'-9" H)	SF	55	0%	55	\$ 5.04	\$ 8.96
36		(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (7'-0" H)	SF	24	0%	24	\$ 5.04	\$ 8.96
37		(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (5'-0" H)	SF	69	0%	69	\$ 5.04	\$ 8.96

38	(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (4'-9" H)	SF	65	0%	65	\$ 5.04	\$ 8.96
39	(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (6'-0" H)	SF	193	0%	193	\$ 5.04	\$ 8.96
40	(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (2'-0" H)	SF	42	0%	42	\$ 5.04	\$ 8.96
41	(4" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (2'-10" H)	SF	95	0%	95	\$ 2.88	\$ 5.12
42	(8" Thick) CMU Wall Reinforced W/ #4 Rebars @ 16" O.C. In Grouted Cells (9'-0" H)	SF	224	0%	224	\$ 5.04	\$ 8.96

METALS

	Framing						
	Cellar Level						
43	Galv. Steel Base Plate	EA	4	0%	4	\$ 46.80	\$ 83.20
	1st Level						
44	(1/2" Dia x 6") LAG Bolt/ Screws	EA	9	0%	9	\$ 5.04	\$ 8.96
45	Simpson Heavy Duty	EA	89	0%	89	\$ 16.20	\$ 28.80
	Steel Angle						
46	(3x3x5/8) Steel Angle (3 LF)	Lbs	21.51	0%	22	\$ 2.16	\$ 3.84
47	(3-1/2"x3-1/2"x5/8) Steel Angle (24 LF)	Lbs	173.52	0%	174	\$ 2.16	\$ 3.84
48	(4x6x5/8) Steel Angle (16 LF)	Lbs	227.2	0%	227	\$ 2.16	\$ 3.84
49	Simpson Heavy Duty	EA	92	0%	92	\$ 16.20	\$ 28.80
50	Galv. Steel Base Plate	EA	4	0%	4	\$ 46.80	\$ 83.20
	2nd Level						
51	Simpson Heavy Duty	EA	90	0%	90	\$ 16.20	\$ 28.80
	Steel Angle						
52	(3x3x5/8) Steel Angle (10 LF)	Lbs	71.7	0%	72	\$ 2.16	\$ 3.84
53	(6x6x5/8) Steel Angle (24 LF)	Lbs	357.6	0%	358	\$ 2.16	\$ 3.84
54	(3-1/2"x3-1/2"x5/8) Steel Angle (18 LF)	Lbs	130.14	0%	130	\$ 2.16	\$ 3.84
55	Galv. Steel Base Plate	EA	8	0%	8	\$ 46.80	\$ 83.20
	3rd Level						
56	Simpson Heavy Duty	EA	94	0%	94	\$ 16.20	\$ 28.80
57	(3-1/2"x3-1/2"x5/8) Steel Angle (30 LF)	Lbs	216.9	0%	217	\$ 2.16	\$ 3.84
58	(6x6x5/8) Steel Angle (27 LF)	Lbs	402.3	0%	402	\$ 2.16	\$ 3.84
59	Galv. Steel Base Plate	EA	6	0%	6	\$ 46.80	\$ 83.20

WOOD, PLASTICS AND COMPOSITES

	Framing						
	Cellar Level						
	Post						
60	(4x8) PSL Post W/ Galv. Steel Base Plate (8'-3" H) (4	LF	33	0%	33	\$ 5.76	\$ 10.24
61	Stair Assembly (11" Wide) Tread (18 EA) (7-1/2" High) Riser (19 EA) (2x) Stringer (36 LF) Landing Area (9 SF)	LOC	1	0%	1	\$ 900.00	\$ 1,600.00
	1st Level						
	Floor Trusses						
62	(4x12) Open Web Trusses @ 16" O.C.	SF	222	0%	222	\$ 4.68	\$ 8.32
63	(4x12) Open Web Trusses @ 19" O.C.	SF	614	0%	614	\$ 4.32	\$ 7.68
64	(4x12) Open Web Truss	LF	115	0%	115	\$ 5.76	\$ 10.24
	Joists						
65	(2x10) Joist	LF	11	0%	11	\$ 5.04	\$ 8.96
66	(2x10) Joist @ 16" O.C. (17 SF)	SF	13	0%	13	\$ 3.60	\$ 6.40
67	(2x10) P.T. Joist Sistered @ 16" O.C. (204 SF)	SF	154	0%	154	\$ 3.60	\$ 6.40
68	(2x10) P.T. Rim Joist	LF	43	0%	43	\$ 4.32	\$ 7.68
69	(1-1/4"x13-7/8") TJI Rim Joist Cont.	LF	36	0%	36	\$ 3.60	\$ 6.40
	Plywood Sheathing						
70	(3/4") Plywood Sheathing	SF	853	0%	853	\$ 1.08	\$ 1.92
71	(1-1/4"x6") P.T. Cementitious Deck	SF	204	0%	204	\$ 1.80	\$ 3.20
	Beams						
72	(2x12) PT Beam	LF	56	0%	56	\$ 5.40	\$ 9.60
73	(1-3/4"x14") LVL Band Beam	LF	30	0%	30	\$ 5.76	\$ 10.24
74	(2x10) LVL Header	LF	29	0%	29	\$ 4.32	\$ 7.68
75	(2x12) P.T. Ledger	LF	15	0%	15	\$ 5.04	\$ 8.96
	Post						
76	(6x6) Post (9'-0" H) (4 EA)	LF	36	0%	36	\$ 6.48	\$ 11.52
77	Stair Assembly (11" Wide) Tread (21 EA) (7-1/2" High) Riser (22 EA) (2x) Stringer (50 LF) Landing Area (26 SF)	LOC	1	0%	1	\$ 972.00	\$ 1,728.00
	2nd Level						
	Floor Trusses						
78	(4x12) Open Web Trusses @ 19" O.C.	SF	590	0%	590	\$ 4.32	\$ 7.68
79	(4x12) Open Web Trusses @ 16" O.C.	SF	234	0%	234	\$ 4.68	\$ 8.32
	Joists						
80	(2x10) PT Joist @ 24" O.C. (186 SF)	SF	93	0%	93	\$ 3.60	\$ 6.40
81	(2x8) Joists	LF	41	0%	41	\$ 3.60	\$ 6.40

		Plywood Sheathing					
82		(3/4") Plywood Sheathing	SF	1009	0%	1009	\$ 1.08 \$ 1.92
		Beams					
83		(2x10) P.T. Band Beam	LF	44	0%	44	\$ 4.68 \$ 8.32
84		(1-3/4"x8") LVL Band Beam	LF	24	0%	24	\$ 3.60 \$ 6.40
85		(1-3/4"x14") LVL Beam	LF	54	0%	54	\$ 5.76 \$ 10.24
86		(4x12) Open Web Truss	LF	87	0%	87	\$ 5.76 \$ 10.24
87		(1-1/4"x13-7/8") TJI Rim Joist Cont.	LF	26	0%	26	\$ 4.32 \$ 7.68
88		(1-3/4"x14") LVL Band Beam	LF	30	0%	30	\$ 5.76 \$ 10.24
		Post					
89		(4x8) PSL Post W/ Galv. Steel Base Plate (9'-0" H) (5	LF	45	0%	45	\$ 5.76 \$ 10.24
90		(4x4) PSL Post W/ Galv. Steel Base Plate (9'-0" H) (3	LF	27	0%	27	\$ 4.32 \$ 7.68
91		Stair Assembly (11" Wide) Tread (15 EA) (7-1/2" High) Riser (16 EA) (2x) Stringer (30 LF) Landing Area (7 SF)	LOC	1	0%	1	\$ 792.00 \$ 1,408.00
		3rd Level					
		Floor Trusses					
92		(4x12) Open Web Trusses @ 19" O.C.	SF	523	0%	523	\$ 4.32 \$ 7.68
93		(4x12) Open Web Trusses @ 16" O.C.	SF	338	0%	338	\$ 4.68 \$ 8.32
94		(4x12) Open Web Truss	LF	184	0%	184	\$ 5.76 \$ 10.24
		Plywood Sheathing					
95		(3/4") Plywood Sheathing	SF	888	0%	888	\$ 1.08 \$ 1.92
		Beams					
96		(1-1/4"x13-7/8") TJI Rim Joist Cont.	LF	35	0%	35	\$ 4.32 \$ 7.68
97		(1-3/4"x14") LVL Beam	LF	58	0%	58	\$ 5.76 \$ 10.24
98		(2x10) LVL Header	LF	39	0%	39	\$ 4.32 \$ 7.68
99		(1-3/4"x14") LVL Band Beam	LF	89	0%	89	\$ 5.76 \$ 10.24
		Post					
100		(4x8) PSL Post (9'-0" H) (4 EA)	LF	36	0%	36	\$ 5.76 \$ 10.24
101		(4x4) PSL Post W (9'-0" H) (2 EA)	LF	18	0%	18	\$ 4.32 \$ 7.68
102		Stair Assembly (11" Wide) Tread (12 EA) (7-1/2" High) Riser (13 EA) (2x) Stringer (31 LF) Landing Area (10 SF)	LOC	1	0%	1	\$ 702.00 \$ 1,248.00
		Roof Level					
		Roof Trusses					
103		(4x12) Open Web Trusses @ 19" O.C.	SF	289	0%	289	\$ 4.32 \$ 7.68
104		(4x12) Open Web Trusses @ 16" O.C.	SF	519	0%	519	\$ 4.68 \$ 8.32
105		(4x12) Open Web Truss	LF	186	0%	186	\$ 5.76 \$ 10.24
		Beams					
106		(1-1/4"x13-7/8") TJI Rim Joist Cont.	LF	49	0%	49	\$ 4.32 \$ 7.68
107		(2x10) LVL Header	LF	70	0%	70	\$ 4.32 \$ 7.68
108		(2x10) Beam	LF	68	0%	68	\$ 4.68 \$ 8.32
		Post					
109		(4x8) PSL Post W/ Galv. Steel Base Plate (8'-6" H) (4	LF	34	0%	34	\$ 5.76 \$ 10.24
		Plywood Sheathing					
110		(3/4") Non Combustible Exterior Grade Sheathing	SF	842	0%	842	\$ 1.22 \$ 2.18
111		(1-1/4") Composite Roof Decking	SF	758	0%	758	\$ 2.16 \$ 3.84
THERMAL & MOISTURE PROTECTION							
		Waterproofing					
112		Waterproofing @ CMU Wall	SF	879	0%	879	\$ 0.65 \$ 1.15
		Vapor Barrier @ Underside Slab					
113		(6 Mill.) Polythene Vapor Barrier	SF	969	0%	969	\$ 0.70 \$ 1.25
		Insulation					
		1st Level					
114		(R-19) Batt Insulation	SF	853	0%	853	\$ 0.72 \$ 1.28
		2nd Level					
115		(R-19) Batt Insulation	SF	1009	0%	1009	\$ 0.72 \$ 1.28
		3rd Level					
116		(R-19) Batt Insulation	SF	888	0%	888	\$ 0.72 \$ 1.28
		Exterior					
117		Window Flashing	LF	630	0%	630	\$ 2.52 \$ 4.48
118		Door Flashing	LF	83	0%	83	\$ 2.52 \$ 4.48
		Roofing					
119		Built-Up Rubber Roof Membrane	SF	758	0%	758	\$ 0.76 \$ 1.34
120		(2") R-15 Min. Rigid Insulation	SF	758	0%	758	\$ 0.86 \$ 1.54
121		Metal Cap Flashing	LF	124	0%	124	\$ 3.60 \$ 6.40
122		Counter Flashing	LF	124	0%	124	\$ 2.88 \$ 5.12
123		Cont. Drip Edge Flashing	LF	124	0%	124	\$ 3.24 \$ 5.76
124		(12"x12"x1-3/4") LT.WT.Roof Pavers	EA	124	0%	124	\$ 5.04 \$ 8.96
125		Gutter	LF	126	0%	126	\$ 2.88 \$ 5.12
126		Scupper W/ (6" Dia) Downspout	LF	76	0%	76	\$ 3.24 \$ 5.76
OPENINGS							
		Unit A Cellar Level					
		Doors					

127	001 (6'-2"x6'-9") Full Glass Tempered W/ Wood Frame	EA	1	0%	1	\$ 432.00	\$ 768.00
128	(2'-8"x6'-8") Door W/ Frame	EA	3	0%	3	\$ 280.80	\$ 499.20
129	(2'-2"x6'-8") Door W/ Frame	EA	1	0%	1	\$ 252.00	\$ 448.00
130	(4'-0"x6'-8") Pan Door W/ Frame	EA	4	0%	4	\$ 345.60	\$ 614.40
	Door Hardware's						
131	Door Hardware's	EA	9	0%	9	\$ 86.40	\$ 153.60
	Windows						
132	001 (2'-11"x5'-0") Casement Type Window W/ Wood Frame	EA	4	0%	4	\$ 252.00	\$ 448.00
	Unit A 1st Level						
	Doors						
133	101 (3'-5"x8'-8") Full Glass Tempered W/ Glass Transom & Wood Frame	EA	1	0%	1	\$ 396.00	\$ 704.00
134	102 (9'-2"x7'-0") Full Glass Tempered W/ Wood Frame	EA	1	0%	1	\$ 504.00	\$ 896.00
135	103 (3'-5"x8'-8") Full Glass Tempered W/ Glass Transom & Wood Frame	EA	1	0%	1	\$ 460.80	\$ 819.20
136	(2'-8"x6'-8") Door W/ Frame	EA	1	0%	1	\$ 280.80	\$ 499.20
137	(3'-0"x6'-8") Double Door W/ Frame	EA	2	0%	2	\$ 316.80	\$ 563.20
	Door Hardware's						
138	Door Hardware's	EA	6	0%	6	\$ 86.40	\$ 153.60
	Windows						
139	101 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	8	0%	8	\$ 234.00	\$ 416.00
140	102 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	1	0%	1	\$ 234.00	\$ 416.00
141	103 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	1	0%	1	\$ 234.00	\$ 416.00
	Unit B 2nd Level						
	Doors						
142	(2'-3"x6'-8") Pan Door W/ Frame	EA	4	0%	4	\$ 270.00	\$ 480.00
	Door Hardware's						
143	Door Hardware's	EA	4	0%	4	\$ 86.40	\$ 153.60
	Windows						
144	200 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	2	0%	2	\$ 234.00	\$ 416.00
145	201 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	8	0%	8	\$ 234.00	\$ 416.00
146	202 (3'-4"x6'-2") Casement Type Window W/ Wood Frame	EA	2	0%	2	\$ 270.00	\$ 480.00
147	203 (3'-4"x6'-2") Casement Type Window W/ Wood Frame	EA	1	0%	1	\$ 270.00	\$ 480.00
148	204 (2'-6"x6'-2") Casement Type Window W/ Wood Frame	EA	3	0%	3	\$ 208.80	\$ 371.20
149	205 (2'-6"x1'-11") Casement Type Window W/ Wood Frame	EA	1	0%	1	\$ 151.20	\$ 268.80
	Unit B 3rd Level						
150	(2'-10"x6'-8") Pan Door W/ Frame	EA	1	0%	1	\$ 291.60	\$ 518.40
151	(2'-3"x6'-8") Pan Door W/ Frame	EA	2	0%	2	\$ 270.00	\$ 480.00
152	(3'-0"x7'-0") Door W/ Frame	EA	3	0%	3	\$ 331.20	\$ 588.80
153	(2'-3"x6'-8") Door W/ Frame	EA	1	0%	1	\$ 270.00	\$ 480.00
	Door Hardware's						
154	Door Hardware's	EA	7	0%	7	\$ 86.40	\$ 153.60
	Windows						
155	300 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	3	0%	3	\$ 234.00	\$ 416.00
156	301 (2'-8"x5'-0") Casement Type Window W/ Wood Frame	EA	6	0%	6	\$ 234.00	\$ 416.00
157	304 (2'-6"x5'-0") Casement Type Window W/ Wood Frame	EA	2	0%	2	\$ 180.00	\$ 320.00
158	305 (2'-6"x1'-11") Casement Type Window W/ Wood Frame	EA	1	0%	1	\$ 144.00	\$ 256.00
FINISHES							
	Partition Wall						
	Unit A Cellar Level						
	(6" Thick) Wall Type 6 (9' H) (118 LF)						

159	(2x6) Top And Bottom Plate	LF	236	0%	236	\$ 2.09	\$ 3.71
160	(2x6) Studs @ 16" O.C. (89 EA) (801 LF)	SF	1062	0%	1062	\$ 1.62	\$ 2.88
161	(5/8") 2 HR Fire Rated Type "X" Gypsum Board	SF	4248	0%	4248	\$ 0.97	\$ 1.73
162	R-19 Batt Insulation	SF	1062	0%	1062	\$ 0.61	\$ 1.09
163	Sealant	LF	472	0%	472	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5a (9' H) (129 LF)						
164	(2x6) Top And Bottom Plate	LF	258	0%	258	\$ 2.09	\$ 3.71
165	(2x6) Studs @ 16" O.C. (97 EA) (873 LF)	SF	1161	0%	1161	\$ 1.62	\$ 2.88
166	(5/8") 1 HR Fire Rated Type "X" Gypsum Board	SF	4248	0%	4248	\$ 0.94	\$ 1.66
167	(5/8") Non Combustible 1 HR Rated Exterior Grade Sheathing	SF	1161	0%	1161	\$ 1.15	\$ 2.05
168	Sealant	LF	258	0%	258	\$ 0.36	\$ 0.64
	Unit A 1st Level						
	(6" Thick) Wall Type 5 (9' H) (87 LF)						
169	(2x6) Top And Bottom Plate	LF	174	0%	174	\$ 2.09	\$ 3.71
170	(2x6) Studs @ 16" O.C. (66 EA) (594 LF)	SF	783	0%	783	\$ 1.62	\$ 2.88
171	(5/8") 1 HR Fire Rated Gypsum Board	SF	1566	0%	1566	\$ 0.86	\$ 1.54
172	(3") Mineral Wool Batting Insulation	SF	783	0%	783	\$ 0.68	\$ 1.22
173	Sealant	LF	348	0%	348	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 6 (9' H) (23 LF)						
174	(2x6) Top And Bottom Plate	LF	46	0%	46	\$ 2.09	\$ 3.71
175	(2x6) Studs @ 16" O.C. (18 EA) (162 LF)	SF	207	0%	207	\$ 1.62	\$ 2.88
176	(5/8") 2 HR Fire Rated Type "X" Gypsum Board	SF	828	0%	828	\$ 0.97	\$ 1.73
177	R-19 Batt Insulation	SF	207	0%	207	\$ 0.61	\$ 1.09
178	Sealant	LF	92	0%	92	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5a (9' H) (88 LF)						
179	(2x6) Top And Bottom Plate	LF	176	0%	176	\$ 2.09	\$ 3.71
180	(2x6) Studs @ 16" O.C. (67 EA) (603 LF)	SF	792	0%	792	\$ 1.62	\$ 2.88
181	(5/8") 1 HR Fire Rated Type "X" Gypsum Board	SF	792	0%	792	\$ 0.94	\$ 1.66
182	(5/8") Non Combustible 1 HR Rated Exterior Grade Sheathing	SF	792	0%	792	\$ 1.15	\$ 2.05
183	Sealant	LF	176	0%	176	\$ 0.36	\$ 0.64
	Unit B 2nd Level						
	(6" Thick) Wall Type 6 (9' H) (73 LF)						
184	(2x6) Top And Bottom Plate	LF	146	0%	146	\$ 2.09	\$ 3.71
185	(2x6) Studs @ 16" O.C. (55 EA) (495 LF)	SF	657	0%	657	\$ 1.62	\$ 2.88
186	(5/8") 2 HR Fire Rated Type "X" Gypsum Board	SF	2628	0%	2628	\$ 0.97	\$ 1.73
187	R-19 Batt Insulation	SF	657	0%	657	\$ 0.61	\$ 1.09
188	Sealant	LF	292	0%	292	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5 (9' H) (43 LF)						
189	(2x6) Top And Bottom Plate	LF	86	0%	86	\$ 2.09	\$ 3.71
190	(2x6) Studs @ 16" O.C. (33 EA) (297 LF)	SF	387	0%	387	\$ 1.62	\$ 2.88
191	(5/8") 1 HR Fire Rated Gypsum Board	SF	774	0%	774	\$ 0.86	\$ 1.54
192	(3") Mineral Wool Batting Insulation	SF	387	0%	387	\$ 0.68	\$ 1.22
193	Sealant	LF	172	0%	172	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5a (9' H) (92 LF)						
194	(2x6) Top And Bottom Plate	LF	184	0%	184	\$ 2.09	\$ 3.71
195	(2x6) Studs @ 16" O.C. (70 EA) (630 LF)	SF	828	0%	828	\$ 1.62	\$ 2.88
196	(5/8") 1 HR Fire Rated Type "X" Gypsum Board	SF	828	0%	828	\$ 0.94	\$ 1.66
197	(5/8") Non Combustible 1 HR Rated Exterior Grade Sheathing	SF	828	0%	828	\$ 1.15	\$ 2.05
198	Sealant	LF	184	0%	184	\$ 0.36	\$ 0.64
	Unit B 3rd Level						
	(6" Thick) Wall Type 6 (9' H) (118 LF)						
199	(2x6) Top And Bottom Plate	LF	236	0%	236	\$ 2.09	\$ 3.71
200	(2x6) Studs @ 16" O.C. (89 EA) (801 LF)	SF	1062	0%	1062	\$ 1.62	\$ 2.88
201	(5/8") 2 HR Fire Rated Type "X" Gypsum Board	SF	4248	0%	4248	\$ 0.97	\$ 1.73
202	R-19 Batt Insulation	SF	1062	0%	1062	\$ 0.61	\$ 1.09
203	Sealant	LF	472	0%	472	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5 (9' H) (131 LF)						
204	(2x6) Top And Bottom Plate	LF	262	0%	262	\$ 2.09	\$ 3.71
205	(2x6) Studs @ 16" O.C. (99 EA) (891 LF)	SF	1179	0%	1179	\$ 1.62	\$ 2.88
206	(5/8") 1 HR Fire Rated Gypsum Board	SF	2358	0%	2358	\$ 0.86	\$ 1.54
207	(3") Mineral Wool Batting Insulation	SF	1179	0%	1179	\$ 0.68	\$ 1.22
208	Sealant	LF	524	0%	524	\$ 0.36	\$ 0.64
	(6" Thick) Wall Type 5a (9' H) (26 LF)						
209	(2x6) Top And Bottom Plate	LF	52	0%	52	\$ 2.09	\$ 3.71
210	(2x6) Studs @ 16" O.C. (20 EA) (180 LF)	SF	234	0%	234	\$ 1.62	\$ 2.88
211	(5/8") 1 HR Fire Rated Type "X" Gypsum Board	SF	234	0%	234	\$ 0.94	\$ 1.66
212	(5/8") Non Combustible 1 HR Rated Exterior Grade Sheathing	SF	234	0%	234	\$ 1.15	\$ 2.05
213	Sealant	LF	52	0%	52	\$ 0.36	\$ 0.64
	Roof Level						
	(6" Thick) Wall Type 5 (3' H) (122 LF)						
214	(2x6) Top And Bottom Plate	LF	244	0%	244	\$ 2.09	\$ 3.71
215	(2x6) Studs @ 16" O.C. (92 EA) (276 LF)	SF	366	0%	366	\$ 1.62	\$ 2.88
216	(5/8") 1 HR Fire Rated Gypsum Board	SF	732	0%	732	\$ 0.86	\$ 1.54
217	(3") Mineral Wool Batting Insulation	SF	366	0%	366	\$ 0.68	\$ 1.22
218	Sealant	LF	488	0%	488	\$ 0.36	\$ 0.64
	Ceiling Gypsum Board						
	Unit A Cellar Level						

219	(5/8") Fire Rated Ceiling Gypsum Board (Double Layer)	SF	1524	0%	1524	\$ 1.01	\$ 1.79
	Unit A 1st Level						
220	(5/8") Fire Rated Ceiling Gypsum Board (Double Layer)	SF	1722	0%	1722	\$ 1.01	\$ 1.79
	Unit B 2nd Level						
221	(5/8") Fire Rated Ceiling Gypsum Board (Double Layer)	SF	1712	0%	1712	\$ 1.01	\$ 1.79
	Unit B 3rd Level						
222	(5/8") Fire Rated Ceiling Gypsum Board (Double Layer)	SF	1606	0%	1606	\$ 1.01	\$ 1.79
	Interior Finishes						
	Unit A Cellar Level						
223	(3/4") Hardwood Flooring	SF	710	0%	710	\$ 2.88	\$ 5.12
224	(6x6) Ceramic Tile	SF	118	0%	118	\$ 4.32	\$ 7.68
225	(12x12) Ceramic Tile	SF	46	0%	46	\$ 4.32	\$ 7.68
226	Wall Base	LF	264	0%	264	\$ 2.52	\$ 4.48
227	Ceramic Wall Tile	SF	58	0%	58	\$ 6.12	\$ 10.88
228	Wall Paint	SF	318	0%	318	\$ 0.47	\$ 0.83
	Unit A 1st Level						
229	(3/4") Hardwood Flooring	SF	855	0%	855	\$ 2.88	\$ 5.12
230	(6x6) Ceramic Tile	SF	16	0%	16	\$ 4.32	\$ 7.68
231	Wall Base	LF	194	0%	194	\$ 2.52	\$ 4.48
232	Ceramic Wall Tile	SF	16	0%	16	\$ 6.12	\$ 10.88
233	Wall Paint	SF	214	0%	214	\$ 0.47	\$ 0.83
	Unit B 2nd Level						
234	(3/4") Hardwood Flooring	SF	815	0%	815	\$ 2.88	\$ 5.12
235	(6x6) Ceramic Tile	SF	46	0%	46	\$ 4.32	\$ 7.68
236	Wall Base	LF	227	0%	227	\$ 2.52	\$ 4.48
237	Ceramic Wall Tile	SF	23	0%	23	\$ 6.12	\$ 10.88
238	Wall Paint	SF	245	0%	245	\$ 0.47	\$ 0.83
	Unit B 3rd Level						
239	(3/4") Hardwood Flooring	SF	562	0%	562	\$ 2.88	\$ 5.12
240	(12x12) Ceramic Tile	SF	128	0%	128	\$ 4.32	\$ 7.68
241	(6x6) Ceramic Tile	SF	118	0%	118	\$ 4.32	\$ 7.68
242	Wall Base	LF	249	0%	249	\$ 2.52	\$ 4.48
243	Ceramic Tile	SF	59	0%	59	\$ 4.32	\$ 7.68
244	Wall Paint	SF	284	0%	284	\$ 0.47	\$ 0.83
	Paint @ Ceiling Gypsum Board						
	Unit A Cellar Level						
245	Paint @ Ceiling Gypsum Board	SF	762	0%	762	\$ 0.61	\$ 1.09
	Unit A 1st Level						
246	Paint @ Ceiling Gypsum Board	SF	861	0%	861	\$ 0.61	\$ 1.09
	Unit B 2nd Level						
247	Paint @ Ceiling Gypsum Board	SF	856	0%	856	\$ 0.61	\$ 1.09
	Unit B 3rd Level						
248	Paint @ Ceiling Gypsum Board	SF	803	0%	803	\$ 0.61	\$ 1.09
	Openings Finish						
	Unit A Cellar Level						
249	Door Frame Paint	LF	153	0%	153	\$ 1.08	\$ 1.92
250	Door Paint	SF	217	0%	217	\$ 0.72	\$ 1.28
	Unit A 1st Level						
251	Door Frame Paint	LF	114	0%	114	\$ 1.08	\$ 1.92
252	Door Paint	SF	182	0%	182	\$ 0.72	\$ 1.28
	Unit B 2nd Level						
253	Door Frame Paint	LF	63	0%	63	\$ 1.08	\$ 1.92
254	Door Paint	SF	60	0%	60	\$ 0.72	\$ 1.28
	Unit B 3rd Level						
255	Door Frame Paint	LF	114	0%	114	\$ 1.08	\$ 1.92
256	Door Paint	SF	127	0%	127	\$ 0.72	\$ 1.28
	Exterior Finish						
257	Brick Vener	SF	986	0%	986	\$ 4.32	\$ 7.68
258	Siding	SF	89	0%	89	\$ 3.24	\$ 5.76
259	Stucco/ Exterior Paint	SF	1806	0%	1806	\$ 2.88	\$ 5.12
260	Stone Cap	LF	51	0%	51	\$ 7.92	\$ 14.08

SPECIALTIES							
	Unit A Cellar Level						
261	Countertop	SF	20	0%	20	\$ 21.60	\$ 38.40
262	(18") Grab Bar	EA	2	0%	2	\$ 28.80	\$ 51.20
263	(24") Grab Bar	EA	2	0%	2	\$ 32.40	\$ 57.60
264	(36") Grab Bar	EA	2	0%	2	\$ 39.60	\$ 70.40
265	Tissue Dispenser	EA	2	0%	2	\$ 32.40	\$ 57.60
266	Soap Dispenser	EA	2	0%	2	\$ 39.60	\$ 70.40
267	(4'-0"x2'-6") Shower Compartment	EA	1	0%	1	\$ 450.00	\$ 800.00
268	(3'-0"x2'-6") Shower Compartment	EA	1	0%	1	\$ 432.00	\$ 768.00
269	(6'-0"x3'-0") Shower Compartment	EA	2	0%	2	\$ 540.00	\$ 960.00
270	(6'-0"x7'-6") Shower Compartment	EA	1	0%	1	\$ 594.00	\$ 1,056.00
271	Guardrail	LF	44	0%	44	\$ 19.80	\$ 35.20
	Unit A 1st Level						

272	Countertop	SF	49	0%	49	\$ 21.60	\$ 38.40
273	(6'-0"x2'-6") Shower Compartment	EA	1	0%	1	\$ 504.00	\$ 896.00
274	(18") Grab Bar	EA	1	0%	1	\$ 28.80	\$ 51.20
275	(24") Grab Bar	EA	1	0%	1	\$ 32.40	\$ 57.60
276	(36") Grab Bar	EA	1	0%	1	\$ 39.60	\$ 70.40
277	Tissue Dispenser	EA	1	0%	1	\$ 32.40	\$ 57.60
278	Soap Dispenser	EA	1	0%	1	\$ 39.60	\$ 70.40
279	Guardrail	LF	52	0%	52	\$ 19.80	\$ 35.20
	Unit B 2nd Level						
280	Countertop	SF	26	0%	26	\$ 21.60	\$ 38.40
281	(4'-0"x2'-9") Shower Compartment	EA	1	0%	1	\$ 468.00	\$ 832.00
282	Guardrail	LF	40	0%	40	\$ 19.80	\$ 35.20
283	Handrail	LF	12	0%	12	\$ 11.52	\$ 20.48
284	(18") Grab Bar	EA	1	0%	1	\$ 28.80	\$ 51.20
285	(24") Grab Bar	EA	1	0%	1	\$ 32.40	\$ 57.60
286	(36") Grab Bar	EA	1	0%	1	\$ 39.60	\$ 70.40
287	Tissue Dispenser	EA	1	0%	1	\$ 32.40	\$ 57.60
288	Soap Dispenser	EA	1	0%	1	\$ 39.60	\$ 70.40
	Unit B 3rd Level						
289	(18") Grab Bar	EA	2	0%	2	\$ 28.80	\$ 51.20
290	(24") Grab Bar	EA	2	0%	2	\$ 32.40	\$ 57.60
291	(36") Grab Bar	EA	2	0%	2	\$ 39.60	\$ 70.40
292	Tissue Dispenser	EA	2	0%	2	\$ 32.40	\$ 57.60
293	Soap Dispenser	EA	2	0%	2	\$ 39.60	\$ 70.40
294	(3'-0"x3'-0") Shower Compartment	EA	1	0%	1	\$ 460.80	\$ 819.20
295	(4'-0"x2'-6") Shower Compartment	EA	1	0%	1	\$ 450.00	\$ 800.00
296	Countertop	SF	21	0%	21	\$ 21.60	\$ 38.40
297	Guardrail	LF	31	0%	31	\$ 19.80	\$ 35.20

EQUIPMENT

	Unit A Cellar Level						
298	Washer/Dryer	EA	1	0%	1	\$ 612.00	\$ 1,088.00
	Unit A 1st Level						
299	Refrigerator	EA	1	0%	1	\$ 540.00	\$ 960.00
300	Cooking Range	EA	1	0%	1	\$ 342.00	\$ 608.00
301	Kitchen Hood	EA	1	0%	1	\$ 216.00	\$ 384.00
302	Dishwasher	EA	1	0%	1	\$ 648.00	\$ 1,152.00
303	Oven	EA	1	0%	1	\$ 396.00	\$ 704.00
	Unit B 2nd Level						
304	Refrigerator	EA	1	0%	1	\$ 540.00	\$ 960.00
305	Cooking Range	EA	1	0%	1	\$ 342.00	\$ 608.00
306	Kitchen Hood	EA	1	0%	1	\$ 216.00	\$ 384.00
307	Dishwasher	EA	1	0%	1	\$ 648.00	\$ 1,152.00
308	Oven	EA	1	0%	1	\$ 396.00	\$ 704.00
	Unit B 3rd Level						
309	Washer/Dryer	EA	1	0%	1	\$ 612.00	\$ 1,088.00

PLUMBING

	Unit A Cellar Level						
310	(4" Dia) Sewer Lateral Pipe	LF	172	0%	172	\$ 6.60	\$ 8.40
311	(1-1/2" Dia) Vent Up Pipe	LF	7	0%	7	\$ 3.52	\$ 4.48
312	Extendable Cleanout	EA	3	0%	3	\$ 70.40	\$ 89.60
313	Backwater Valve	EA	1	0%	1	\$ 92.40	\$ 117.60
314	(3" Dia) Sewer Pipe	LF	98	0%	98	\$ 5.28	\$ 6.72
315	(2" Dia) Sewer Pipe	LF	37	0%	37	\$ 4.40	\$ 5.60
316	(1-1/2" Dia) Sewer Pipe	LF	6	0%	6	\$ 3.52	\$ 4.48
317	(4" Dia) PVC Drain Pipe	LF	3	0%	3	\$ 6.60	\$ 8.40
	Connection						
318	(45 D) Bend	EA	30	0%	30	\$ 15.40	\$ 19.60
319	Tee	EA	19	0%	19	\$ 22.00	\$ 28.00
320	Floor Drain	EA	5	0%	5	\$ 79.20	\$ 100.80
321	Cleanout	EA	3	0%	3	\$ 61.60	\$ 78.40
322	Thermostatic Tempering Valve	EA	1	0%	1	\$ 127.60	\$ 162.40
323	Vacuum Relief Valve	EA	1	0%	1	\$ 83.60	\$ 106.40
324	Backflow Preventer	EA	1	0%	1	\$ 154.00	\$ 196.00
	Plumbing Fixtures						
325	Water Closet	EA	2	0%	2	\$ 382.80	\$ 487.20
326	Lavatory	EA	4	0%	4	\$ 352.00	\$ 448.00
327	(2'-6"x5'-0") Bath Tub	EA	1	0%	1	\$ 528.00	\$ 672.00
328	Sump Pump	EA	1	0%	1	\$ 171.60	\$ 218.40
329	Hot Water Heater	EA	1	0%	1	\$ 616.00	\$ 784.00
	Unit A 1st Level						
330	(2" Dia) Sewer Pipe	LF	19	0%	19	\$ 4.40	\$ 5.60
331	(1-1/2" Dia) Vent Up	LF	108	0%	108	\$ 3.52	\$ 4.48
	Plumbing Fixtures						
332	Water Closet	EA	1	0%	1	\$ 382.80	\$ 487.20
333	Lavatory	EA	1	0%	1	\$ 352.00	\$ 448.00
334	Double Sink	EA	1	0%	1	\$ 431.20	\$ 548.80
	Connection						

335	(90 D) Bend	EA	1	0%	1	\$ 11.00	\$ 14.00
336	(45 D) Bend	EA	4	0%	4	\$ 15.40	\$ 19.60
337	Tee	EA	3	0%	3	\$ 22.00	\$ 28.00
	Unit B 2nd Level						
338	(2" Dia) Sewer Pipe	LF	21	0%	21	\$ 4.40	\$ 5.60
339	(1-1/2" Dia) Sewer Pipe	LF	8	0%	8	\$ 3.52	\$ 4.48
340	(1-1/2" Dia) Vent Up Pipe	LF	217	0%	217	\$ 3.52	\$ 4.48
341	Full Flow Shut Off Valve	EA	2	0%	2	\$ 101.20	\$ 128.80
342	Backflow Preventer	EA	1	0%	1	\$ 154.00	\$ 196.00
343	Vacuum Relief Valve	EA	1	0%	1	\$ 83.60	\$ 106.40
344	Thermostatic Tempering Valve	EA	1	0%	1	\$ 127.60	\$ 162.40
	Connection						
345	(45 D) Bend	EA	8	0%	8	\$ 15.40	\$ 19.60
346	Tee	EA	4	0%	4	\$ 22.00	\$ 28.00
	Plumbing Fixtures						
347	Water Closet	EA	1	0%	1	\$ 382.80	\$ 487.20
348	Lavatory	EA	1	0%	1	\$ 352.00	\$ 448.00
349	Double Sink	EA	1	0%	1	\$ 431.20	\$ 548.80
350	Hot Water Heater	EA	1	0%	1	\$ 616.00	\$ 784.00
	Unit B 3rd Level						
351	(2" Dia) Sewer Pipe	LF	40	0%	40	\$ 4.40	\$ 5.60
352	(3" Dia) Sewer Pipe	LF	5	0%	5	\$ 5.28	\$ 6.72
353	(1-1/2" Dia) Vent Up Pipe	LF	185	0%	185	\$ 3.52	\$ 4.48
	Connection						
	Plumbing Fixtures						
354	Lavatory	EA	4	0%	4	\$ 352.00	\$ 448.00
355	Water Closet	EA	2	0%	2	\$ 382.80	\$ 487.20
356	(2'-6"x5'-0") Bath Tub	EA	1	0%	1	\$ 528.00	\$ 672.00
357	(45 D) Bend	EA	10	0%	10	\$ 15.40	\$ 19.60
358	(90 D) Bend	EA	3	0%	3	\$ 11.00	\$ 14.00
359	Tee	EA	6	0%	6	\$ 22.00	\$ 28.00
	Unit B Roof Level						
360	(3" Dia) Sewer Pipe	LF	35	0%	35	\$ 5.28	\$ 6.72
	Connection						
361	Roof Drain	EA	5	0%	5	\$ 92.40	\$ 117.60
362	(45 D) Bend	EA	2	0%	2	\$ 15.40	\$ 19.60
363	Tee	EA	1	0%	1	\$ 22.00	\$ 28.00

HVAC/MECHANICAL							
364	AC Indoor Unit	EA	2	0%	2	\$ 660.00	\$ 840.00
	Unit A Cellar Level						
365	(11x13) Duct	LF	29	0%	29	\$ 11.88	\$ 15.12
366	(8x12) Duct	LF	13	0%	13	\$ 10.12	\$ 12.88
367	(8x8) Duct	LF	22	0%	22	\$ 8.36	\$ 10.64
368	(6" Dia) Duct	LF	20	0%	20	\$ 3.52	\$ 4.48
369	(4" Dia) Duct	LF	6	0%	6	\$ 2.64	\$ 3.36
370	(10x6) Supply Diffuser CFM:50	EA	8	0%	8	\$ 70.40	\$ 89.60
371	(12x12) Supply Diffuser CFM:600	EA	1	0%	1	\$ 85.80	\$ 109.20
372	Return Air Grille	EA	1	0%	1	\$ 66.00	\$ 84.00
	Connection						
373	Tee	EA	9	0%	9	\$ 24.20	\$ 30.80
374	Transition	EA	4	0%	4	\$ 33.00	\$ 42.00
375	Gas S/O Valve	EA	1	0%	1	\$ 52.80	\$ 67.20
	Unit A 1st Level						
376	(11x13) Duct	LF	29	0%	29	\$ 11.88	\$ 15.12
377	(8x12) Duct	LF	13	0%	13	\$ 10.12	\$ 12.88
378	(8x8) Duct	LF	23	0%	23	\$ 8.36	\$ 10.64
379	(6" Dia) Duct	LF	25	0%	25	\$ 3.52	\$ 4.48
380	(4" Dia) Duct	LF	6	0%	6	\$ 2.64	\$ 3.36
381	(10x6) Supply Diffuser CFM:50	EA	9	0%	9	\$ 70.40	\$ 89.60
382	Return Air Grille	EA	1	0%	1	\$ 66.00	\$ 84.00
	Connection						
383	Gas S/O Valve	EA	1	0%	1	\$ 52.80	\$ 67.20
384	Tee	EA	8	0%	8	\$ 24.20	\$ 30.80
385	Transition	EA	6	0%	6	\$ 33.00	\$ 42.00
	Unit B 2nd Level						
386	(11x13) Duct	LF	38	0%	38	\$ 11.88	\$ 15.12
387	(8x8) Duct	LF	50	0%	50	\$ 8.36	\$ 10.64
388	(6" Dia) Duct	LF	22	0%	22	\$ 3.52	\$ 4.48
389	(4" Dia) Duct	LF	7	0%	7	\$ 2.64	\$ 3.36
390	(10x6) Supply Diffuser CFM:50	EA	9	0%	9	\$ 70.40	\$ 89.60
391	(12x12) Supply Diffuser CFM:600	EA	1	0%	1	\$ 85.80	\$ 109.20
392	Gas S/O Valve	EA	2	0%	2	\$ 52.80	\$ 67.20
393	Return Air Grille	EA	2	0%	2	\$ 66.00	\$ 84.00
	Connection						

394	Tee	EA	9	0%	9	\$ 24.20	\$ 30.80
395	Transition	EA	10	0%	10	\$ 33.00	\$ 42.00
	Unit B 3rd Level						
396	(11x13) Duct	LF	37	0%	37	\$ 11.88	\$ 15.12
397	(8x8) Duct	LF	48	0%	48	\$ 8.36	\$ 10.64
398	(6" Dia) Duct	LF	16	0%	16	\$ 3.52	\$ 4.48
399	(4" Dia) Duct	LF	14	0%	14	\$ 2.64	\$ 3.36
400	(10x6) Supply Diffuser CFM:50	EA	8	0%	8	\$ 70.40	\$ 89.60
401	(12x12) Supply Diffuser CFM:600	EA	1	0%	1	\$ 85.80	\$ 109.20
	Connection						
402	Tee	EA	10	0%	10	\$ 24.20	\$ 30.80
403	Transition	EA	9	0%	9	\$ 33.00	\$ 42.00
	Roof Level						
404	AC Outdoor Unit	EA	2	0%	2	\$ 792.00	\$ 1,008.00

ELECTRICAL							
	Unit A Cellar Level						
405	Duplex Receptacle	EA	23	0%	23	\$ 79.20	\$ 100.80
406	Duplex Receptacle GFI	EA	3	0%	3	\$ 83.60	\$ 106.40
407	Waterproof Duplex Receptacle	EA	1	0%	1	\$ 88.00	\$ 112.00
408	Single pole Switch	EA	14	0%	14	\$ 39.60	\$ 50.40
409	SD Smoke Detector And Carbon Monoxide Detector	EA	4	0%	4	\$ 74.80	\$ 95.20
410	RL Recessed Light Fixture	EA	4	0%	4	\$ 118.80	\$ 151.20
411	C Ceiling Light Fixture	EA	9	0%	9	\$ 125.40	\$ 159.60
412	M Exterior Motion Detector Light Fixture	EA	1	0%	1	\$ 167.20	\$ 212.80
413	V Wall Mounted Vanity Light	EA	2	0%	2	\$ 123.20	\$ 156.80
414	D Data Comm. Port	EA	3	0%	3	\$ 57.20	\$ 72.80
415	F Ceiling Mounted Fan 100 CFM	EA	2	0%	2	\$ 140.80	\$ 179.20
416	D Equipment Disconnect	EA	2	0%	2	\$ 70.40	\$ 89.60
417	Electrical Wiring And Conduits	SF	846	0%	846	\$ 0.88	\$ 1.12
	Unit A 1st Level						
418	Duplex Receptacle	EA	15	0%	15	\$ 79.20	\$ 100.80
419	Duplex Receptacle GFI	EA	6	0%	6	\$ 83.60	\$ 106.40
420	Single pole Switch	EA	16	0%	16	\$ 39.60	\$ 50.40
421	SD Smoke Detector And Carbon Monoxide Detector	EA	1	0%	1	\$ 74.80	\$ 95.20
422	RL Recessed Light Fixture	EA	22	0%	22	\$ 118.80	\$ 151.20
423	DP Drop Pendant Light Fixture	EA	3	0%	3	\$ 136.40	\$ 173.60
424	C Ceiling Light Fixture	EA	3	0%	3	\$ 125.40	\$ 159.60
425	F Ceiling Mounted Fan 100 CFM	EA	1	0%	1	\$ 140.80	\$ 179.20
426	V Wall Mounted Vanity Light	EA	1	0%	1	\$ 123.20	\$ 156.80
427	GD Garbage Disposal W/ Disconnect	EA	1	0%	1	\$ 484.00	\$ 616.00
428	D Data Comm. Port	EA	2	0%	2	\$ 57.20	\$ 72.80
429	D Equipment Disconnect	EA	2	0%	2	\$ 70.40	\$ 89.60
430	Electrical Wiring And Conduits	SF	904	0%	904	\$ 0.88	\$ 1.12
	Unit B 2nd Level						
431	Duplex Receptacle	EA	15	0%	15	\$ 79.20	\$ 100.80
432	Duplex Receptacle GFI	EA	6	0%	6	\$ 83.60	\$ 106.40
433	Single pole Switch	EA	16	0%	16	\$ 39.60	\$ 50.40
434	SD Smoke Detector And Carbon Monoxide Detector	EA	1	0%	1	\$ 74.80	\$ 95.20
435	RL Recessed Light Fixture	EA	22	0%	22	\$ 118.80	\$ 151.20
436	DP Drop Pendant Light Fixture	EA	3	0%	3	\$ 136.40	\$ 173.60
437	C Ceiling Light Fixture	EA	3	0%	3	\$ 125.40	\$ 159.60
438	F Ceiling Mounted Fan 100 CFM	EA	1	0%	1	\$ 140.80	\$ 179.20
439	V Wall Mounted Vanity Light	EA	1	0%	1	\$ 123.20	\$ 156.80
440	D Data Comm. Port	EA	2	0%	2	\$ 57.20	\$ 72.80
441	D Equipment Disconnect	EA	2	0%	2	\$ 70.40	\$ 89.60
442	GD Garbage Disposal W/ Disconnect	EA	1	0%	1	\$ 484.00	\$ 616.00
443	Electrical Wiring And Conduits	SF	904	0%	904	\$ 0.88	\$ 1.12
	Unit B 3rd Level						
444	Duplex Receptacle	EA	7	0%	7	\$ 79.20	\$ 100.80
445	Duplex Receptacle GFI	EA	4	0%	4	\$ 83.60	\$ 106.40
446	C Ceiling Light Fixture	EA	4	0%	4	\$ 125.40	\$ 159.60
447	SD Smoke Detector And Carbon Monoxide Detector	EA	1	0%	1	\$ 74.80	\$ 95.20
448	Single pole Switch	EA	5	0%	5	\$ 39.60	\$ 50.40
449	F Ceiling Mounted Fan 100 CFM	EA	2	0%	2	\$ 140.80	\$ 179.20
450	V Wall Mounted Vanity Light	EA	2	0%	2	\$ 123.20	\$ 156.80
451	Electrical Wiring And Conduits	SF	366	0%	366	\$ 0.88	\$ 1.12
	Unit B Roof Level						
452	Waterproof Duplex Receptacle	EA	2	0%	2	\$ 88.00	\$ 112.00

Prepared for:

Project ID:

Scope:

Date:

X.Y.Z.

Everything

7-Feb-22

UNIT COST	SUB COST
\$ -	\$ 106,240.00
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ -	\$ -
\$ 2.70	\$ 7,803.00
SUBTOTAL \$ 114,043.00	

\$ 3.20	\$ 115.20
\$ 1.50	\$ 562.50
\$ 2.00	\$ 42.00
\$ 3.20	\$ 160.00
\$ 1.50	\$ 421.50
\$ 2.00	\$ 126.00
\$ 3.20	\$ 169.60
\$ 1.50	\$ 756.00
\$ 2.00	\$ 80.00
\$ 3.60	\$ 2,890.80
\$ 5.00	\$ 1,710.00
\$ 18.00	\$ 4,050.00
\$ 2.40	\$ 5,997.60
\$ 2.00	\$ 1,938.00
\$ 12.00	\$ 456.00
\$ 16.00	\$ 304.00
\$ 45.00	\$ 1,395.00
SUBTOTAL \$ 21,174.20	

\$ 640.00	\$ 11,026.05
\$ 640.00	\$ 213.33
\$ 640.00	\$ 4,561.42
\$ 640.00	\$ 1,965.04
\$ 640.00	\$ 2,038.40
\$ 6.00	\$ 5,814.00
\$ 22.00	\$ 242.00
SUBTOTAL \$ 25,860.23	

\$ 14.00	\$ 182.00
\$ 10.00	\$ 220.00
\$ 10.00	\$ 770.00
\$ 14.00	\$ 770.00
\$ 14.00	\$ 336.00
\$ 14.00	\$ 966.00

\$ 14.00	\$ 910.00
\$ 14.00	\$ 2,702.00
\$ 14.00	\$ 588.00
\$ 8.00	\$ 760.00
\$ 14.00	\$ 3,136.00

SUBTOTAL \$ 11,340.00

\$ 130.00	\$ 520.00
\$ 14.00	\$ 126.00
\$ 45.00	\$ 4,005.00
\$ 6.00	\$ 129.06
\$ 6.00	\$ 1,041.12
\$ 6.00	\$ 1,363.20
\$ 45.00	\$ 4,140.00
\$ 130.00	\$ 520.00
\$ 45.00	\$ 4,050.00
\$ 6.00	\$ 430.20
\$ 6.00	\$ 2,145.60
\$ 6.00	\$ 780.84
\$ 130.00	\$ 1,040.00
\$ 45.00	\$ 4,230.00
\$ 6.00	\$ 1,301.40
\$ 6.00	\$ 2,413.80
\$ 130.00	\$ 780.00

SUBTOTAL \$ 29,016.22

\$ 16.00	\$ 528.00
\$ 2,500.00	\$ 2,500.00
\$ 13.00	\$ 2,886.00
\$ 12.00	\$ 7,368.00
\$ 16.00	\$ 1,840.00
\$ 14.00	\$ 154.00
\$ 10.00	\$ 130.00
\$ 10.00	\$ 1,540.00
\$ 12.00	\$ 516.00
\$ 10.00	\$ 360.00
\$ 3.00	\$ 2,559.00
\$ 5.00	\$ 1,020.00
\$ 15.00	\$ 840.00
\$ 16.00	\$ 480.00
\$ 12.00	\$ 348.00
\$ 14.00	\$ 210.00
\$ 18.00	\$ 648.00
\$ 2,700.00	\$ 2,700.00
\$ 12.00	\$ 7,080.00
\$ 13.00	\$ 3,042.00
\$ 10.00	\$ 930.00
\$ 10.00	\$ 410.00

\$ 3.00	\$ 3,027.00
\$ 13.00	\$ 572.00
\$ 10.00	\$ 240.00
\$ 16.00	\$ 864.00
\$ 16.00	\$ 1,392.00
\$ 12.00	\$ 312.00
\$ 16.00	\$ 480.00
\$ 16.00	\$ 720.00
\$ 12.00	\$ 324.00
\$ 2,200.00	\$ 2,200.00
\$ 12.00	\$ 6,276.00
\$ 13.00	\$ 4,394.00
\$ 16.00	\$ 2,944.00
\$ 3.00	\$ 2,664.00
\$ 12.00	\$ 420.00
\$ 16.00	\$ 928.00
\$ 12.00	\$ 468.00
\$ 16.00	\$ 1,424.00
\$ 16.00	\$ 576.00
\$ 12.00	\$ 216.00
\$ 1,950.00	\$ 1,950.00
\$ 12.00	\$ 3,468.00
\$ 13.00	\$ 6,747.00
\$ 16.00	\$ 2,976.00
\$ 12.00	\$ 588.00
\$ 12.00	\$ 840.00
\$ 13.00	\$ 884.00
\$ 16.00	\$ 544.00
\$ 3.40	\$ 2,862.80
\$ 6.00	\$ 4,548.00
SUBTOTAL \$ 93,937.80	
\$ 1.80	\$ 1,582.20
\$ 1.95	\$ 1,889.55
\$ 2.00	\$ 1,706.00
\$ 2.00	\$ 2,018.00
\$ 2.00	\$ 1,776.00
\$ 7.00	\$ 4,410.00
\$ 7.00	\$ 581.00
\$ 2.10	\$ 1,591.80
\$ 2.40	\$ 1,819.20
\$ 10.00	\$ 1,240.00
\$ 8.00	\$ 992.00
\$ 9.00	\$ 1,116.00
\$ 14.00	\$ 1,736.00
\$ 8.00	\$ 1,008.00
\$ 9.00	\$ 684.00
SUBTOTAL \$ 24,149.75	

\$ 1,200.00	\$ 1,200.00
\$ 780.00	\$ 2,340.00
\$ 700.00	\$ 700.00
\$ 960.00	\$ 3,840.00
\$ 240.00	\$ 2,160.00
\$ 700.00	\$ 2,800.00
\$ 1,100.00	\$ 1,100.00
\$ 1,400.00	\$ 1,400.00
\$ 1,280.00	\$ 1,280.00
\$ 780.00	\$ 780.00
\$ 880.00	\$ 1,760.00
\$ 240.00	\$ 1,440.00
\$ 650.00	\$ 5,200.00
\$ 650.00	\$ 650.00
\$ 650.00	\$ 650.00
\$ 750.00	\$ 3,000.00
\$ 240.00	\$ 960.00
\$ 650.00	\$ 1,300.00
\$ 650.00	\$ 5,200.00
\$ 750.00	\$ 1,500.00
\$ 750.00	\$ 750.00
\$ 580.00	\$ 1,740.00
\$ 420.00	\$ 420.00
\$ 810.00	\$ 810.00
\$ 750.00	\$ 1,500.00
\$ 920.00	\$ 2,760.00
\$ 750.00	\$ 750.00
\$ 240.00	\$ 1,680.00
\$ 650.00	\$ 1,950.00
\$ 650.00	\$ 3,900.00
\$ 500.00	\$ 1,000.00
\$ 400.00	\$ 400.00
SUBTOTAL \$ 56,920.00	

\$ 5.80	\$ 1,368.80
\$ 4.50	\$ 4,779.00
\$ 2.70	\$ 11,469.60
\$ 1.70	\$ 1,805.40
\$ 1.00	\$ 472.00
\$ 5.80	\$ 1,496.40
\$ 4.50	\$ 5,224.50
\$ 2.60	\$ 11,044.80
\$ 3.20	\$ 3,715.20
\$ 1.00	\$ 258.00
\$ 5.80	\$ 1,009.20
\$ 4.50	\$ 3,523.50
\$ 2.40	\$ 3,758.40
\$ 1.90	\$ 1,487.70
\$ 1.00	\$ 348.00
\$ 5.80	\$ 266.80
\$ 4.50	\$ 931.50
\$ 2.70	\$ 2,235.60
\$ 1.70	\$ 351.90
\$ 1.00	\$ 92.00
\$ 5.80	\$ 1,020.80
\$ 4.50	\$ 3,564.00
\$ 2.60	\$ 2,059.20
\$ 3.20	\$ 2,534.40
\$ 1.00	\$ 176.00
\$ 5.80	\$ 846.80
\$ 4.50	\$ 2,956.50
\$ 2.70	\$ 7,095.60
\$ 1.70	\$ 1,116.90
\$ 1.00	\$ 292.00
\$ 5.80	\$ 498.80
\$ 4.50	\$ 1,741.50
\$ 2.40	\$ 1,857.60
\$ 1.90	\$ 735.30
\$ 1.00	\$ 172.00
\$ 5.80	\$ 1,067.20
\$ 4.50	\$ 3,726.00
\$ 2.60	\$ 2,152.80
\$ 3.20	\$ 2,649.60
\$ 1.00	\$ 184.00
\$ 5.80	\$ 1,368.80
\$ 4.50	\$ 4,779.00
\$ 2.70	\$ 11,469.60
\$ 1.70	\$ 1,805.40
\$ 1.00	\$ 472.00
\$ 5.80	\$ 1,519.60
\$ 4.50	\$ 5,305.50
\$ 2.40	\$ 5,659.20
\$ 1.90	\$ 2,240.10
\$ 1.00	\$ 524.00
\$ 5.80	\$ 301.60
\$ 4.50	\$ 1,053.00
\$ 2.60	\$ 608.40
\$ 3.20	\$ 748.80
\$ 1.00	\$ 52.00
\$ 5.80	\$ 1,415.20
\$ 4.50	\$ 1,647.00
\$ 2.40	\$ 1,756.80
\$ 1.90	\$ 695.40
\$ 1.00	\$ 488.00

\$ 2.80	\$ 4,267.20
\$ 2.80	\$ 4,821.60
\$ 2.80	\$ 4,793.60
\$ 2.80	\$ 4,496.80
\$ 8.00	\$ 5,680.00
\$ 12.00	\$ 1,416.00
\$ 12.00	\$ 552.00
\$ 7.00	\$ 1,848.00
\$ 17.00	\$ 986.00
\$ 1.30	\$ 413.40
\$ 8.00	\$ 6,840.00
\$ 12.00	\$ 192.00
\$ 7.00	\$ 1,358.00
\$ 17.00	\$ 272.00
\$ 1.30	\$ 278.20
\$ 8.00	\$ 6,520.00
\$ 12.00	\$ 552.00
\$ 7.00	\$ 1,589.00
\$ 17.00	\$ 391.00
\$ 1.30	\$ 318.50
\$ 8.00	\$ 4,496.00
\$ 12.00	\$ 1,536.00
\$ 12.00	\$ 1,416.00
\$ 7.00	\$ 1,743.00
\$ 12.00	\$ 708.00
\$ 1.30	\$ 369.20
\$ 1.70	\$ 1,295.40
\$ 1.70	\$ 1,463.70
\$ 1.70	\$ 1,455.20
\$ 1.70	\$ 1,365.10
\$ 3.00	\$ 459.00
\$ 2.00	\$ 434.00
\$ 3.00	\$ 342.00
\$ 2.00	\$ 364.00
\$ 3.00	\$ 189.00
\$ 2.00	\$ 120.00
\$ 3.00	\$ 342.00
\$ 2.00	\$ 254.00
\$ 12.00	\$ 11,832.00
\$ 9.00	\$ 801.00
\$ 8.00	\$ 14,448.00
\$ 22.00	\$ 1,122.00
SUBTOTAL \$ 230,134.60	
\$ 60.00	\$ 1,200.00
\$ 80.00	\$ 160.00
\$ 90.00	\$ 180.00
\$ 110.00	\$ 220.00
\$ 90.00	\$ 180.00
\$ 110.00	\$ 220.00
\$ 1,250.00	\$ 1,250.00
\$ 1,200.00	\$ 1,200.00
\$ 1,500.00	\$ 3,000.00
\$ 1,650.00	\$ 1,650.00
\$ 55.00	\$ 2,420.00

\$ 60.00	\$ 2,940.00
\$ 1,400.00	\$ 1,400.00
\$ 80.00	\$ 80.00
\$ 90.00	\$ 90.00
\$ 110.00	\$ 110.00
\$ 90.00	\$ 90.00
\$ 110.00	\$ 110.00
\$ 55.00	\$ 2,860.00
\$ 60.00	\$ 1,560.00
\$ 1,300.00	\$ 1,300.00
\$ 55.00	\$ 2,200.00
\$ 32.00	\$ 384.00
\$ 80.00	\$ 80.00
\$ 90.00	\$ 90.00
\$ 110.00	\$ 110.00
\$ 90.00	\$ 90.00
\$ 110.00	\$ 110.00
\$ 80.00	\$ 160.00
\$ 90.00	\$ 180.00
\$ 110.00	\$ 220.00
\$ 90.00	\$ 180.00
\$ 110.00	\$ 220.00
\$ 1,280.00	\$ 1,280.00
\$ 1,250.00	\$ 1,250.00
\$ 60.00	\$ 1,260.00
\$ 55.00	\$ 1,705.00

SUBTOTAL \$ 31,739.00

\$ 1,700.00	\$ 1,700.00
\$ 1,500.00	\$ 1,500.00
\$ 950.00	\$ 950.00
\$ 600.00	\$ 600.00
\$ 1,800.00	\$ 1,800.00
\$ 1,100.00	\$ 1,100.00
\$ 1,500.00	\$ 1,500.00
\$ 950.00	\$ 950.00
\$ 600.00	\$ 600.00
\$ 1,800.00	\$ 1,800.00
\$ 1,100.00	\$ 1,100.00
\$ 1,700.00	\$ 1,700.00

SUBTOTAL \$ 15,300.00

\$ 15.00	\$ 2,580.00
\$ 8.00	\$ 56.00
\$ 160.00	\$ 480.00
\$ 210.00	\$ 210.00
\$ 12.00	\$ 1,176.00
\$ 10.00	\$ 370.00
\$ 8.00	\$ 48.00
\$ 15.00	\$ 45.00
\$ 35.00	\$ 1,050.00
\$ 50.00	\$ 950.00
\$ 180.00	\$ 900.00
\$ 140.00	\$ 420.00
\$ 290.00	\$ 290.00
\$ 190.00	\$ 190.00
\$ 350.00	\$ 350.00
\$ 870.00	\$ 1,740.00
\$ 800.00	\$ 3,200.00
\$ 1,200.00	\$ 1,200.00
\$ 390.00	\$ 390.00
\$ 1,400.00	\$ 1,400.00
\$ 10.00	\$ 190.00
\$ 8.00	\$ 864.00
\$ 870.00	\$ 870.00
\$ 800.00	\$ 800.00
\$ 980.00	\$ 980.00

\$ 25.00	\$ 25.00
\$ 35.00	\$ 140.00
\$ 50.00	\$ 150.00
\$ 10.00	\$ 210.00
\$ 8.00	\$ 64.00
\$ 8.00	\$ 1,736.00
\$ 230.00	\$ 460.00
\$ 350.00	\$ 350.00
\$ 190.00	\$ 190.00
\$ 290.00	\$ 290.00
\$ 35.00	\$ 280.00
\$ 50.00	\$ 200.00
\$ 870.00	\$ 870.00
\$ 800.00	\$ 800.00
\$ 980.00	\$ 980.00
\$ 1,400.00	\$ 1,400.00
\$ 10.00	\$ 400.00
\$ 12.00	\$ 60.00
\$ 8.00	\$ 1,480.00
\$ 800.00	\$ 3,200.00
\$ 870.00	\$ 1,740.00
\$ 1,200.00	\$ 1,200.00
\$ 35.00	\$ 350.00
\$ 25.00	\$ 75.00
\$ 50.00	\$ 300.00
\$ 12.00	\$ 420.00
\$ 210.00	\$ 1,050.00
\$ 35.00	\$ 70.00
\$ 50.00	\$ 50.00
SUBTOTAL \$ 39,289.00	

\$ 1,500.00	\$ 3,000.00
\$ 27.00	\$ 783.00
\$ 23.00	\$ 299.00
\$ 19.00	\$ 418.00
\$ 8.00	\$ 160.00
\$ 6.00	\$ 36.00
\$ 160.00	\$ 1,280.00
\$ 195.00	\$ 195.00
\$ 150.00	\$ 150.00
\$ 55.00	\$ 495.00
\$ 75.00	\$ 300.00
\$ 120.00	\$ 120.00
\$ 27.00	\$ 783.00
\$ 23.00	\$ 299.00
\$ 19.00	\$ 437.00
\$ 8.00	\$ 200.00
\$ 6.00	\$ 36.00
\$ 160.00	\$ 1,440.00
\$ 150.00	\$ 150.00
\$ 120.00	\$ 120.00
\$ 55.00	\$ 440.00
\$ 75.00	\$ 450.00
\$ 27.00	\$ 1,026.00
\$ 19.00	\$ 950.00
\$ 8.00	\$ 176.00
\$ 6.00	\$ 42.00
\$ 160.00	\$ 1,440.00
\$ 195.00	\$ 195.00
\$ 120.00	\$ 240.00
\$ 150.00	\$ 300.00

\$ 55.00	\$ 495.00
\$ 75.00	\$ 750.00
\$ 27.00	\$ 999.00
\$ 19.00	\$ 912.00
\$ 8.00	\$ 128.00
\$ 6.00	\$ 84.00
\$ 160.00	\$ 1,280.00
\$ 195.00	\$ 195.00
\$ 55.00	\$ 550.00
\$ 75.00	\$ 675.00
\$ 1,800.00	\$ 3,600.00
SUBTOTAL \$ 22,628.00	

\$ 180.00	\$ 4,140.00
\$ 190.00	\$ 570.00
\$ 200.00	\$ 200.00
\$ 90.00	\$ 1,260.00
\$ 170.00	\$ 680.00
\$ 270.00	\$ 1,080.00
\$ 285.00	\$ 2,565.00
\$ 380.00	\$ 380.00
\$ 280.00	\$ 560.00
\$ 130.00	\$ 390.00
\$ 320.00	\$ 640.00
\$ 160.00	\$ 320.00
\$ 2.00	\$ 1,692.00
\$ 180.00	\$ 2,700.00
\$ 190.00	\$ 1,140.00
\$ 90.00	\$ 1,440.00
\$ 170.00	\$ 170.00
\$ 270.00	\$ 5,940.00
\$ 310.00	\$ 930.00
\$ 285.00	\$ 855.00
\$ 320.00	\$ 320.00
\$ 280.00	\$ 280.00
\$ 1,100.00	\$ 1,100.00
\$ 130.00	\$ 260.00
\$ 160.00	\$ 320.00
\$ 2.00	\$ 1,808.00
\$ 180.00	\$ 2,700.00
\$ 190.00	\$ 1,140.00
\$ 90.00	\$ 1,440.00
\$ 170.00	\$ 170.00
\$ 270.00	\$ 5,940.00
\$ 310.00	\$ 930.00
\$ 285.00	\$ 855.00
\$ 320.00	\$ 320.00
\$ 280.00	\$ 280.00
\$ 130.00	\$ 260.00
\$ 160.00	\$ 320.00
\$ 1,100.00	\$ 1,100.00
\$ 2.00	\$ 1,808.00
\$ 180.00	\$ 1,260.00
\$ 190.00	\$ 760.00
\$ 285.00	\$ 1,140.00
\$ 170.00	\$ 170.00
\$ 90.00	\$ 450.00
\$ 320.00	\$ 640.00
\$ 280.00	\$ 560.00
\$ 2.00	\$ 732.00
\$ 200.00	\$ 400.00
SUBTOTAL \$ 55,115.00	

DETAILED BREAKDOWN OF ITEMS

SR #	REF. DWG.	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	LABOR COST	MAT. COST
								PROJECTED COST
OVERHEAD AND PROFIT			0.2	0.2				
INSURANCE						0.03	0.03	
CONTINGENCY						0.07	0.07	
TAX						0.07	0.07	

SUGGESTED BID

Note:

- 1.Please verify the equipment's and their prices with owner.
- 2.For tree plantation average prices are use. Please verify according to tree type.
- 3.Online sources are used for pricing.
- 4.Prices can vary depending upon field conditions.

Prepared for:
X.Y.Z.

Project ID:

Scope:

Date:

Everything

7-Feb-22

UNIT COST	SUB COST
	\$770,647
20%	\$154,129
3%	\$23,119
7%	\$53,945
7%	\$53,945
	\$1,055,786