

GENERAL SUMMARY				
Prepared for:				
Project ID:				
Scope:		Site and Utilities		
Date:		17-Jul-24		
BUILDING GSF		502,265		
DIVISION NO	DESCRIPTION	TOTAL DIV. COST	TOTAL DIV. COST (PER SF)	
1000	General Requirements	\$ 181,000	\$ 0.36	
2000	Existing Condition	\$ 8,524	\$ 0.02	
31000	Earthwork	\$ 93,811	\$ 0.19	
32000	Site Improvements	\$ 930,293	\$ 1.85	
33000	Utilities	\$ 814,300	\$ 1.62	
TOTAL TRADE COST		\$ 2,027,928	\$ 4	
OVERHEAD AND PROFIT		15%	\$ 304,189	\$ 0.61
INSURANCE		3%	\$ 60,838	\$ 0
CONTINGENCY		5%	\$ 101,396	\$ 0
TAX		8%	\$ 162,234	\$ 0
SUGGESTED BID		\$ 2,656,586	\$ 5	

DIVISION COST COMPARISON

DIVISION COST COMPARISON

Category	Cost (\$)
General Requirements	181,000
Existing Condition	8,524
Earthwork	93,811
Site Improvements	930,293
Utilities	814,300

DETAILED BREAKDOWN OF ITEMS													
Prepared for:													
Project ID:													
Scope: Site													
												Date:	17-Jul-24
SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MANHOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
GENERAL REQUIREMENTS													
1			Permits	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 15,000.00	\$ 15,000.00
2			Supervision and Coordination	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 80,000.00	\$ 80,000.00
3			Submittals and Shop drawings	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 7,500.00	\$ 7,500.00
4			Final Cleaning	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 10,500.00	\$ 10,500.00
5			Mobilization Costs	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 50,000.00	\$ 50,000.00
6			Temporary Control & Facilities	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ 18,000.00	\$ 18,000.00
7			Scaffolding	LS	1	0%	1	0.000	\$ -	\$ -	\$ -	\$ -	\$ -
												SUBTOTAL	\$ 15,000.00
EXISTING CONDITIONS													
DEMOLITION													
8			Remove Culvert Pipe	LF	62	0%	62	0.30	55.00	\$ 16.50	\$ -	\$ 16.50	\$ 1,021.02
9			Remove Existing Fence	LF	295	0%	295	0.20	50.00	\$ 10.00	\$ -	\$ 10.00	\$ 2,952.80
10			Remove Existing Tree	EA	26	0%	26	3.50	50.00	\$ 175.00	\$ -	\$ 175.00	\$ 4,550.00
												SUBTOTAL	\$ 8,524.82
EARTHWORK													
EROSIN & SEDIMENT CONTROL													
11			Swale Fill	SF	3847	10%	4232	0.05	50.00	\$ 2.50	\$ 0.45	\$ 2.95	\$ 12,483.22
12			Filter Fabric (3'-6" H.)	LF	3161	10%	3477	0.30	55.00	\$ 16.50	\$ 0.98	\$ 17.48	\$ 60,780.86
13			2 x 4 Wood Post (4'-0" H.)	EA	1154	0%	1154	0.06	50.00	\$ 2.80	\$ 15.00	\$ 17.80	\$ 20,547.13
												SUBTOTAL	\$ 6,841.11
SITE IMPROVEMENTS													
PAVERS													
		C5.00	Asphalt Pavements	SF	52075								
14			2" Thk Compacted Asphalt	CY	328	10%	361	0.45	60.00	\$ 27.00	\$ 150.00	\$ 177.00	\$ 63,838.47
15			9" Thk Crushed Concrete Base Aggregate	CY	1447	10%	1591	0.35	60.00	\$ 21.00	\$ 60.00	\$ 81.00	\$ 128,886.24
16			12" Stabilize Subgrade	CY	1929	10%	2122	0.45	55.00	\$ 24.75	\$ 35.00	\$ 59.75	\$ 126,764.66
			Concrete Pavement	SF	1518								
17			4" Thk Concrete	CY	19	10%	20	0.60	65.00	\$ 39.00	\$ 225.00	\$ 264.00	\$ 5,387.99
18			Compacted Sub Base	SF	1518	10%	1670	0.30	45.00	\$ 13.50	\$ 0.95	\$ 14.45	\$ 24,129.09
19		ASSUMED	RV Pad Pavement	SF	41390	10%	45529	0.10	55.00	\$ 5.50	\$ 4.00	\$ 9.50	\$ 432,524.77
20			7" Thk Crushed Concrete Base Aggregate	CY	889	10%	978	0.35	55.00	\$ 19.25	\$ 50.00	\$ 69.25	\$ 67,728.49
21			8" Stabilize Subgrade	CY	1022	10%	1125	0.50	45.00	\$ 22.50	\$ 20.00	\$ 42.50	\$ 47,801.15
			BENCH MARK										
22			Concrete Weir Benchmark	EA	2	0%	2	2.00	60.00	\$ 120.00	\$ 350.00	\$ 470.00	\$ 940.00
SITE PROTECTION													
23			Tree Protection Barrier	LF	91	10%	100	0.35	55.00	\$ 19.25	\$ 15.00	\$ 34.25	\$ 3,411.85
LANDSCAPING													
24			Pine Tree	EA	36	0%	36	3.00	70.00	\$ 210.00	\$ 550.00	\$ 760.00	\$ 27,360.00
25			Palm Tree	EA	2	0%	2	3.00	70.00	\$ 210.00	\$ 550.00	\$ 760.00	\$ 1,520.00
												SUBTOTAL	\$ 90,209.33
UTILITIES													
PIPING													
26			4" Dia Water Main	LF	1624	10%	1786	0.75	70.00	\$ 52.50	\$ 25.00	\$ 77.50	\$ 138,415.31
27			Excavation	CY	400	10%	440	1.100	\$ 50.00	\$ 55.00	\$ -	\$ 55.00	\$ 24,193.74
28			Backfill	CY	395	10%	434	0.785	\$ 50.00	\$ 39.25	\$ -	\$ 39.25	\$ 17,043.47
29			6" Dia PVC Pipe	LF	41	10%	45	1.00	70.00	\$ 70.00	\$ 30.00	\$ 100.00	\$ 4,468.20
30			Excavation	CY	11.28	10%	12.41	1.100	\$ 50.00	\$ 55.00	\$ -	\$ 55.00	\$ 682.64
31			Backfill	CY	10.99	10%	12.09	0.785	\$ 50.00	\$ 39.25	\$ -	\$ 39.25	\$ 474.40
32			3" Dia Water Main	LF	1210	10%	1331	0.75	70.00	\$ 52.50	\$ 20.00	\$ 72.50	\$ 96,466.40
33			Excavation	CY	336.00	10%	369.60	1.100	\$ 50.00	\$ 55.00	\$ -	\$ 55.00	\$ 20,328.17
34			Backfill	CY	327.21	10%	359.93	0.785	\$ 50.00	\$ 39.25	\$ -	\$ 39.25	\$ 14,127.13
35			8" Dia PVC Pipe	LF	1193	10%	1312	1.15	70.00	\$ 80.50	\$ 40.00	\$ 120.50	\$ 158,132.15
36			Excavation	CY	1922	10%	2114	1.100	\$ 50.00	\$ 55.00	\$ -	\$ 55.00	\$ 116,284.36
37			Backfill	CY	1907	10%	2097	0.785	\$ 50.00	\$ 39.25	\$ -	\$ 39.25	\$ 82,318.17
PIP CONNECTION													
38			Water Connection	EA	2	0%	2	8.00	75.00	\$ 600.00	\$ 1,500.00	\$ 2,100.00	\$ 4,200.00
39			3" PVC Pipe Connection	EA	3	0%	3	5.00	75.00	\$ 375.00	\$ 1,000.00	\$ 1,375.00	\$ 4,125.00
40			4" Water Main Loop	EA	2	0%	2	3.00	75.00	\$ 225.00	\$ 750.00	\$ 975.00	\$ 1,950.00
41			Connection To Existing 6" Water Main Stub Out	EA	1	0%	1	12.00	75.00	\$ 900.00	\$ 1,250.00	\$ 2,150.00	\$ 2,150.00
42			Connect To Existing 8" Stub out	EA	1	0%	1	12.00	75.00	\$ 900.00	\$ 1,250.00	\$ 2,150.00	\$ 2,150.00
VALVE													
43			3" Gate Valve	EA	3	0%	3	2.50	75.00	\$ 187.50	\$ 1,150.00	\$ 1,337.50	\$ 4,012.50
44			4" Gate Valve	EA	4	0%	4	2.50	75.00	\$ 187.50	\$ 1,450.00	\$ 1,637.50	\$ 6,550.00
45			6" Gate Valves	EA	1	0%	1	2.50	75.00	\$ 187.50	\$ 1,850.00	\$ 2,037.50	\$ 2,037.50
TEE & STATION													
46			Lift station	EA	1	0%	1	520.00	100.00	\$ 52,000.00	\$ 25,000.00	\$ 77,000.00	\$ 77,000.00
47			6" x 4" TEE	EA	1	0%	1	2.00	75.00	\$ 150.00	\$ 195.00	\$ 345.00	\$ 345.00
INLET													
48			3" PVC Inlet	EA	2	0%	2	1.50	75.00	\$ 112.50	\$ 60.00	\$ 172.50	\$ 345.00
PRE CAST STRUCTURAL													
MANE HOLE													
49			Pre Cast Sanitary Manhole	EA	6	0%	6	6.00	65.00	\$ 390.00	\$ 4,000.00	\$ 4,390.00	\$ 26,340.00
50			6" Crushed Stone	CY	3	10%	3	0.45	55.00	\$ 24.75	\$ 60.00	\$ 84.75	\$ 292.87
51			Excavation	CY	101	10%	111	1.100	\$ 50.00	\$ 55.00	\$ -	\$ 55.00	\$ 6,082.12
52			Backfill	CY	31	10%	34	0.785	\$ 50.00	\$ 39.25	\$ -	\$ 39.25	\$ 1,326.24
53			8" Sanitary Sewer	EA	2	0%	2	6.00	85.00	\$ 510.00	\$ 720.00	\$ 1,230.00	\$ 2,460.00
												Note We Have Assumed Depth For Pipe Excavation 5' Please Check & Verify.	
												SUBTOTAL	\$ 814,300

DETAILED BREAKDOWN OF ITEMS

Prepared for:

Project ID:

Project ID:	
Scope:	Site

Date: 17-Jul-24

SR #	Drawing #	Detail #	DESCRIPTION	UNIT	QUANTITY	WASTAGE	QUANTITY W/ WASTAGE	UNIT MAN/ HOUR	HOURLY WAGE	LABOR COST	MAT. COST	UNIT COST	SUB COST
PROJECTED COST													\$2,027,928
OVERHEAD AND PROFIT												15%	\$304,189
INSURANCE												3%	\$60,838
CONTINGENCY												5%	\$101,396
TAX												8%	\$162,234
SUGGESTED BID													\$2,656,586

Notes:

1. Online sources are used for pricing.
2. Prices can vary depending upon field conditions.